



CITY OF ST PETERS  
636.477.6600  
[bids@stpetersmo.net](mailto:bids@stpetersmo.net)

November 3, 2017

**Addendum 1 - Bid 18-107; Jungermann Road Bridge Replacements, Federal Project No. BRM 5640 (613)**

To all Contract Bidders of Record,

This Addendum, consisting of three (3) pages, is issued to answer questions received, modify, explain, or correct the original contract documents as noted below, and is hereby made a part of the contract documents.

1. Please provide clarification for the following:  
Item #13 Temp Signal Modification  
There are 4 ea Units shown on the proposal but in the Technical Description of Proposal Items, it states measurement and payment will be per each complete and operational signalized intersection. Should the proposal be changed to 1 ea Units?
    - Both the signal at Country Creek Drive and Barkwood Trails Drive will be modified as shown in the plans for each of the two construction phases. Payment will be made per signal for modifications made for each phase.
  2. Item #53 Conduit System on Structure  
Plan Sheet #38 calls for ¾" Galv Rigid Steel Conduit to be used for the underpass lighting along with Cast Junction Boxes can this be installed using PVC Conduit and Junction Boxes since this is all going to be encased in the bridge concrete?
    - No.
  3. Item #60 Luminaire  
Can you possibly provide a manufacturer of the Luminaires which you want to be installed under the bridge for the walkway. All that I can find is the description of the luminaire but there is no manufacturer provided.
    - Any manufacturer that meets all specifications will be accepted.
  4. Item #64 150 Watt 120 Volt LED Luminaire Please provide Manufacturer of Luminaire if possible which St. Peters uses.
    - Any manufacturer that meets all specifications will be accepted. The original specification was incorrect in that it should have specified a 250 Watt LED Luminaire. Below is the updated technical description for Line Item #64.
64. 250 WATT LED LUMINAIRE – This work shall consist of furnishing and installing 250 Watt LED Luminaires as indicated on the plans and this document in accordance with Missouri Standard Specifications for Highway Construction (2016). Work shall consist of all labor, materials, and equipment required for the complete and operational 250 Watt Luminaires. Measurement and payment will be made per each accepted luminaire at the contract unit price. There will be no direct payment for luminaire tenon mount or bracket arms required for this contract.

**Special Instructions Update:**

- A. Important: Label the lower left corner of your sealed submittal package with the bid number and name
- B. Submit one original and one copy of your bid proposal
- C. Include with Proposal Sections:
  - **C – Proposal**
  - **D – Bid Bond**
  - **O – Addendum**
  - **S – Affidavit of Enrollment in Federal Work Authorization (with E-Verify)**
  - **V – Disadvantaged Business Enterprise Contact Provisions**
  - **W – Buy America Certification**

Thank you,  
City of St. Peters  
[bids@stpetersmo.net](mailto:bids@stpetersmo.net)

**Section – O - Addenda**

ADDENDUM ACKNOWLEDGEMENT: The undersigned states that the all addenda's have been received, acknowledged and incorporated into their proposal, prior to submittal. Complete and return with this proposal.

Addendum #1 – November 3, 2017

Addendum  
Received By: \_\_\_\_\_

Signed: \_\_\_\_\_  
(Signature of Authorized Representative)

Name \_\_\_\_\_  
(Printed Name of Authorized Representative)

Title \_\_\_\_\_

Date \_\_\_\_\_