



**IFB #17-001
CMAQ-7304(605)
Flashing Yellow Arrow Signalization Improvements and
Accessible Pedestrian Signalization Improvements**

ADDENDUM 3

Addendum issued February 2, 2017

The deadline for submitting bids has been extended to Wednesday February 8th, 2017 at 2 pm.

The following clarifications are hereby incorporated into the Invitation for Bids:

- 1) The specifications have a section JSP 7, Upgrade Existing Detection Devices, at Intersection of Wentzville Parkway and Bridlespur Drive. The Basis of Payment is per each, however there is not a line item on the bid form for this item. Therefore the cost of this JSP cannot be included in the submitted bids at this time.

City Response: The base bid for the Flashing Yellow Arrow Portion is hereby amended to include the Upgrade Existing Detection Devices for Wentzville Parkway and Bridlespur Drive as part of the subtotal of Signal & Lighting Items (Federally Participating); revised Bid Form attached.

As further clarification, Add Alternate 1 is for Upgrade Existing Detection Devices at the intersection Wentzville Parkway & Luetkenhaus Boulevard as indicated in JSP-9. It should be noted that the existing detection device at Wentzville Parkway & Luetkenhaus Boulevard is inductance loops and not video detection.

In response to the above clarification, the deadline for bids has been extended to Wednesday February 8th, 2017 at 2 pm.

All other Terms and Conditions as applicable to this Invitation for Bid shall remain as stated.

This addendum forms a part of the contract documents and modifies the original bidding documents dated January 6, 2017. Contractor shall acknowledge receipt of this addendum in the space provided on the Pricing Form (Exhibit A). Failure to do so may subject bidder to disqualification.

BID FORM
REVISED PER ADDENDUM 3
City of Wentzville
City Hall
310 West Pearce Boulevard
Wentzville, Missouri 63385

In accordance with the invitation to bid for the Flashing Yellow Arrow Signalization Improvements Project and the Accessible Pedestrian Signalization Improvements Project for the City of Wentzville subject to the conditions and requirements of the Agreement, and the specifications, which so far as they relate to the Proposal are made a part of it, the undersigned herewith proposes to provide and perform such work for the sum below: (Any items not listed in pay items shall be considered incidental to construction)

BID TABULATION - FYA SIGNALIZATION IMPROVEMENTS PROJECT SUMMARY (FEDERAL PARTICIPATING)					
ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
616-10.05	CONSTRUCTION SIGNS	SF	567		
616-10.25	CHANNELIZERS (TRIM-LINE)	EA	209		
616-10.34	DIRECTIONAL INDICATOR BARRICADE WITH LIGHT	EA	77		
616-10.40	FLASHING ARROW PANEL	EA	11		
618-10.00	MOBILIZATION	LS	11		
SUBTOTAL OF ROADWAY ITEMS (FEDERALLY PARTICIPATING):					
902-02.11	SIGNAL HEAD, TYPE 1S (LED)	EA	34		
902-05.13	SIGNAL HEAD, TYPE 3S (LED)	EA	2		
902-05.14	SIGNAL HEAD, TYPE 4B (LED)	EA	28		
902-99.01	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	LS	10		
902-99.02A	MODIFY EXISTING SIGNAL CABINET	EA	10		
902-99.02B	UPGRADE EXISTING SIGNAL CABINET	EA	1		
902-99.02C	RELOCATE EXISTING TRAFFIC SIGNAL HEAD	EA	1		
902-99.02D	UPGRADE EXISTING DETECTION DEVICES (JSP-7, FYA)	EA	1		
902-99.02E	MMU	EA	11		
903-50.65	SIGNAL SIGN, TYPE SHR2L-3 (FOR FYA & R10-3E SIGNS)	SF	225.2		
SUBTOTAL OF SIGNAL & LIGHTING ITEMS (FEDERALLY PARTICIPATING):					
FYA PROJECT TOTAL (FEDERAL PARTICIPATING):					

**BID TABULATION – ACCESSIBLE PEDESTRIAN SIGNALIZATION
IMPROVEMENTS PROJECT SUMMARY (NON-FEDERAL PARTICIPATING)**

ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
202-20.10	REMOVAL OF IMPROVEMENTS	LS	10		
608-10.10	CONCRETE MEDIAN	SY	167.1		
608-10.12	TRUNCATED DOMES	SF	249		
608-60.04	CONCRETE SIDEWALK, 4 IN.	SY.	269.8		
617-99.01	TRAFFIC CONTROL	LS	13		
618-10.00	MOBILIZATION	LS	13		
SUBTOTAL OF ROADWAY ITEMS (NON-FEDERAL PARTICIPATING):					
902-27.08	POST, SIGNAL, 8 FT. - BLACK	EA	1		
902-49.20	DETECTOR, PUSHBUTTON (WITH APS FEATURE)	EA	54		
902-52.00	CONDUIT, 2 IN., IN TRENCH	LF	267		
902-53.00	CONDUIT, 3 IN., IN TRENCH	LF	75		
902-83.10	CABLE, 16 AWG 5 CONDUCTOR	LF	710		
902-83.11	CABLE, 16 AWG 7 CONDUCTOR	LF	170		
902-91.00	BASE, CONCRETE	CY	6.0		
902-99.02A	STANCHION POST (SINGLE PUSHBUTTON) - BLACK	EA	21		
902-99.02B	STANCHION POST (DOUBLE PUSHBUTTON) - BLACK	EA	3		
902-99.02C	RELOCATE SIGNAL POST	EA	6		
902-99.02D	DRILL PULLBOX (1 OPENING)	EA	30		
902-99.02E	UNINTERRUPTIBLE POWER SUPPLY	EA	11		
902-99.02F	EXTENSION POST, 1 FT - BLACK.	EA	12		
902-99.03	APS PUSHBUTTON CABLES	LF	9300		
903-50.65	SIGNAL SIGN, TYPE SHR2L-3 (FOR FYA & R10-3E SIGNS)	SF	50.8		
SUBTOTAL OF SIGNAL & LIGHTING ITEMS (NON-FEDERAL PARTICIPATING):					
ADA PROJECT TOTAL (NON-FEDERAL PARTICIPATING):					

TOTAL BASE BID - COMBINED TOTAL OF FYA & ADA PROJECTS (WRITTEN):	
---	--

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	PRICE/UNIT	COST
ADD ALTERNATES					
ALTERNATE 1 – FYA MISCELLANEOUS IMPROVEMENTS (FEDERAL PARTICIPATING)					
902-99.02D	UPGRADE EXISTING DETECTION DEVICES (JSP-9, FYA)	EA	1		
ALTERNATE 1 -TOTAL (FEDERAL PARTICIPATNG):					
ALTERNATE 2 – ADA MISCELLANEOUS IMPROVEMENTS (NON-FEDERAL PARTICIPATING)					
902-99.02F	UNINTERRUPTIBLE POWER SUPPLY (JSP-12, ADA)	EA	2		
ALTERNATE 2 TOTAL (FEDERAL PARTICIPATNG):					

The priority of the add alternates which will be considered are listed below. The award will be based on the lowest responsible bid for whichever combination of base bid plus add alternates is awarded.

- 1. Combined Total of FYA & ADA Projects Base Bid + Alternate 1 + Alternate 2 (\$):
- 2. Combined Total of FYA & ADA Projects Base Bid + Alternate 1 (\$):
- 3. Combined Total of FYA & ADA Projects Base Bid Base Bid (\$):

Contractor's Company Name

Mailing Address:

Contractor's Authorized Rep. (SIGNATURE)

Date:

Authorized Representative's Title

Phone Number:

Indicate below all Addenda received on which the above bid is based;

- Addendum No. ____ Dated: ____
- Addendum No. ____ Dated: ____
- Addendum No. ____ Dated: ____
- Addendum No. ____ Dated: ____