



Kevin Keith, Director

---

February 14, 2011

**Addendum No. 001**  
**IFB 9-110225**

MISSOURI DEPARTMENT OF TRANSPORTATION: DISTRICT – 9 RADIO TOWERS, TAUM SAUK

BID OPENING DATE AND TIME: FEBRUARY 25, 2011 AT 3:00 P.M. LOCAL TIME.

ATTACHMENTS: Anchor design information for existing towers.

CHANGE:

Time of Completion for the tower is changed to “complete the work and billing within 40 working days from the date specified”.

DELETE:

Section 01500 - Construction Facilities and Temporary Control Requirements, Paragraph 1.3, Telephone Service Requirements.

Section 01500 - Construction Facilities and Temporary Control Requirements, Paragraph 1.4, Facsimile Service Requirements.

Section 01500 - Construction Facilities and Temporary Control Requirements, Paragraph 1.14, Field Offices and Sheds Requirements.

CLARIFY:

- All concrete shall have a minimum compressive strength at twenty-eight (28) days of 3,000 P.S.I.
- Perimeter fencing for the towers and buildings may remain in place.
- All fencing shall meet the grounding requirements of the specifications.
- All existing guy wires, anchors, and guy wire protective fencing shall be removed. Each anchor needs to be removed from the ground in its entirety. No portion of the anchor can be cut off at ground level.
- The existing towers need to stay functional until the new ones are functional.

**END SECTION**