



## **SECTION 728**

### **RELAID PIPE**

**728.1 Description.** This work shall consist of removing existing pipe or pipe-arch culverts and cleaning and relaying suitable sections.

**728.2 Construction Requirements.** All work done in relaying pipe or pipe-arch culverts shall be performed in accordance with the requirements for placing new pipe. Pipe may be relaid at the same location or at a new location as shown on the plans or as specified by the engineer. Pipe shall be carefully removed and any cutting that may be required to obtain necessary lengths for relaying shall be done by the contractor.

#### **728.3 Method of Measurement.**

**728.3.1** Measurement will be made to the nearest linear foot (0.5 m) along the geometrical center of the relaid pipe.

**728.3.2** Measurement of Class 3 Excavation for relaying the pipe will be made in accordance with [Sec 206](#).

#### **728.4 Basis of Payment.**

**728.4.1** The accepted quantities of relaid pipe or pipe-arch culvert actually relaid, regardless of size, will be paid for at the contract unit price. No direct payment will be made for excavation for removing the pipe, hauling, cleaning, cutting, joining, furnishing new coupling bands required, backfilling, or disposing of old pipe not relaid.

**728.4.2** Payment for Class 3 Excavation for relaying the pipe will be made at the contract unit price per cubic yard (cubic meter) under roadway items.