

STATE OF MISSOURI
HIGHWAYS and TRANSPORTATION
COMMISSION

JEFFERSON CITY, MISSOURI

CONSTRUCTING OR IMPROVING
CONTRACT I.D. 161216-D01

THIS JOB SHALL BE CONSTRUCTED UNDER
FEDERAL PROJECT NUMBER(S) : FAF-50-3(100)
FAF-50-3(101)

Job J5P3056 Route 50 COLE County
Job J5P3127 Route 50 COLE County.

BIDDER CHECKLIST
FINAL CHECKLIST BEFORE SUBMITTING BID

1. Submit completed Contractor Questionnaire and/or Contractor Prequalification Questionnaire with attachments not later than seven (7) days prior to the date and hour of the bid opening. See Secs 101-103 of the Missouri Standard Specifications for Highway Construction, and Rule 7 CSR 10-15.010, "Prequalifications to Bid of Certain Contractors". Questionnaire and Contact information are provided on MoDOT's website.
2. All bids shall be submitted electronically using "Bid Express Secure Internet Bidding" at www.bidx.com. Any paper bid submitted will be considered irregular per section 102.8 of the Missouri Standard Specifications for Highway Construction.
3. Please read all items in the bidding document carefully. The EBS files from MoDOT's website may be used for the itemized bid.
4. If submitted in the name of a firm or corporation, the legal name of the firm or corporation should appear in the space designated, and be signed for by one or more persons legally qualified to execute papers in the name of said firm or corporation.
5. The bidder shall submit a Bid Guaranty meeting the requirements of Sec 102 of the Missouri Standard Specifications for Highway Construction. If submitting a project specific or annual bid bond, bidders must use the MoDOT provided bid bond forms. The project specific bond form is included in the request for bid. The project specific and annual bid bond forms are also available on MoDOT's website. Annual bid bonds shall be executed by June 15th of each year.
6. Submit the Subcontractor Disclosure Form in accordance with the bidding documents. For bids of more than \$2,000,000, each bidder shall submit with each bid a disclosure of the subcontracts that have a subcontract value that is equal or greater than twenty percent of the total project bid or subcontracts that are greater than or equal to \$2,000,000. If that information is not available at the time of bid the bidder shall submit the "Subcontractor Disclosure Form" pages with MoDOT on or before 4:00 p.m. of the third business day after the bid opening date.
7. Submit the DBE Identification Submittal in accordance with the bidding documents for Federal Projects Only.
8. Alternate Pavements; to exercise this option, separate pay items, descriptions and quantities are included in the itemized proposal for each of the two alternates. The bidder shall bid only one of the two alternates and leave the contract unit price column blank for any pay item listed for the other alternate.

- 9. When submitting a bid, your bid will still come through with "red" folders. You should make sure that it is not the Schedule of Items folder or the Signature and Identity of Bidder folder. Click on the yellow checkmark (Check Bid) at the top and it will list any errors in the bid. To view itemized folders, click the Tree View. This will show the status of the individual folders.

Below is a list of common mistakes made by bidders leading to non-responsive bids. Please refer to the Standard Specifications for the appropriate procedures for completing and submitting a bid.

- a) Submitting a paper bid for a project
- b) Using a different bid bond form than the one provided
- c) Improper use of the Maximum Monetary Value Award Provision
-only used if bidding more than one project and should be in only one bid proposal
- d) Not obtaining a digital ID in advance of the letting
(obtaining a digital ID may take 5 business days)

All questions concerning the bid document preparation shall be directed to the Central Office - Design Division at (573) 751-2876. Project specific questions shall be directed to the project contact listed in the Job Special Provisions.

TABLE OF CONTENTS

Notice to Contractors

Proposed Work..... item (1)

Compliance With Contract Provisions..... item (2)

Period of Performance..... item (3)

Liquidated Damages..... item (4)

Acceptance of Provision for Price Adjustment for Fuel..... item (5a)

Acceptance of Provision for Asphalt Cement Price Index.... item (5b)

Max. Monetary Value of Awards Accepted this Bid Opening... item (6)

Combination Bids..... item (7)

Bid Guaranty..... item (8)

Certification for Federal Jobs..... item (9a)

Certification for State Jobs..... item (9b)

Antidiscrimination..... item (10)

Preference to Missouri Firms in Awarding of Contracts..... item (11)

Signature and Identity of Bidder..... item (12)

Trainees..... item (13)

Bidder's Certification for DBE Program and Contract Goal.. item (14)

Itemized Bid..... item (15)

Bid Bond*

Subcontractor Disclosure Form*

DBE Identification Submittal (Applies to Federal Projects Only) *

*These forms are also available on MoDOT's Website, www.modot.org under General Information on the Bid Opening Info page of the Contractor Resources site.

NOTICE TO CONTRACTORS

Electronic bids submitted through the Bid Express website for the proposed work will be received by the Missouri Highways and Transportation Commission until 11:00 o'clock a.m. (prevailing local time) on 12-16-16.

Bid bonds will be received at the office of the Secretary to the Commission in the Missouri Department of Transportation Central Office Building, 105 West Capitol Avenue, Jefferson City, Missouri; delivered by US Mail should be mailed to: Missouri Highways and Transportation Commission, Attention: State Design Engineer/Bid Bond, P.O. Box 270, Jefferson City, MO 65102 or delivered by parcel delivery services, (such as UPS, Fed Ex, DHL, etc.) should be shipped to Missouri Highways and Transportation Commission, Attention: State Design Engineer/Bid Bond, 105 West Capitol Avenue, Jefferson City, MO 65102.

(1) PROPOSED WORK: The proposed work, hereinafter called the work, includes:

****(1): Job J5P3056 Route 50 COLE County. Safety improvements from west of Moreau River near Jefferson City to Lisletown Road, the total length of improvement being 4.493 miles.****(2): Job J5P3127 Route 50 COLE County. Resurface from the Moreau River near Jefferson City to Osage County Line, the total length of improvement being 9.934 miles.

Combination bids will be Required on the Jobs listed above.

(2) COMPLIANCE WITH CONTRACT PROVISIONS: The bidder, having examined and being familiar with the local conditions affecting the work, and with the contract, contract documents, including the Missouri Highways and Transportation Commission's "Missouri Standard Specifications for Highway Construction, 2016," and "Missouri Standard Plans for Highway Construction, 2016", their revisions, and the request for bid, including appendices, the special provisions and plans, hereby proposes to furnish all labor, materials, equipment, services, etc., required for the performance and completion of the work. All references are to the Missouri Standard Specifications for Highway Construction, as revised, unless otherwise noted. All questions concerning the bid document preparation shall be directed to the Central Office - Design Division at (573) 751-2876.

(3) PERIOD OF PERFORMANCE: If the bid is accepted, the bidder shall continuously and diligently prosecute the work in such order and manner as will ensure the completion of the work within the time specified in the Job Special Provisions in accordance with Sec 108.

(4) LIQUIDATED DAMAGES: The bidder agrees that, should the bidder fail to complete the work in the time specified or such additional time as may be allowed by the engineer under the contract, the amount of liquidated damages as specified in the Job Special Provisions to be recovered in accordance with Sec 108.

(5a) ACCEPTANCE OF PROVISION FOR PRICE ADJUSTMENT FOR FUEL: Bidders have the option to accept the provision for Price Adjustment for Fuel in accordance with Sec. 109.14. The bidder must select "Yes" for those items of work in which they choose to accept the provision. No price adjustments will be made, due to fuel price changes, for bidders who do not accept this provision. This provision does not apply to Seal Coat.

EXCAVATION PRODUCTION
ASPHALT PAVING PRODUCTION AND HAULING
CONCRETE PAVING PRODUCTION AND HAULING
AGGREGATE BASE HAULING

(5b) ACCEPTANCE FOR PROVISION FOR ASPHALT CEMENT PRICE INDEX, SEAL COAT PRICE INDEX, UNDERSEAL PRICE INDEX, OR POLYMER MODIFIED EMULSION MEMBRANE PRICE INDEX:

Bidders have the option to accept the provision for Asphalt Cement Price Index, Seal Coat Price Index, Underseal Price Index, and/or Polymer Modified Emulsion Membrane Price Index in accordance with the General Provisions. The bidder must mark each box below if they choose to accept the provision. No price adjustments will be made, due to asphalt price changes, for bidders who do not accept this provision.

ASPHALT CEMENT
SEAL COAT
UNDERSEAL
POLYMER MODIFIED EMULSION MEMBRANE

(6) MAXIMUM MONETARY VALUE OF AWARDS ACCEPTED THIS BID OPENING: Bidders have the option to specify the maximum monetary value of awards that they will accept for the total of all bids they have submitted in the bid opening, Sec 102.7.2. If the bidder is submitting only one bid, or if the bidder does not want to specify a maximum monetary value for submitted bids, this section should not be completed. If a submitted bid upon correction exceeds the indicated maximum monetary amount, the bid may be

declared non-responsive. If a bidder's submitted bids show different values for the maximum monetary value, the lowest value will govern.

MAXIMUM MONETARY VALUE OF AWARDS ACCEPTED THIS BID OPENING

(Note: this amount should be entered in only one of the bids for this bid opening)

(7) COMBINATION BIDS: (Applies only if combination bids are specified. See cover and/or notice to contractor(s).) Combination bids will be in accordance with Sec 102.12. By selecting "ALL OR NONE", the bidder desires to combine all projects in accordance with Sec 102.12.2.1.

(8) BID GUARANTY: The bidder shall submit a Bid Guaranty meeting the requirements of Section 102 of the Missouri Standard Specifications for Highway Construction. MoDOT's bid bond and annual bid bond forms are available on MoDOT's website.

(9a) CERTIFICATIONS FOR FEDERAL JOBS: (Applies to Federal Projects only.) By signing and submitting this bid, the bidder makes the certifications appearing in Sec. 102.18.1 (regarding affirmative action and equal opportunity), Sec. 102.18.2 (regarding disbarment, eligibility, indictments, convictions, or civil judgments), Sec.102.18.3 (regarding anti-collusion), and Sec.102.18.4 (regarding lobbying activities). Any necessary documentation is to accompany the bid submission, as required by these sections. As provided in Sec.108.13, the Commission may terminate the contract for acts of misconduct, which includes but is not limited to fraud, dishonesty, and material misrepresentation or omission of fact within the bid submission.

(9b) CERTIFICATIONS FOR STATE JOBS: (Applies to State Projects only.) By signing and submitting this bid, the bidder makes the certifications appearing in Sec. 102.18.2 (regarding diseligibility, indictments, convictions, or civil judgments), Sec. 102.18.3 (regarding anti-collusion), and Sec. 102.18.5 (regarding Missouri Domestic Products Procurement Act). Any necessary documentation is to accompany the bid submission, as required by these sections. As provided in Sec. 108.13, the Commission may terminate the contract for acts of misconduct, which includes but is not limited to fraud, dishonesty, and material misrepresentation or omission of fact within the bid submission.

Any necessary documentation is to accompany the bid submission, as required by these sections. As provided in Sec. 108.13, the Commission may terminate the contract for acts of misconduct, which includes but is not limited to fraud, dishonesty, and material misrepresentation or omission of fact within the bid submission.

By selecting "No" the bidder REFUSES to make one or more certifications for the above items 9a or 9b. The bidder shall provide a statement of explanation for the refusal in the space below or by fax to the Design Division @ Fax no. 573-522-2281.

(10) ANTIDISCRIMINATION: The Commission hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, businesses owned and controlled by socially and economically disadvantaged individuals will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, creed, sex, age, ancestry, or national origin in consideration for an award.

(11) PREFERENCE TO MISSOURI FIRMS IN AWARDING OF CONTRACTS: (Applies to State Projects only.) The bidder's attention is directed to Section 34.355 RSMo Supp 2000, et seq, which requires that preference be given in awarding contracts to firms, corporations, or individuals doing business as Missouri firms, corporations, or individuals, or which maintain Missouri offices or places of business, when the quality of performance promised is equal, or better, and the price quoted is the same, or less.

The law also requires that a contractor or bidder domiciled outside the state of Missouri shall be required, in order to be the successful bidder, to submit a bid which is the same percent less than the lowest bid submitted by a responsible contractor or bidder domiciled in Missouri as would be required for the Missouri domiciled contractor or bidder to succeed over the bidding contractor or bidder domiciled outside Missouri in a like contract or bid being let in his state. A contractor or bidder domiciled outside Missouri domiciliary shall also be required to submit an audited financial statement as would

be required of a Missouri domiciled contractor or bidder on a like contract or bid being let in the domiciliary state of that contractor or bidder.

For firms, corporations or individuals domiciled outside the state of Missouri, it is requested they submit the following information:

List the state of domicile

List address of all Missouri offices or places of business

I acknowledge that I have read, understand and completed the above Contract Provisions.

(12) Signature and Identity of Bidder

BY SUBMITTING THIS BID ELECTRONICALLY, I HEREBY ACKNOWLEDGE THAT ALL REQUIREMENTS INCLUDED IN THE HARD COPY REQUEST FOR BID, AND AMENDMENTS ARE A PART OF THIS BID AND CONTRACT.

*** AN ELECTRONIC PROPOSAL SUBMITTED AND SIGNED WITH A DIGITAL ID, UNDER THE PROVISION OF THE MISSOURI DEPARTMENT OF TRANSPORTATION, WILL BE CONSIDERED VALID AND BINDING. ***

THE BIDDER CERTIFIES THAT THE BIDDER AND ITS OFFICIALS, AGENTS, AND EMPLOYEES HAVE NEITHER DIRECTLY NOR INDIRECTLY ENTERED INTO ANY AGREEMENT, PARTICIPATED IN ANY COLLUSION, OR OTHERWISE TAKEN ANY ACTION IN RESTRAINT OF FREE COMPETITIVE BIDDING IN CONNECTION WITH THIS BID, AND THAT THE BIDDER INTENDS TO PERFORM THE WORK WITH ITS OWN BONAFIDE EMPLOYEES AND SUBCONTRACTORS, AND DID NOT BID FOR THE BENEFIT OF ANOTHER CONTRACTOR.

THE BIDDER CERTIFIES THAT THE BIDDER'S COMPANY KNOWINGLY EMPLOYS ONLY INDIVIDUALS WHO ARE AUTHORIZED TO WORK IN THE UNITED STATES IN ACCORDANCE WITH THE APPLICABLE FEDERAL AND STATE LAWS AND ALL PROVISIONS OF MISSOURI EXECUTIVE ORDER NO. 07-13 FOR CONTRACTS WITH THE MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION, ACTING THROUGH THE MISSOURI DEPARTMENT OF TRANSPORTATION.

THE BIDDER ACKNOWLEDGES THAT THIS IS AN UNSWORN DECLARATION, EXECUTED UNDER PENALTY OF PERJURY UNDER THE LAWS OF THE UNITED STATES AND/OR FALSE DECLARATION UNDER THE LAWS OF MISSOURI, AND ANY OTHER APPLICABLE STATE OR FEDERAL LAWS. THE FAILURE TO PROVIDE THIS CERTIFICATION IN THIS BID MAY MAKE THIS BID NON-RESPONSIVE, AND CAUSE IT TO BE REJECTED.

Select "No" ONLY if the bidder REFUSES to make this certification. The bidder may provide an explanation for the refusal with this submittal in the space below or by fax to the Design Division @ fax no. 573-522-2281.

USE OF ANOTHER PERSON'S DIGITAL ID IN THIS BIDDING PROCESS VIOLATES THE LAWS OF MISSOURI.

I acknowledge that I have read, understand and completed the above Electronic Bid Submission Certification.

DBE CERTIFICATION

(13) Trainees: (Applies to Federal Projects only) The number of trainee hours provided under this contract will be 0 slots at 1000 hours per slot or 0 hours.

(14) Bidder's Certification for DBE Program and Contract Goal (Applies to Federal Projects Only.)

(A) DBE Contract Goal: By submitting this bid, the bidder certifies that the bidder is familiar with the DBE Program Requirements in the General Provisions. The contract goal for the amount of work to be awarded is 10.00% of the total federal project price. The bidder shall also complete the DBE Identification Submittal form in accordance with the General Provisions. This form is available on MoDOT's Website, www.modot.org under General Information on the Bid Opening Info page of the Contractor Resources site.

(B) DBE Participation: The bidder certifies that it will utilize DBE's as follows: % OF TOTAL FEDERAL CONTRACT

NOTE: Bidder must fill in the above box. If no percentage is specified, the bidder certifies that it agrees to and will comply with the contract goal. If a percentage below the contract goal is specified, then the bidder must submit complete documentation of good faith efforts to met the DBE contract goal, immediately below.

The DBE Identification Submittal form will be submitted via

(C) Certification of Good Faith Efforts to Obtain DBE Participation: By submitting its signed bid, the bidder certifies under penalty of perjury and other provisions of law, that the bidder took each of the following steps to try to obtain sufficient DBE participation to achieve the Commission's proposed DBE Contract Goal:

(15) ITEMIZED BID: The bidder should complete the following section in accordance with Sec 102.7. The bidder proposes to furnish all labor, materials, equipment, services, etc. required for the performance and completion of the work, as follows:

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price Dollars Cts	Bid Amount Dollars Ct
Section 0001 Roadway Items - J5P3056				
Alt Group				
0010	2022010 REMOVAL OF IMPROVEMENTS	LUMP	LUMP	
0020	2031000 CLASS A EXCAVATION	202.000 CUYD		
0030	2035000 UNCLASSIFIED EXCAVATION	2,675.000 CUYD		
0040	2036000 COMPACTING EMBANKMENT	509.000 CUYD		
0050	2063000 CLASS 3 EXCAVATION	26.000 CUYD		
0060	2072000 LINEAR GRADING CLASS 2	24.600 STA		
0070	3040506 TYPE 5 AGGREGATE FOR BASE (6 IN. THICK)	10,013.000 SQYD		

State of MISSOURI
Dept of Transportation
Schedule of Items

Contract ID: 161216-D01

Letting Date: 12-16-16

Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0080	4019905 MISC. MODIFIED TYPE A2 SHOULDER	2,723.300 SQYD				
0090	4039905 MISC. 10.75" OPTIONAL PAVEMENT	1,895.800 SQYD				
0100	4039905 MISC. 10.25" OPTIONAL PAVEMENT	4,721.600 SQYD				
0110	5029905 MISC. MODIFIED TYPE A3 SHOULDER	1,348.100 SQYD				
0120	6161005 CONSTRUCTION SIGNS	185.000 SQFT				
0130	6161009 FLAG ASSEMBLY	4.000 EA				
0140	6161025 CHANNELIZER (TRIM LINE)	25.000 EA				
0150	6161031 TYPE III MOVEABLE BARRICADE WITH LIGHT	16.000 EA				

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01

Letting Date: 12-16-16

Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0160	6161099 CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	4.000 EA				
0170	6181000 MOBILIZATION	LUMP	LUMP			
0180	6189902 MISC. ADDITIONAL MOBILIZATION FOR SEEDING	4.000 EA	600.00000		2,400.00	
0190	6191000 PAVEMENT EDGE TREATMENT	5,650.000 LF				
0200	6205425 PREFORMED SHORT TERM MARKING TAPE 24 IN., WHITE	24.000 LF				
0210	6206000C 4 IN. WHITE WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	5,418.000 LF				

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0220	6206001C 4 IN. YELLOW WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,133.000 LF				
0230	6274000 CONTRACTOR FURNISHED SURVEYING AND STAKING	LUMP	LUMP			
0240	7250318A 18 IN. PIPE GROUP B	82.000 LF				
0250	7320018A 18 IN. OR ALLOWED SUBSTITUTE GROUP B FLARED END SECTION	2.000 EA				
0260	8051000A SEEDING - COOL SEASON MIXTURES	2.500 ACRE				
0270	8061003 SEDIMENT TRAP EXCAVATION	60.000 CUYD				
0280	8061005 ROCK DITCH CHECK	604.000 LF				

State of MISSOURI
Dept of Transportation
Schedule of Items

Contract ID: 161216-D01
Letting Date: 12-16-16
Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0290	8061006 ALTERNATE DITCH CHECK	343.000 LF				
0300	8061016 SEDIMENT REMOVAL	75.000 CUYD				
0310	8061017 TEMPORARY SEEDING AND MULCHING	0.300 ACRE				
0320	8061019 SILT FENCE	2,800.000 LF				
0330	8069928 MISC. WATER POLLUTION CONTROL MANAGER	67.000 WK				
	Section 0001 Total					2,400.00

Section 0002 Signing Items - J5P3056

Alt Group

0340	9031252 7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED WHITE	29.000 EA				
0350	9031253A 7 FT. CHANNEL POST DELINEATOR, DOUBLE STACKED YELLOW	21.000 EA				

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
	Section 0002 Total					0.00

Section 0003 Roadway Items - J5P3127

Alt Group

0360	2022010 REMOVAL OF IMPROVEMENTS	LUMP		LUMP		
0370	2151000A SHAPING SLOPES, CLASS I	100F	164.000			
0380	2152000A SHAPING SLOPES, CLASS II	100F	516.000			
0390	2153000 SHAPING SLOPES, CLASS III	100F	13.000			
0400	3049905 MISC. FURNISHING AND PLACING CLEAN AGGREGATE - 2" THICK	SQYD	85.000			
0410	3049910 MISC. TYPE 1 AGGREGATE FOR BASE (2IN. THICK)	TONS	891.000			

State of MISSOURI
Dept of Transportation
Schedule of Items

Contract ID: 161216-D01
Letting Date: 12-16-16
Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0420	4011209 BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	8,982.500 TONS				
0430	4030103 ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125C MIX)	16,724.100 TONS				
0440	4071005 TACK COAT	6,650.000 GAL				
0450	4079912 MISC. POLYMER MODIFIED EMULSION MEMBRANE	31,250.000 GAL				
0460	4139905 MISC. SURFACE SEALING TREATMENT	9,949.000 SQYD				
0470	4139905 MISC. HIGH FRICTION SURFACE TREATMENT - BAUXITE	3,534.000 SQYD				
0480	6069902 MISC. SURFACE MOUNTED FLEXIBLE DELINEATORS - YELLOW	6.000 EA				
0490	6092011 INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	68.000 LF				

State of MISSOURI
Dept of Transportation
Schedule of Items

Contract ID: 161216-D01
Letting Date: 12-16-16
Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0500	6123000A TRUCK OR TRAILER MOUNTED ATTENUATOR (TMA)	EA 2.000				
0510	6131010 FURNISHING AND PLACING CONCRETE MATERIAL FOR FULL DEPTH PAVEMENT REPAIR	SQYD 622.000				
0520	6131012 SUBGRADE COMPACTION (6 IN. DEPTH) (PAVEMENT REPAIR)	SQYD 62.000				
0530	6131014 FULL DEPTH PAVEMENT REPAIR SAW CUT (FOR PERIMETER AND INTERNAL SAW CUTS)	LF 1,947.000				
0540	6131015 DOWEL BAR (DRILLING, FURNISHING AND INSTALLATION) FOR FULL DEPTH PAVEMENT REPAIR	EA 1,210.000				
0550	6133018 FURNISHING AND PLACING BITUMINOUS MATERIAL FOR CLASS B PARTIAL DEPTH PAVEMENT REPAIR	TONS 43.000				

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0560	6133019 REMOVAL FOR CLASS B PARTIAL DEPTH PAVEMENT REPAIR	198.600 SQYD				
0570	6134001 DOWEL BAR RETROFIT	1,842.000 EA				
0580	6134002 CROSS STITCH TIE BAR	611.000 EA				
0590	6161005 CONSTRUCTION SIGNS	711.000 SQFT				
0600	6161008 ADVANCED WARNING RAIL SYSTEM	13.000 EA				
0610	6161009 FLAG ASSEMBLY	9.000 EA				
0620	6161025 CHANNELIZER (TRIM LINE)	332.000 EA				
0630	6161040 FLASHING ARROW PANEL	3.000 EA				

State of MISSOURI
Dept of Transportation
Schedule of Items

Contract ID: 161216-D01

Letting Date: 12-16-16

Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0640	6161099 CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	EA 2.000				
0650	6181000 MOBILIZATION	LUMP	LUMP			
0660	6205120 TYPE 2 PREFORMED MARKING TAPE (GROOVED), 24 IN., WHITE	LF 24.000				
0670	6205130 TYPE 2 PREFORMED MARKING TAPE (GROOVED), LEFT/RIGHT ARROW	EA 6.000				
0680	6205133 TYPE 2 PREFORMED MARKING TAPE (GROOVED), WORD (ONLY)	EA 2.000				
0690	6205139 TYPE 2 PREFORMED MARKING TAPE (GROOVED), 12 IN. WHITE, YIELD LINE TRIANGLES	EA 10.000				

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0700	6205902A 6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	79,545.000 LF				
0710	6205903A 6 IN. YELLOW HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	59,668.000 LF				
0720	6205906A 12 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	4,545.000 LF				
0730	6206000C 4 IN. WHITE WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	2,924.000 LF				
0740	6206001C 4 IN. YELLOW WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	5,028.000 LF				
0750	6206108A 8 IN. WHITE WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	727.000 LF				

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0760	6206124A 24 IN. WHITE WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	200.000 LF				
0770	6206125A 24 IN. YELLOW WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	45.000 LF				
0780	6221001 COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (3 IN. THICK OR LESS)	1,662.000 SQYD				
0790	6224010 MODIFIED COLDMILLING (DEPTH TRANSITIONS)	8,077.000 SQYD				
0800	6261000A BITUMINOUS SHOULDER RUMBLE STRIP	903.000 STA				
	Section 0003 Total					0.00
Section 0004 Guardrail/ Guard Cable Items - J5P3127						
Alt Group						

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0810	6061061 MGS GUARDRAIL, 8 FT. POSTS, 6 FT. - 3 IN. SPACING	2,263.000 LF				
0820	6061068 MGS BRIDGE APPROACH TRANSITION SECTION (MAJOR ROUTE)	4.000 EA				
0830	6061074 MGS HEIGHT AND BLOCK TRANSITION	2.000 EA				
0840	6061080 MGS END ANCHOR	4.000 EA				
0850	6062303 ASYMMETRICAL TRANSITION SECTION, 6.5 FT. POSTS	4.000 EA				
0860	6063014 TYPE A CRASHWORTHY END TERMINAL (MASH)	12.000 EA				
	Section 0004 Total					0.00

Section 0005 Signing Items - J5P3127

Alt Group

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0870	9031010 CONCRETE FOOTINGS, EMBEDDED	18.700 CUYD				
0880	9031210 STRUCTURAL STEEL POSTS	1,740.000 LB				
0890	9031220 PIPE POSTS	820.000 LB				
0900	9031241 BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	14.000 EA				
0910	9031272 2.25 IN. PSST POST - 12 GA.	384.000 LF				
0920	9031273 POST ANCHOR FOR 2 IN. PSST - 7 GA.	72.000 LF				
0930	9035004A SH-FLAT SHEET	219.000 SQFT				
0940	9035011A ST-STRUCTURAL	181.000 SQFT				

State of MISSOURI
 Dept of Transportation
 Schedule of Items

Contract ID: 161216-D01
 Letting Date: 12-16-16
 Project(s):

Bidder: -

Line No.	Item Description	Approx. Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Ct
0950	9035069A SHF-FLAT SHEET FLUORESCENT	18.000 SQFT				
	Section 0005 Total					0.00
	Bid Total					2,400.00

Contract Id: 161216-D01
Vendor Name:

Vendor Number:

SUBCONTRACTOR DISCLOSURE

The bidder shall submit with this bid any subcontracts that meet the requirements of Sec 102. List below the name of each subcontractor that will be furnishing labor or labor and materials, the category of work that the subcontractor will be performing (e.g. asphalt, concrete, earthwork, bridges...), and the dollar value of the subcontract. Select "NONE" if there are no subcontractors that need to be disclosed.

If the information is not available at the time of bid the bidder shall submit the "Subcontractor Disclosure Form", located on MoDOT's website, on or before 4:00 p.m. of the third business day after the bid opening date, directly to the Design Division, Missouri Department of Transportation, 105 W. Capitol Avenue, P.O. Box 270, Jefferson City, Missouri 65102-0270. Telefax transmittal to MoDOT will be permitted at fax no. 573-522-2281 or e-mailed to subcontractor.disclosure@modot.mo.gov. The complete signed original documents do not need to be mailed to MoDOT, but the bidder shall have it available if requested by the Design Division or the engineer.

SUBCONTRACTOR NAME	DOLLAR VALUE OF SUBCONTRACT	CATEGORY OF WORK
--------------------	--------------------------------	------------------

BID BOND

KNOW ALL PERSONS BY THESE PRESENTS, that we as principal and and as surety, are held and firmly bound unto the state of Missouri (acting by and through the Missouri Highways and Transportation Commission) in the penal sum of 120.00 Dollars to be paid to the commission to be credited to the state road fund, the principal and surety binding themselves, their heirs, executors, administrators, successors, and assigns, jointly and severally, firmly by these presents.

Sealed with our seals and dated this.

THE CONDITION OF THIS OBLIGATION is such that WHEREAS the principal is submitting herewith a bid to the commission on

route(s)
in County(ies)
project(s)

for construction or improvement of state highway as set out in said bid;

NOW THEREFORE, if the commission shall accept the bid of the principal and if the principal shall properly execute and deliver to the commission the contract, contract bond, and evidence of insurance coverage in compliance with the requirements of the bid, the specifications, and the provisions of section 227.100 RSMo, to the satisfaction of the commission, then this obligation shall be void and of no effect, otherwise to remain in full force and effect.

In the event the said principal shall, in the judgment of the commission, fail to comply with any requirement as set forth in the preceding paragraph, then the state of Missouri, acting by and through the commission, shall immediately and forthwith be entitled to recover the full penal sum above set out, together with court costs, attorney's fees, and any other expense of recovery.

The principal and surety hereby certify that the document is the original or a verbatim copy of the bid bond form furnished by the Commission, in accordance with Sec 102.9 of the Missouri Standard Specifications for Highway Construction.

This Bid contains 0 amendment files



JOB SPECIAL PROVISIONS TABLE OF CONTENTS

(Job Special Provisions shall prevail over General Provisions whenever in conflict therewith.)

- A. General
- B. Contract Liquidated Damages
- C. Liquidated Damages Specified
- D. Work Zone Traffic Management Plan
- E. Utilities
- F. Project Contact for Contractor/Bidder Questions
- G. Emergency Provisions and Incident Management
- H. Contractor Quality Control
- I. Supplemental Revisions
- J. DBE Program Requirements
- K. Contractor Retained Items
- L. Disposition of Existing Asphalt Pavement
- M. Optional Pavement
- N. Stormwater Compliance Requirements
- O. e-Construction
- P. Electronic Information for Bidder's Automation
- Q. Capping Existing Median Drop Inlet
- R. Pavement Construction Requirements
- S. Bonded Asphalt Concrete Pavement
- T. Additional Mobilization for Seeding
- U. Fertilizing, Seeding, and Mulching

 <p>THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.</p>	MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65102 Phone 1-888-275-6636
	If a seal is present on this sheet, JSP's have been electronically sealed and dated.
	JOB NUMBER: J5P3056 COLE COUNTY, MO DATE PREPARED: 09/22/16
	ADDENDUM DATE:
Only the following items of the Job Special Provisions (Roadway) are authenticated by this seal: All	

JOB
SPECIAL PROVISION

A. GENERAL - FEDERAL JSP-09-02B

1.0 Description. The Federal Government is participating in the cost of construction of this project. All applicable Federal laws, and the regulations made pursuant to such laws, shall be observed by the contractor, and the work will be subject to the inspection of the appropriate Federal Agency in the same manner as provided in Sec 105.10 of the Missouri Standard Specifications for Highway Construction with all revisions applicable to this bid and contract.

1.1 This contract requires payment of the prevailing hourly rate of wages for each craft or type of work required to execute the contract as determined by the Missouri Department of Labor and Industrial Relations, and requires adherence to a schedule of minimum wages as determined by the United States Department of Labor. For work performed anywhere on this project, the contractor and the contractor's subcontractors shall pay the higher of these two applicable wage rates. State Wage Rates, Information on the Required Federal Aid Provisions, and the current Federal Wage Rates are available on the Missouri Department of Transportation web page at www.modot.org under "Bidding". Effective Wage Rates will be posted 10 days prior to the applicable bid opening. These supplemental bidding documents have important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.

1.2 The following documents are available on the Missouri Department of Transportation web page at www.modot.org under "Business"; "Standards and Specifications". The effective version shall be determined by the letting date of the project.

General Provisions & Supplemental Specifications

Supplemental Plans to October 2016 Missouri Standard Plans
For Highway Construction

These supplemental bidding documents contain all current revisions to the published versions and have important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.

B. CONTRACT LIQUIDATED DAMAGES

1.0 Description. Liquidated Damages for failure or delay in completing the work on time for this contract shall be in accordance with Sec 108.8. The liquidated damages include separate amounts for road user costs and contract administrative costs incurred by the Commission.

2.0 Period of Performance. Prosecution of work is expected to begin on the date specified below in accordance with Sec 108.2. Regardless of when the work is begun on this contract, all work shall be completed on or before the date specified below. Completion by this date shall be in accordance with the requirements of Sec 108.7.1.

Notice to Proceed: February 6, 2017
Completion Date: October 31, 2017

2.1 Calendar Days. The count of calendar days will begin on the date the contractor starts any construction operations on the project.

Job Number	Calendar Days	Daily Road User Cost
J5P3056	54	\$3,200
J5P3127	54	\$3,200

3.0 Liquidated Damages for Contract Administrative Costs. Should the contractor fail to complete the work on or before the completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged contract administrative liquidated damages in accordance with Sec 108.8 in the amount of **\$1,000** per calendar day for each calendar day, or partial day thereof, that the work is not fully completed. For projects in combination, these damages will be charged in full for failure to complete one or more projects within the above specified completion date or calendar days.

4.0 Liquidated Damages for Road User Costs. Should the contractor fail to complete the work on or before the completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged road user costs in accordance with Sec 108.8 in the amount specified in Section 2.1 for each calendar day, or partial day thereof, that the work is not fully completed. These damages are in addition to the contract administrative damages and any other damages as specified elsewhere in this contract.

C. LIQUIDATED DAMAGES SPECIFIED

1.0 Description. If the Eastbound Acceleration Lane, Eastbound Right Turn Lane, Lisletown Acceleration & Deceleration Lanes, and Liberty/Shamrock Intersection are not open to traffic and the existing median cross over at Liberty Road closed prior to June 1, 2017, the Commission, the traveling public, and state and local police and governmental authorities will be damaged in various ways, including but not limited to, increased construction administration cost, potential liability, traffic and traffic flow regulation cost, traffic congestion and motorist delay, with its resulting cost to the traveling public. These damages are not reasonably capable of being computed or quantified. Therefore, the contractor will be charged with liquidated damages specified in the amount of \$3,200 per day for each full day that the aforementioned intersection is not complete and open to traffic in excess of the limitation as specified elsewhere in this special provision. It shall be the responsibility of the engineer to determine the quantity of excess closure time.

1.1 Contractor Coordination. Both S. Shamrock Road and Liberty Road shall be opened prior to the closure of the Cole Route M/J Bridge over Route 50 being constructed under Job Number J5S3146. The contractor may coordinate and adjust of the opening date to correspond with the closure date of the bridge, once discussion with, and approval from, the engineer is completed.

2.2 Closure Date for Road Closure. The closure of Liberty Road and Shamrock Road for the completion of the tie-in work shall not occur prior to April 15, 2017; to accommodate a bridge construction project completion and the opening of Liberty Road at Rising Creek. The bridge project is

located approximately 1.75 miles east of the Liberty/Shamrock intersection and is being administered by Cole County Public Works.

2.3 Definition of Road Open to Traffic. The road shall be considered open to traffic once the pavement base course of the aforementioned segments of the Liberty/Shamrock intersection improvements is completed and the proper traffic control devices and temporary pavement markings are in place and approved by the engineer.

3.0 The said liquidated damages specified will be assessed regardless of whether it would otherwise be charged as liquidated damages under the Missouri Standard Specification for Highway Construction, as amended elsewhere in this contract.

D. WORK ZONE TRAFFIC MANAGEMENT PLAN

1.0 Description. Work zone traffic management shall be in accordance with applicable portions of Division 100 and Division 600 of the Standard Specifications, and specifically as follows.

1.1 Work Zone Specialist (WZS). The Traffic Management Plan shall name an individual, either employed by the contractor or hired by the contractor, to act as the Work Zone Specialist (WZS) throughout the entirety of the project. Any change in personnel for the WZS shall be submitted in written form to the engineer. This individual will be a trained Work Zone Specialist in accordance with Standard Specifications Section 616.3.3 and will be directly involved with daily traffic management and traffic management planning. It will be the responsibility of the WZS to coordinate daily traffic management with the engineer. The WZS shall maintain daily contact with the engineer either on-site or via telecommunication.

1.2 Maintaining Work Zones and Work Zone Reviews. The WZS shall maintain work zones on a daily basis to ensure safety to the traveling public and the workers; this includes long term work zones that have devices and/or roadway conditions that need to be maintained. If the engineer or a designated MoDOT employee (identified at the preconstruction meeting) notifies the WZS of any safety or traffic delay concerns in the work zone, the WZS shall promptly inspect and work to provide a solution to correct the situation. The WZS shall have personnel reviewing traffic control devices daily and any temporary lane drop traffic control devices for initial set up and during the operation. Missing, damaged or over-turned traffic control devices shall typically be corrected without the need for direction by the engineer. The WZS is responsible to assure all traffic control devices are maintained in accordance with EPG standards. The WZS is responsible to ensure the work zone is operated within the hours specified by the engineer and will not deviate from the specified hours without prior approval of the engineer. The WZS is responsible to manage work zone delay in accordance with these project provisions. The WZS and engineer shall submit one joint weekly technical review of work zone operations identifying any concerns present and the corrective actions taken. Reviews may be subjected to unannounced inspections by the engineer to corroborate the validity of the ratings. The engineer and WZS will be notified of the results.

1.3 Work Zone Conflict Resolution. Any conflict resolution shall be in accordance with Standard Specifications Section 616.4. Failure to make corrections on time may result in the engineer suspending work. The suspension will be non-excusable and non-compensable regardless if road user costs are being charged for closures.

2.0 Traffic Management Schedule.

2.1 Traffic management schedules shall be submitted to the engineer for review prior to the start of work and prior to any revisions to the traffic management schedule. The traffic management schedule shall include the proposed traffic control measures, the hours traffic control will be in place, and work hours.

2.2 The contractor shall request permission at least two working days prior to lane closures or shifting traffic onto detours, and 14 calendar days prior to the imposition of height, width or weight restrictions. This is to ensure closures do not conflict with other work within the zone of influence and the work zone information on the MoDOT's website can remain real-time.

2.3 The engineer shall be notified as soon as practical of any postponement due to weather, material or other circumstances.

2.4 In order to ensure minimal traffic interference, the contractor shall schedule lane closures for the absolute minimum amount of time required to complete the work. Lanes shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed lane is opened to traffic.

2.5 Traffic Congestion. The contractor shall, upon approval of the engineer, take proactive measures to reduce traffic congestion in the work zone. The contractor shall immediately implement appropriate mitigation strategies whenever traffic congestion reaches an excess of **12 minutes** to prevent congestion from escalating beyond this delay threshold. If disruption of the traffic flow occurs and traffic is backed up in queues equal to or greater than the delay time threshold listed above then the contractor shall immediately review the construction operations which contributed directly to disruption of the traffic flow and make adjustments to the operations to prevent the queues from reoccurring. Traffic delays may be monitored by physical presence on site or by utilizing real-time travel data through the work zone that generate text and/or email notifications where available. The engineer monitoring the work zone may also notify the contractor of delays that require prompt mitigation. The contractor may work with the engineer to determine what other alternative solutions or time periods would be acceptable. The contractor may refer to the Work Zone Analysis Spreadsheet found in the electronic deliverables under the MoDOT Online Plans Room for detailed information on traffic delays.

2.5.1 Traffic Safety.

2.5.1.1 Where traffic queues routinely extend to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway, the contractor shall extend the advance warning area, as approved by the engineer.

2.5.1.2 When a traffic queue extends to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway due to non-recurring congestion, the contractor shall deploy a means of providing advance warning of the traffic congestion, as approved by the engineer. The warning location shall be no less than 1000 feet and no more than 0.5 mile in advance of the end of the traffic queue on divided highways and no less than 500 feet and no more than 0.5 mile in advance of the end of the traffic queue on undivided highways.

3.0 Work Hour Restrictions.

3.1 There are six major holiday periods shown below. All lanes shall be scheduled to be open to traffic during these holiday periods, from 12:00 noon on the last working day proceeding the holiday until 9:00 a.m. on the first working day subsequent to the holiday.

Memorial Day
Independence Day
Labor Day
Thanksgiving
Christmas
New Year's Day

3.2 The contractor shall not perform any construction operation on the roadway, including the hauling of material within the project limits, during restricted periods, holiday periods or other special events specified in the contract documents.

3.3 The contractor shall be aware that traffic volume data indicates construction operations on the roadbed between the following hours will likely result in traffic queues greater than 15 minutes. Based on this, the contractors operations will be restricted accordingly unless it can be successfully demonstrated the operations can be performed without a 15 minute queue in traffic. It shall be the responsibility of the engineer to determine if the above work hours may be modified. Working hours for evenings, weekends and holidays will be determined by the engineer.

Route 50 Eastbound:
3:00 p.m. - 6:00 p.m. Monday through Friday

Route 50 Westbound:
6:00 a.m. - 8:00 a.m. Monday through Friday

3.5 The contractor shall not alter the start time, ending time, or a reduction in the number of through lanes of traffic or ramp closures without advance notification and approval by the engineer. The only work zone operation approved to begin 30 minutes prior to a reduction in through traffic lanes or ramp closures is the installation of traffic control signs. Should lane closures be placed or remain in place, prior to the approved starting time or after the approved ending time, the Commission, the traveling public, and state and local police and governmental authorities will be damaged in various ways, including but not limited to, increased construction administration cost, potential liability, traffic and traffic flow regulation cost, traffic congestion and motorist delays, with a resulting cost to the traveling public. These damages are not easily computed or quantified. Therefore, the contractor will be charged with liquidated damages specified in the amount of **\$1,000 per 15 minute increment** for each 15 minutes that the temporary lane closures are in place and not open to traffic in excess of the limitation as specified elsewhere in this special provision. It shall be the responsibility of the engineer to determine the quantity of unapproved closure time.

3.5.1 The said liquidated damages specified will be assessed regardless if it would otherwise be charged as liquidated damages under the Missouri Standard Specification for Highway Construction, as amended elsewhere in this contract.

4.0 Detours and Lane Closures.

4.1 The contractor shall provide changeable message signs (CMS) notifying motorists of future traffic disruption and possible traffic delays one week before traffic is shifted to a detour or prior to lane closures. The CMS shall be installed at a location as approved or directed by the engineer. The CMS shall be capable of communication with the Transportation Management Center (TMC), if applicable, prior to installation on right of way. All messages planned for use in the work zone shall be approved and authorized by the engineer or its designee prior to deployment. Permanent dynamic message signs (DMS) owned and operated by MoDOT may also be used to provide warning and information for the work zone. Permanent DMS shall be operated by the TMC, and any messages planned for use on DMS shall be approved and authorized by the TMC at least 72 hours in advance of the work.

4.2 At least one lane of traffic in each direction shall be maintained at all times except for brief intervals of time required when the movement of the contractor's equipment will seriously hinder the safe movement of traffic. Periods during which the contractor will be allowed to interrupt traffic will be designated by the engineer.

5.0 Basis of Payment. No direct payment will be made to the contractor to recover the cost of equipment, labor, materials or time required to fulfill the above provisions, unless specified elsewhere in the contract document. All authorized changes in the traffic control plan shall be provided for as specified in Standard Specifications Section 616.

E. UTILITIES

1.0 For informational purposes only, the following is a list of names, addresses, and telephone numbers of the known utility companies in the area of the construction work for this improvement:

<u>Utility Name</u>	<u>Known Required Adjustment</u>	<u>Type</u>
Ameren Missouri Electric 1310 Industrial Drive Jefferson City, MO 65109 Contact: Brody Ash Phone: (573) 681-7528 Email: bash@ameren.com	None – see 1.1.1	Electric
Centurylink 3456 North Ten Mile Drive Jefferson City, MO 65109 Contact: Allen Groner Phone: (573) 634-1686 Email: allen.t.groner@centurylink.com	None – see 1.1.2	Communications

City of Jefferson – Wastewater 320 East McCarty Jefferson City, MO 65101 Contact: Eric Seaman Phone: (573) 634-6410 Email: ESeaman@jeffcitymo.org	None	Sewer
Cole County PWSD#4 7712 Route M Jefferson City, MO 65101 Contact: Will Humphrey Phone: (573) 395-4578 Email: will@colepwsd4.com	None	Water
Phillips 66 Pipeline 2116 Idlewood Road Jefferson City, MO 65109 Contact: Kevin Jungmeyer Phone: (573) 636-4984 Email: k.d.jungmeyer@p66.com	None – see 1.1.3	Gas
Three Rivers Electric Cooperative 1324 E. Main Street Linn, MO 65051 Contact: Ted Neuner Phone: (573) 644-9000 Email: TNeuner@threeriverselectric.com	None – see 1.1.4	Electric
Sho-Me Technologies 301 W. Jackson P.O. Box D Marshfield, MO 65706 Contact: Eric Wutke Phone: (417) 859-2615 Email: ewutke@shometech.com	None	Communications
Suddenlink Communications Contact: Brent Lovell Phone: (816) 646-3438 Email: Brent.lovell@suddenlink.com	None	Communications

1.1 The existence and approximate location of utility facilities known to exist, as shown on the plans, are based upon the best information available to the Commission at this time. This information is provided by the Commission "as-is" and the Commission expressly disclaims any representation or warranty as to the completeness, accuracy, or suitability of the information for any use. Reliance upon this information is done at the risk and peril of the user, and the Commission shall not be liable for any damages that may arise from any error in the information. It is, therefore, the responsibility of the

contractor to verify the above listing information indicating existence, location and status of any facility. Such verification includes direct contact with the listed utilities.

1.1.1 Ameren Electric has overhead lines in the work area. These facilities will not be relocated; therefore the contractor shall use caution to not disturb the overhead electric lines with their construction activities. The contractor shall be responsible for any damage to the overhead electric lines in the project limits.

1.1.2 Centurylink has an overhead line in the work area. These facilities will not be relocated; therefore the contractor shall use caution to not disturb the overhead communication line with their construction activities. The contractor shall be responsible for any damage to the overhead communication line in the project limits.

1.1.3 Phillips Pipeline has underground gas pipelines located south of the Route 50/63 right of way. These facilities will not be relocated, therefore the contractor shall use caution to not disturb the underground gas pipeline in the area while performing construction activities. The contractor shall be responsible for any damage to the underground gas pipeline in the project limits.

1.1.4 Three Rivers Electric has overhead lines in the work area. These facilities will not be relocated; therefore the contractor shall use caution to not disturb the overhead electric lines with their construction activities. The contractor shall be responsible for any damage to the overhead electric lines in the project limits.

1.2 The contractor agrees that any effects of the presence of the utilities, their relocation, contractor's coordination of work with the utilities and any delay in utility relocation shall not be compensable as a suspension of work, extra work, a change in the work, as a differing site condition or otherwise including but, without limitation, delay, impact, incidental or consequential damages. The contractor's sole remedy for the effects of the presence of utilities, delay in their relocation or any other effects shall be an excusable delay as provided in [Sec 105.7.6](#). The contractor waives, for itself, its subcontractors and suppliers the compensability of the presence of utilities, delay in their relocation and any cost to the contractor, it's subcontractors and suppliers in any claim or action arising out of or in relation to the work under the contract.

1.3 The contractor shall be solely responsible and liable for incidental and consequential damage to any utility facilities or interruption of the service caused by it or its subcontractors operation. The contractor shall hold and save harmless the Commission from damages to any utility facilities interruption of service by it or its subcontractor's operation.

F. PROJECT CONTACT FOR CONTRACTOR/BIDDER QUESTIONS

All questions concerning this project during the bidding process shall be forwarded to the project contact listed below.

Bruce Green, Project Contact
MoDOT - Central Missouri District
1511 Missouri Blvd., P.O. Box 718
Jefferson City, Missouri 65102

Telephone Number 573-751-7688
Email: Bruce.Green@modot.mo.gov

All questions concerning the bid document preparation can be directed to the Central Office – Design at (573) 751-2876.

G. EMERGENCY PROVISIONS AND INCIDENT MANAGEMENT

1.0 The contractor shall have communication equipment on the construction site or immediate access to other communication systems to request assistance from the police or other emergency agencies for incident management. In case of traffic accidents or the need for police to direct or restore traffic flow through the job site, the contractor shall notify police or other emergency agencies immediately as needed. The resident engineer's office shall also be notified when the contractor requests emergency assistance.

2.0 In addition to the 911 emergency telephone number for ambulance, fire or police services, the following agencies may also be notified for accident or emergency situation within the project limits.

Missouri Highway Patrol (Troop F): 573-751-1000 (*55 Cell)	
Cole County Sheriff	573-634-9160
Jefferson City Police	573-634-6400
Jefferson City Fire Depart.	573-634-6401

2.1 This list is not all inclusive. Notification of the need for wrecker or tow truck services will remain the responsibility of the appropriate police agency.

2.2 The contractor shall notify enforcement and emergency agencies before the start of construction to request their cooperation and to provide coordination of services when emergencies arise during the construction at the project site. When the contractor completes this notification with enforcement and emergency agencies, a report shall be furnished to the engineer on the status of incident management.

3.0 No direct pay will be made to the contractor to recover the cost of the communication equipment, labor, materials or time required to fulfill the above provisions.

H. CONTRACTOR QUALITY CONTROL NJSP-15-42

1.0 The contractor shall perform Quality Control (QC) testing in accordance with the specifications and as specified herein. The contractor shall submit a Quality Control Plan (QC Plan) to the engineer for approval that includes all items listed in Section 2.0, prior to beginning work.

2.0 Quality Control Plan.

- (a) The name and contact information of the person in responsible charge of the QC testing.

- (b) A list of the QC technicians who will perform testing on the project, including the fields in which they are certified to perform testing.
- (c) A proposed independent third party testing firm for dispute resolution, including all contact information.
- (d) A list of Hold Points, when specified by the engineer.
- (e) The MoDOT Standard Inspection and Testing Plan (ITP). This shall be the version that is posted at the time of bid on the MoDOT website (www.modot.org/quality).

3.0 Quality Control Testing and Reporting. Testing shall be performed per the test method and frequency specified in the ITP. All personnel who perform sampling or testing shall be certified in the MoDOT Technician Certification Program for each test that they perform.

3.1 Reporting of Test Results. All QC test reports shall be submitted as soon as practical, but no later than the day following the test. Test data shall be immediately provided to the engineer upon request at any time, including prior to the submission of the test report. No payment will be made for the work performed until acceptable QC test results have been received by the engineer and confirmed by QA test results.

3.1.1 Test results shall be reported on electronic forms provided by MoDOT. Forms and Contractor Reporting Excel2Oracle Reports (CRE2O) can be found on the MoDOT website. All required forms, reports and material certifications shall be uploaded to a Microsoft SharePoint® site provided by MoDOT, and organized in the file structure established by MoDOT.

3.2 Non-Conformance Reporting. A Non-Conformance Report (NCR) shall be submitted by the contractor when the contractor proposes to incorporate material into the work that does not meet the testing requirements or for any work that does not comply with the contract terms or specifications.

3.2.1 Non-Conformance Reporting shall be submitted electronically on the Non-Conformance Report form provided on the MoDOT Website. The NCR shall be uploaded to the MoDOT SharePoint® site and an email notification sent to the engineer.

3.2.2 The contractor shall propose a resolution to the non-conforming material or work. Acceptance of a resolution by the engineer is required before closure of the non-conformance report.

4.0 Work Planning and Scheduling.

4.1 Two-week Schedule. Each week, the contractor shall submit to the engineer a schedule that outlines the planned project activities for the following two-week period. The two-week schedule shall detail all work and traffic control events planned for that period and any Hold Points specified by the engineer.

4.2 Weekly Meeting. When work is active, the contractor shall hold a weekly project meeting with the engineer to review the planned activities for the following week and to resolve any outstanding issues. Attendees shall include the engineer, the contractor superintendent or project manager and any foreman leading major activities. This meeting may be waived when, in the opinion of the engineer, a meeting is not necessary. Attendees may join the meeting in person, by phone or video conference.

4.3 Pre-Activity Meeting. A pre-activity meeting is required in advance of the start of each new activity, except when waived by the engineer. The purpose of this meeting is to review construction

details of the new activity. At a minimum, the discussion topics shall include: safety precautions, QC testing, traffic impacts, and any required Hold Points. Attendees shall include the engineer, the contractor superintendent and the foreman who will be leading the new activity. Pre-activity meetings may be held in conjunction with the weekly project meeting.

4.4 Hold Points. Hold Points are events that require approval by the engineer prior to continuation of work. Hold Points occur at definable stages of work when, in the opinion of the engineer, a review of the preceding work is necessary before continuation to the next stage.

4.4.1 A list of typical Hold Point events is available on the MoDOT website. Use of the Hold Point process will only be required for the project-specific list of Hold Points, if any, that the engineer submits to the contractor in advance of the work. The engineer may make changes to the Hold Point list at any time.

4.4.2 Prior to all Hold Point inspections, the contractor shall verify the work has been completed in accordance with the contract and specifications. If the engineer identifies any corrective actions needed during a Hold Point inspection, the corrections shall be completed prior to continuing work. The engineer may require a new Hold Point to be scheduled if the corrections require a follow-up inspection. Re-scheduling of Hold Points require a minimum 24-hour advance notification from the contractor unless otherwise allowed by the engineer.

5.0 Quality Assurance Testing and Inspection. MoDOT will perform quality assurance testing and inspection of the work, except as specified herein. The contractor shall utilize the inspection checklists provided in the ITP as a guide to minimize findings by MoDOT inspection staff. Submittal of completed checklists is not required, except as specified in 5.1.

5.1 Inspection and testing required in the production of concrete for the project shall be the responsibility of the contractor. Submittal of the 501 Concrete Plant Checklist is required.

6.0 Basis of Payment. No direct payment will be made for compliance with this provision.

I. SUPPLEMENTAL REVISIONS JSP-09-01U

Insert Sec 109.15, Sec 109.16 and Sec 109.17, subsequent section renumbered accordingly:

109.15 Seal Coat Price Index. Adjustments will be made to the payments due the contractor for Seal Coat placed in accordance with Sec 409 of the Standard Specifications. Adjustments will be calculated in accordance with Asphalt Cement Price Index of the General Provisions, except as defined herein.

109.15.1 Basis of Payment. To determine the adjustment for any material specified in this provision the following formula will be used.

$$A = B \times (0.68 \times 8.58/2000) \times (D - E)$$

Where:

- A = adjustment for Seal Coat placed during the index period
- B = gallons of seal coat placed during the index period
- D = average index price at the beginning of the period
- E = average index price at the time of bid

0.68 = factor to reduce volume of emulsion to AC only
(use average specific gravity of 1.03 for seal coat)

109.15.2 Optional. This provision is optional. If the bidder wishes to be bound by this provision, the bidder shall execute the acceptance form in the Bid for the Asphalt Cement Price Index. Acceptance of this provision will apply to both the Asphalt Cement Price Index and Seal Coat Price Index. Failure by the bidder to execute the acceptance form will be interpreted to mean election to not participate in the Asphalt Cement Price Index or Seal Coat Price Index.

109.16 Asphalt Underseal Price Index. Adjustments will be made to the payments due the contractor for Asphalt underseal placed in accordance with Sec 625 of the Standard Specifications. Adjustments will be calculated in accordance with Asphalt Cement Price Index of the General Provisions, except as defined herein.

109.16.1 Basis of Payment. To determine the adjustment for any material specified in this provision the following formula will be used.

$$A = B \times (8.66/2000) \times (D - E)$$

Where: A = adjustment for asphalt underseal placed during the index period
B = gallons of asphalt underseal placed during the index period
D = average index price at the beginning of the period
E = average index price at the time of bid
(use average specific gravity of 1.04 for underseal)

109.16.2 Optional. This provision is optional. If the bidder wishes to be bound by this provision, the bidder shall execute the acceptance form in the Bid for the Seal Coat Price Index. Failure by the bidder to execute the acceptance form will be interpreted to mean election to not participate in the Seal Coat Price Index.

109.17 Polymer Modified Emulsion Membrane Price Index. Adjustments will be made to the payments due the contractor for Polymer Modified Emulsion Membrane placed in accordance with Sec 413.30. Adjustment will be calculated in accordance with the Supplemental Asphalt Price Adjustment except as defined herein.

109.17.1 Basis of Payment. To determine the adjustment for any material specified in this provision the following formula will be used.

$$A=B \times (0.9/2000) \times (D - E)$$

Where: A = adjustment for membrane placed during the index period
B = square yards of membrane placed during the index period
D = average index price at the beginning of the period
E = average index price at time of bid

109.17.2 Optional. This provision is optional. If the bidder wishes to be bound by the provision, the bidder shall execute the acceptance form in the Bid for Polymer Modified Emulsion Membrane Price Index. Failure by the bidder to execute the acceptance form will be interpreted to mean election not to participate in the Polymer Modified Emulsion Membrane Price Index.

Delete Sec 403.2.5.2 and substitute the following:

403.2.5.2 Fibers. A fiber additive shall be used as a stabilizer in SMA Mixtures. Fibers shall be uniformly distributed by the end of the plant mixing process. The dosage rate for fibers shall be no less than 0.3 percent by weight of the total mixture for cellulose and no less than 0.4 percent by weight for mineral fibers.

Delete Sec 407 in its entirety and substitute the following:

407.1 Description. This work shall consist of preparing and treating an existing bituminous or concrete surface with bituminous material, in accordance with these specifications.

407.2 Material. All material shall be in accordance with Division 1000, Material Details, and specifically as follows:

Item	Section
Emulsified Asphalt or PG Liquid Asphalt	1015

407.3 Equipment. The contractor shall provide a system for heating and applying the bituminous material. The system shall be designed, equipped, maintained and operated such that emulsified asphalt or liquid asphalt, at even heat, may be applied uniformly on variable widths of surface up to 15 feet with uniform pressure and an allowable variation from any specified rate of ± 0.01 gallon per square yard. The system shall include a calibrated tank and a thermometer for measuring temperature of tank contents. The system shall be equipped with instrumentation that continuously verifies application rates. The calibration of the system shall be approved by the engineer prior to use, and the contractor shall furnish all equipment, material and assistance if calibration is required.

407.4 Construction Requirements.

407.4.1 Preparation of Surface. The existing surface shall be free of all dust, loose material, grease or other foreign material at the time the tack is applied. Any excess bituminous surface mixture or bituminous joint material will be removed by MoDOT without cost to the contractor before the tack is applied.

407.4.2 Application. Asphalt emulsion or PG liquid asphalt shall be applied uniformly with a pressure distributor at the minimum rates indicated in the following table. No dilution of the emulsified asphalt material shall be allowed. The tack coat material shall be heated at the time of application to a temperature in accordance with Sec 1015. The tack coat shall be properly cured and the tacked surface shall be clean of all dirt before the next course is placed.

Tack Coat Application Rates	
Surface Type	Minimum Application Rate (Gal. per sq. yd.)
New Asphalt Pavement	0.05
Existing Asphalt or Concrete Pavement	0.08

407.4.3 Tack. The tack coat shall be applied in such a manner as to cause the least inconvenience to traffic and to permit one-way traffic without tracking of asphalt emulsion. All exposed tack coat shall be covered with bituminous mixture prior to opening to traffic.

407.5 Method of Measurement. Measurement of asphalt emulsion to the nearest 10 gallons will be made in accordance with Sec 1015.

407.6 Basis of Payment. The accepted quantity of tack coat will be paid for at the contract unit price.

Amend Sec 620.10.3.1.1.1, and 620.10.3.1.1.2 to include the following:

620.10.3.1.1.1 Type 1 Preformed Marking Tape in Lieu of Type 2. Type 1 Preformed Pavement Marking Tape will be allowed in lieu of Type 2 Preformed Marking Tape (Grooved) at no additional cost to the Commission. This work shall be in accordance with Sec 620 and accompanying provisions except as modified herein.

620.10.3.1.1.2 Construction Requirements. Grooving will not be required when Type 1 Preformed Marking Tape is used.

Delete Sec 606.30.4 & 606.30.5 and substitute the following:

606.30.4 Method of Measurement. Measurement for crashworthy end terminals will be made for each unit assembled, installed and complete in place. Grading for crashworthy end terminals will be measured in accordance with [Sec 203](#) when roadway and drainage excavation is included in the contract, otherwise grading will be measured in accordance with Shaping Slopes, Class III or as directed on plans.

606.30.5 Basis of Payment. The accepted quantities of Type A, B C, D and E crashworthy end terminals, complete in place, will be paid for at the contract unit price. Payment will be considered full compensation for complete installation including any backup assemblies or other items necessary for proper installation of the end terminal or crash cushion as required. Grading for end terminals will be paid for at the contract unit price for roadway and drainage excavation if included in the contract; otherwise it will be paid for as Shaping Slopes, Class III. If the contractor elects to use a flared Type A crashworthy end terminal, additional embankment as shown on the plans shall be provided at the contractor's expense.

Insert Sec 620.80 by to including the following:

SECTION 620.80 CONTRAST PAVEMENT MARKINGS

620.80.1 Description. This work shall consist of furnishing and installing black contrasting pavement marking for intermittent markings (skips), dotted lines and solid intersection lane lines on new, and newly ground concrete surfaces. This work shall be in accordance with Sec 620 and accompanying provisions except as modified herein

620.80.2 Material. The black contrast marking shall be compatible with the white pavement marking material specified in the plans.

620.80.3 Construction Requirements.

620.80.3.1 The Contrast markings shall be accomplished by placing the black pavement marking according to manufacturer's recommendations.

620.80.3.2 The white marking shall be centered within the black marking such that there will be a 1.5 inch border of black on both sides of the white marking. Tolerances for the width and length of the black and white markings shall be in accordance with Sec 620.2.4.2.

620.80.4 Basis of Payment. There will be no direct payment for compliance with the requirements of this provision.

Delete Sec 1048.10.1.1 and substitute the following:

1048.10.1.1 Application. Application shall be in accordance with the manufacturer's recommendations.

J. DBE PROGRAM REQUIREMENTS NJSP-15-41A

1.0 Description: Insert the following additional program provisions in the Disadvantaged Business Enterprise (DBE) Program Requirements of the General Provisions and Supplemental Specifications to Missouri Standard Specifications for Highway Construction.

13.6 Factors Used to Determine if a DBE Regular Dealer of Liquid Asphalt is Performing a CUF. The DBE must be responsible with respect to materials and supplies used on a contract perform all of the following, pursuant to 49 CFR § 26.55(c)(1) and 7 CSR 10-8.131:

- (a) Negotiating price.
- (b) Determining quality and quantity.
- (c) Ordering the material.
- (d) Paying for the material itself.
- (e) 30% of the work must be performed by the DBE's permanent employees (which does not include owner-operators or leased employees) or those hired by the DBE firm for the project from an independent source other than the prime contractor, such as a union hall. For at least 30% of the work the DBE's owned (not leased) equipment shall be used and the DBE must provide documentation that this owned equipment was used on the project as required by this provision.
- (f) For up to 70% of the remaining work the equipment used by the DBE must be by long term lease (at least one year) with another DBE or non-DBE but not the prime contractor. The DBE must have absolute priority over other businesses or entities to use the long term leased equipment and must display the name and identification number of the DBE.
- (g) The Contractor shall require DBE subcontractors to provide documentation in one of the following formats: bills of lading, hauling tickets, shippers manifest, and/or paid invoices. Regardless of the document format, the document(s) shall include the following information: name

of the carrier, full name of the driver, driver ID number(s), truck and tanker ID or VIN number, and reflect the contract number, job number, county and route.

The contract number, job number, county and route can be reported through a consignee number or lift number, as long as the DBE Subcontractor has provided the consignee number, or lift number, along with project specific information which shall include contract number, job number, county and route.

The documentation must be submitted and generated by the DBE Subcontractor and be printed on letterhead or other similar documentation outlining the contact information for the DBE Subcontractor. In addition the documentation shall indicate the quantity and amount invoiced to the prime contractor (Such as an invoice). **“MoDOT’s DBE Contractor/Subcontractor Project Trucker and Equipment List”** (Form 1) will be provided by MoDOT and shall be completed and submitted to MoDOT by the DBE Subcontractor or Liquid Asphalt Supplier before Asphalt Operations begin. The DBE Subcontractor shall report all trucks and tankers they currently own and all full time drivers that they employ, including all of the drivers numbers for each terminal the drivers pick up from. In addition the DBE Subcontractor shall include a list of “long term” leased equipment, along with drivers and drivers’ numbers to the DBE Subcontractor Project Trucker and Equipment List. The DBE Subcontractor shall attach copies of all current long term lease agreements to the DBE Subcontractor Project Trucker and Equipment List.

(h) DBE Trucking/Hauling regulations do not apply to regular dealers of liquid asphalt.

13.7 When a DBE Regular Dealer of Liquid Asphalt is Not Eligible for DBE Credit.

(a) “If its role is limited to that of an extra participant in a transaction, contract or project through which funds are passed in order to obtain the appearance of DBE participation.” 49 CFR § 26.55(c)(2)

(b) If the type of transaction does not allow the DBE subcontractor to perform one of the four required functions, such as a prime contractor deciding the price of a commodity to be supplied by the DBE, that transaction is not eligible for DBE credit.

(c) Work that is performed with trucks that are not owned nor under a lease of at least one year by the DBE will not be eligible for DBE credit.

(d) A lack of documentation verifying that at least one DBE owned (not leased) tractor and tanker/trailer was used to haul liquid asphalt on the project will result in no DBE credit given on that project.

13.8 This form will be completed by the inspector from the project office during the time of the project. MoDOT will use the *MoDOT DBE Job-Site Review CUF Determination Form* to verify CUF was performed on the project, a copy of which is available on the MoDOT Contractor Resource website.

K. CONTRACTOR RETAINED ITEMS

1.0 Description. The drop inlet frame and grate indicated on plans for removal from this project shall

become the property of the Contractor.

2.0 Basis of Payment. All costs incurred for complying with this provision shall be considered completely covered by the contract unit price for Item No. 202-20.10, Removal of Improvements.

L. DISPOSITION OF EXISTING ASPHALT PAVEMENT

1.0 Description. All asphalt pavements indicated for removal in the plans shall become property of the contractor and transported off the site and properly disposed of at a location furnished by the contractor.

2.0 Basis of Payment. Payment for removal and transportation of the asphalt pavement, as shown in the plans, shall be considered as and completely covered by the contract unit price for Item No. 202-20.10 "Removal of Improvements" per lump sum.

M. OPTIONAL PAVEMENT

1.0 Description. This work shall consist of a pavement composed of either Portland cement concrete or asphaltic concrete constructed on a prepared subgrade. This work shall be performed in accordance with the standard specifications and as shown on the plans or established by the engineer.

2.0 The quantities shown reflect the total square yards of pavement surface designated for each pavement type as computed and shown on the plans.

2.1 No additional payment will be made for asphaltic concrete mix quantities to construct the required 1:1 slope along the edge of the pavement.

2.2 No additional payment will be made for aggregate base quantities outside the limits of the final surface area or for 30° safety slope as computed and shown on the plans.

2.3 The grading shown on the plans was designed for the thicker pavement option. For projects with grading in the contract, there will be no adjustment of the earthwork quantities due to adjusting the roadway subgrade for optional pavements.

2.4 The contractor shall comply with Sections 401 through 403 for the asphalt option and Sections 501 and 502 for the concrete option.

3.0 Method of Measurement. The quantities of concrete pavement will be measured in accordance with Section 502.14. The quantities of asphaltic concrete pavement will be measured in accordance with Section 403.22.

4.0 Basis of Payment. The accepted quantity of the chosen option will be paid for by the contract unit bid price for Items 401-99.05, Optional Pavement – 9 ¾", per square yard and 401-99.05 Optional Pavement – 9 ¼", per square yard.

N. STORMWATER COMPLIANCE REQUIREMENTS JSP-15-04A

1.0 Description. The Contractor shall comply with the terms of the United States of America v. Missouri Highways and Transportation Commission Consent Decree (Consent Decree) that are identified as the responsibility of the Contractor or subcontractor, and with the terms of this provision. Viewing of the Consent Decree is available on the MoDOT Land Disturbance webpage under Contractor Resources, or by going to the web address www.modot.org/LD.

1.1 Applicability. The Consent Decree and this provision apply to any project that includes land disturbance of areas totaling greater than one (1) acre on the project site. The project site consists of all areas designated on the plans, including temporary and permanent easements. The Consent Decree and this provision do not apply to Contractor staging, plant, or borrow areas that are not located on MoDOT right of way (Off-site). The Contractor is responsible for obtaining its own separate land disturbance permit for Off-site areas. This provision is in addition to any other stormwater, environmental, and land disturbance requirements specified elsewhere in the contract.

2.0 Stormwater Training for Contractor Employees. The Contractor's on-site project manager, designated Water Pollution Control Manager (WPCM), as defined in Section 3.0, and WPCM delegate, shall complete MoDOT Stormwater Training prior to serving in those roles. If someone other than the Contractor's project manager is given the authority to manage the grading or erosion control operations, the project manager(s) for those operations shall also complete MoDOT Stormwater Training. MoDOT Stormwater Training is also required for any other person who the Contractor gives authority to take measures to prevent or minimize the consequences of non-compliance with the Stormwater requirements, as defined in Section 3.1(a) of this provision.

2.1 The Commission will provide MoDOT Stormwater Training to the Contractor employees specified in Section 2.0 at a location and time determined by MoDOT. There will be no fee for attending the training; however, the Contractor shall be responsible for all other cost related to the training, such as travel expenses, if necessary, and wages for its employees. The time to complete the training is anticipated to be no more than 6 hours. As long as the Consent Decree is in effect, MoDOT will provide periodic trainings at various locations around the state, as needed, to ensure contractors and bidders have the opportunity to maintain the number of WPCMs they need to comply with this provision.

2.2 Those who require MoDOT Stormwater Training per Section 2.0 shall complete the training prior to beginning any land disturbance work. Thereafter, training shall occur at least once every two (2) years. The training is not project-specific. Any Contractor employee who receives the training will be qualified to perform the WPCM duties on any MoDOT project for a period of two (2) years.

2.3 MoDOT will document the names and dates that contractor employees attend MoDOT Stormwater Training and will retain those records for the period of time specified in the Consent Decree. Duplicate record keeping by the contractor is not required.

3.0 Water Pollution Control Manager (WPCM). Prior to the Pre-Activity meeting for Grading/ Land Disturbance, the Contractor shall designate a Water Pollution Control Manager (WPCM) to fulfill the duties and responsibilities listed in Section 3.1 until final stabilization occurs. The Contractor's on-site project manager may also serve as the WPCM or that role may be assigned to another manager employed by the contractor or a subcontractor. The Contractor shall also maintain a WPCM delegate to

temporarily fulfill the WPCM duties in the absence of the primary WPCM (e.g. illness, vacation, other leave).

3.1 Duties of the WPCM:

- (a) Be familiar with Stormwater Requirements including the National Pollutant Discharge Elimination System (NPDES), the current MoDOT State Operating Permit for construction stormwater discharges/ land disturbance activities, the Project-specific Stormwater Pollution Prevention Plan (Project SWPPP), the Corps of Engineers Section 404 Permit, when applicable, the Consent Decree, and this provision. The Project SWPPP includes: a title page with project-specific information, the general SWPPP posted on the MoDOT land disturbance website, the Project Erosion & Sediment Control Plan, all applicable special provisions, and all applicable specifications and standard drawings;
- (b) Complete the stormwater training set forth in Section 2.0;
- (c) Attend the Pre-Activity for Grading/ Land Disturbance Meeting or, if hired after the meeting has occurred, be familiar with the conference decisions;
- (d) Review and sign the Project-specific SWPPP and all updates thereto within time periods set out in the Consent Decree;
- (e) Visit and review the project site for compliance with Stormwater Requirements at least once per week from the start of any grading operations until final stabilization is achieved and permit is closed;
- (f) Be authorized by the Contractor to supervise all work performed by the Contractor and subcontractors that involves compliance with Stormwater Requirements, including the authority to order work be stopped on a Project, implement MoDOT-directed changes in work related to Stormwater Requirements, and order the taking of, measures to cease, correct, prevent, or minimize the consequences of non-compliance with Stormwater Requirements;
- (g) Review and certify electronically each MoDOT inspection report for the Project within three (3) days of receiving each report to ensure it conforms with report requirements in the National Pollution Discharge Elimination System Stormwater (NPDES SW) Permit, Project SWPPP and the Consent Decree and ensure that all Stormwater Deficiencies noted on the report are corrected within the time required;
- (h) Recommend in writing within three (3) days of discovering any changes in site conditions and Best Management Practices (BMPs) that require an update to the Project-specific SWPPP; and
- (i) Be the point of contact relating to Stormwater Requirements and the Consent Decree between the Contractor, Subcontractors and MoDOT.

4.0 Pre-Activity Meeting for Grading/Land Disturbance and Required Hold Point. At each Project, a Pre-Activity Meeting for Grading/Land Disturbance shall be held prior to the start of any land disturbance and shall include a physical visit and review of the project site. Discussion items at the pre-activity meeting shall include a review of the project SWPPP, the planned order of grading operations, proposed areas of initial disturbance, identification of all necessary BMPs that shall be installed prior to

commencement of grading operations, and any issues relating to compliance with the Stormwater requirements that could arise in the course of construction activity at the project.

4.1 Contractor employees who shall attend the Pre-Activity Meeting for Grading/Land Disturbance include the WPCM for the Project and the person(s) designated the authority to manage the grading and erosion control operations.

4.2 Following the pre-activity meeting for Grading/land disturbance, and subsequent installation of the initial BMPs identified at the pre-activity meeting, a Hold Point shall occur prior to the start of any land disturbance operations to allow the engineer and WPCM the time needed to perform an on-site review of the installation of the BMPs to ensure compliance with the SWPPP is met. Land disturbance operations shall not begin until authorization is given by the engineer.

5.0 Compliance with the NPDES SW Permit and Project SWPPP. On all projects, the Contractor shall comply with all applicable Stormwater Requirements which are defined as, but are not limited to:

- (a) Consulting with the engineer on recommended design revisions to the Project SWPPP to accommodate the Contractor's staging plan, implementation, managing, and maintaining BMPs or other control measures to prevent or minimize sediment and other pollutants in stormwater runoff in accordance with contract specifications or any relevant manufacturer specifications and good engineering practices, including but not limited to the manuals (*Note: two manuals cited in the MoDOT permit are "Developing your stormwater pollution prevention plan: A guide for construction activities" and "Protecting Water Quality: A Field Guide to erosion, sediment and stormwater best management practices for development sites in Missouri"*) and any other applicable standards for sedimentation basins, stabilization, rock dams, brush checks, construction entrances, and other BMPs;
- (b) Installing all BMPs at the locations and relative times specified in the Project SWPPP; and
- (c) Complying with the Missouri Water Quality Standards and with effluent limitations in Section E.1 of the NPDES SW Permit. Measurement of effluent is not required except as specified in E.2.

5.1 Stormwater Deficiency Corrections. Per terms of the Consent Decree, Stormwater Deficiencies identified on the MoDOT Land Disturbance Inspection Report shall be corrected within 7 days of the inspection date to avoid stipulated penalties, except that more time might be granted by the engineer when weather or field conditions prohibit the corrective work. If the Contractor does not initiate corrective measures within 5 calendar days of the inspection date or any extended period granted by the engineer, all work shall cease on the project except for work to correct these deficiencies, unless otherwise allowed by the engineer. All impact costs related to this halting of work, including, but not limited to stand-by time for equipment, shall be borne by the Contractor. Work shall not resume until the engineer approves the corrective work.

6.0 Inspection Protocol. The Contractor and all subcontractors shall review and adhere to MoDOT's written Stormwater Inspection Protocol, found on the MoDOT Land Disturbance webpage (www.modot.org/LD). The Inspection Protocol is applicable to all Projects under the consent decree. The MoDOT Resident Engineer will serve the role of Stormwater Resident Engineer, or a delegate will be named in their absence.

6.1 Inspection Reports. MoDOT will provide one or more Environmental Construction Inspectors (ECI) to perform the weekly and post run-off inspections and other duties described in paragraph 17 of the Consent Decree. The ECI will enter the inspection reports into a web-based Stormwater Compliance database. The WPCM will have access to this database to view all report information, including any noted deficiencies, and to certify the report as required in Section 3.1 (g.). Automated email reminders of pending reports that need to be certified and for deficiencies that need to be corrected will be sent to the WPCM. The Contractor may designate other employees or subcontractor employees to have viewing access to this database and to receive the email reminders. Completion of MoDOT Stormwater Training is necessary in order to receive the email reminders. The WPCM and other users shall be equipped with an electronic device (desktop computer, laptop, tablet, smartphone, etc.) with a browser and internet access to connect to the database. The contractor shall be responsible for providing the electronic devices.

7.0 Stipulated Penalties. If the Contractor fails to comply fully and timely with the requirements of the Consent Decree, stipulated penalties will be assessed to the Commission. For matters under the Contractor's responsibility and control the following stipulated penalties will be assessed to the Contractor and MoDOT will withhold payment pursuant to the following:

Violation	Stipulated Penalty Amount
Failure to Designate or Maintain WPCM at each Project in Accordance with Section 3.0.	\$750 for the initial violation (each person not designated) and then \$750 for each fourteen (14) day period that person is not designated.
Failure to complete MoDOT Stormwater Training by an Individual Required to be Trained in Accordance with Section 2.0, such as the WPCM or Project Manager.	\$750 per person for each missed training. This \$750.00 per person violation shall continue to accrue for each fourteen (14) day period that the person fails to timely receive the applicable training
Failure of WPCM to Review and Certify an Inspection Report in Accordance with Inspection Protocol as set forth in Section 6.	\$250 per inspection report not reviewed or signed.
Failure to Comply with Any NPDES SW Permit or SWPPP Requirement.	\$1000 per violation for the first ten (10) days of the violation; \$2500 per violation for days 11-20; \$3500 per violation for days 21 and beyond.
Failure to Correct a Stormwater Deficiency Identified in a MoDOT Inspection Report, or Otherwise Discovered by the WPCM, within the Time Required by the NPDES SW Permit or SWPPP.	\$1000 per deficiency for the first ten (10) days after correction was required; \$2500 per deficiency for days 11-20 after correction was required; \$3500 per deficiency for days 21 and beyond after correction was required.

8.0 Information Collection and Retention. The EPA, its representatives and its agents shall have the right of entry into any facility covered by this Consent Decree, at all reasonable times, upon presentation of credential, to:

- (a) monitor the progress of activities required under the Consent Decree;
- (b) verify any data or information submitted to the United States in accordance with the terms of the Consent Decree;

- (c) obtain samples and, upon request, splits of any samples taken by MoDOT or its representatives, contractors, or consultants;
- (d) obtain documentary evidence, including photographs and similar data; and
- (e) assess MoDOT's compliance with the Consent Decree.

8.1 Until three (3) years after the termination of the Consent Decree, Contractors and the agents of the Contractors shall preserve all non-identical copies of all documents, records, or other information (including documents, records, or other information in electronic form) in its or its Contractors' or agents' possession or control, or that come into the Contractor's or agent's possession or control, and that relate to MoDOT's performance of its obligations under the Consent Decree or to the Contractor's performance of its obligations under the Consent Decree. This information-retention requirement shall apply regardless of any contrary corporate or institutional policies or procedures.

9.0 Basis of Payment. Payment for compliance with this provision will be made per week. All cost associated with the weekly on-site project reviews by the WPCM, compliance with this provision and the Consent Decree, including all other duties of the WPCM and delegate, and all expenses to attend training, will be considered fully covered under 806-99.28, Water Pollution Control Manager. Separate payment will be made for erosion and sediment control devices, and for permanent and temporary seeding and mulching, when payment for those items are provided elsewhere in the contract.

9.1 Method of Measurement. Measurement of the number of full weeks (7 days) will begin on the date of the first MoDOT Inspection Report following initial land disturbance and will continue until the engineer declares final stabilization has been achieved, except that no measurement will be made for any period of time past the contract completion date, or adjusted completion date, when liquidated damages are being assessed for failure of the Contractor to complete the work on time.

O. E-CONSTRUCTION

1.0 Description. e-Construction is a paperless construction administration delivery process that includes electronic submission of construction documents, approval of documents with digital signatures, and communication between stakeholders by mobile devices. e-Construction saves both time and money for all stakeholders involved, simplifies document storage, and eliminates waste of paper and other resources. This provision does not apply to the contract or other contract execution documents.

2.0 Document Submittals.

2.1 The contractor shall submit all required documents to MoDOT electronically, except as described in section 2.2 of this provision. Documents to be submitted electronically include, but are not limited to, Change Orders, Request to Subcontract Work (C-220), Project Payrolls, Progress Schedules, Value Engineering proposals, Safety Plans, Quality Plans, Pre-Construction conference submittals, etc. All documents shall be submitted in standard pdf format, except when otherwise directed by the engineer.

2.2 The Affidavit for Compliance with the Prevailing Wage Law and the Contractor's Affidavit Regarding Settlement of Claims (Form C-242) require a notarization and therefore, by law, must be submitted on paper.

2.3 The engineer will submit project documents to the contractor via email or through other secure file sharing sites, except that the Contractor Performance Questionnaire will be submitted by certified mail.

2.4 Documents that require multiple signatures, such as change orders, must include all required signatures on the original electronic document, without scanning.

2.5 Project Payrolls from subcontractors shall be digitally signed by the subcontractor. Payrolls shall be submitted as separate files per contractor per pay period.

3.0 Digital Signature.

3.1 All electronic documents that require signature, such as those listed in section 2.1, must be signed electronically. Scanning an ink-signed document is not considered a valid digital signature.

3.2 All users who are authorized to sign documents for the contractor shall submit their Digital Signature Certificate (Public Key .fdf file) to the Division of Construction prior to signing any documents. This file is used to validate the user's signature on documents. An authorization letter is also required for each person authorized to sign documents. A Digital Signature for Contractors Quick Reference Guide (QRG) is available on MoDOT's Engineering Policy Guide at <http://epg.modot.mo.gov/> (click on QRG in the left hand column).

4.0 Communication. The contractor shall be able to communicate and exchange information with MoDOT staff by email and mobile phone.

5.0 Basis of Payment. No payment will be made for compliance with this provision.

P. ELECTRONIC INFORMATION FOR BIDDER'S AUTOMATION JSP-05-05A

1.0 Electronic Information. Electronic information, consisting of survey and design information including but not limited to 3-dimensional design models, cross-section models, alignment data, and plan view geometry, does not constitute part of the bid or contract documents. This electronic information will be distributed with the cross-sections or upon the contractor's request. This information, used for project design and quantity estimation purposes, is provided for the bidder's use in automation of bid estimating, contractor furnishing staking, automated machine guidance and other construction methods if provided in the contract. This information shall not be considered a representation of actual conditions to be encountered during construction. Furnishing this information does not relieve a bidder or contractor from the responsibility of making an investigation of conditions to be encountered including, but not limited to site visits, and basing the bid on information obtained from these investigations, and the professional interpretations and judgment of the bidder or contractor. The bidder or contractor shall assume the risk of error if the information is used for any purposes for which the information was not intended. The Commission makes no representation as to the accuracy or reliability of the information, since the information may not be representative of the sealed contract documents. Any assumption the bidder or contractor may make from this electronic information is at the bidder or contractor's risk; none are intended by the Missouri Highways and Transportation Commission. The bidder or contractor assumes the sole risk of liability or loss if the bidder or contractor does rely on this electronic information to its detriment, delay or loss.

Q. CAPPING EXISTING MEDIAN DROP INLET

1.0 Description. The contractor will be required to alter an existing median drop inlet near the Lisletown cross over to accommodate the construction of the Westbound Acceleration lane. It is expected that the existing inlet and connecting drainage structures will need to be accessed in the future if alterations to Route 50 are made.

1.1 The contractor shall remove the existing frame and grate and cap the existing drop inlet using a thick metal plate or a concrete cover that will be of significant strength to support the proposed fill. The cap shall be placed in a stable manner and not damage the structure; to allow for future use and/or access to the drop inlet. The contractor may elect to backfill the drop inlet with compacted aggregate fill which could be easily excavated in the future. The adjoining drainage structure shall be blocked such that the fill material does not enter the culvert prior to backfilling. The method, or any alternatives chosen, shall be demonstrated to and approved by the engineer prior to initiating the capping process.

2.0 Basis of Payment. Payment for removal of the grate and frame and installation of the cap as indicated in the plans, shall be considered as and completely covered by the contract unit price for Item No. 202-20.10, "Removal of Improvements", per lump sum.

R. PAVEMENT CONSTRUCTION REQUIREMENTS

1.0 Description. The pavement options indicated in the plans require the pavement options to be constructed with a 2" Hot Mix Asphalt (HMA) overlay. It is expected, but not required, that the contractor will construct the final overlay concurrent with the paving operations on the combination project J5P3127.

1.1 The contractor is notified that the 2" HMA overlay for the pavements paid for in this project are included in the square yard price for various pavement types and not a separate pay item.

1.2 The optional construction of the bonded asphaltic concrete pavements shown in the typical sections will require a spray paver to be used in the overlay of the concrete base pavement. This work shall require the placement of a Polymer Modified Emulsion Membrane prior to the HMA overlay of the concrete pavement. The membrane shall be considered inclusive to and incidental to the optional pavement quantities by square yard.

S. BONDED ASPHALTIC CONCRETE PAVEMENT

1.0 Description. If the contractor chooses the concrete option for pavement construction, completion of the work shall include the placement a Polymer Modified Emulsion Membrane prior to a bituminous overlay of hot asphaltic concrete pavement. The Polymer Modified Emulsion Membrane shall be spray applied immediately prior to the application of the hot asphaltic concrete pavement so as to produce a homogeneous surface in accordance with Secs 401, 402, or 403.

2.0 Materials. The Polymer Modified Emulsion Membrane shall be in accordance with Sec 1015.20.6.2.

3.0 Construction Requirements. The asphaltic concrete pavement shall be placed in accordance with Secs 401, 402, or 403, except as modified herein.

3.1 Equipment. No wheel, track or other part of the paving machine or any hauling equipment shall come in contact with the Polymer Modified Emulsion Membrane before the asphaltic concrete pavement mixture is applied.

3.2 Application of Polymer Modified Emulsion Membrane.

3.2.1 The Polymer Modified Emulsion Membrane shall be sprayed at a temperature of 120 - 180°. The sprayer shall accurately and continuously monitor the application rate and provide a uniform coverage across the entire width to be overlaid. The target application rate of the asphalt emulsion membrane shall be 0.20 gallons per square yard. The Engineer may make adjustments to the application rate based upon the existing pavement surface conditions and the recommendations of the Polymer Modified Emulsion Membrane supplier; however, the application rate shall be within +/- 0.07 gallon per square yard of the target application rate.

3.2.2 The application rate of the Polymer Modified Emulsion Membrane shall be verified by dividing the volume (of Polymer Modified Emulsion Membrane used) by the area of paving for that day.

3.2.3 No water shall be added to the Polymer Modified Emulsion Membrane.

4.0 Method of Measurement. Measurement of the Polymer Modified Emulsion Membrane shall be based on the volume in gallons in accordance with Sec 1015.

5.0 Basis of Payment. The accepted quantity of Polymer Modified Emulsion Membrane shall be considered included in and completely covered by the various Optional Pavement pay items in the contract by the square yard.

T. ADDITIONAL MOBILIZATION FOR SEEDING NJSP-16-03

1.0 Description. This provision provides compensation for additional mobilization for seeding, as specified herein.

2.0 Additional Mobilization for Seeding. Additional mobilization to perform temporary or permanent seeding, beyond the initial occurrence, may be necessary as specified in Sec 806.50.2 and as required per terms of the SWPPP. Mobilization of all equipment, workers and materials necessary to perform seeding and mulching shall be considered included in this work.

2.1 Measurement of the number of occurrences authorized by the engineer to mobilize equipment onto the project to perform temporary or permanent seeding will be made per each occurrence, except for the initial occurrence and as specified herein. No measurement will be made for mobilization necessary to perform repair work to previously seeded areas or for mobilization necessary due to removal of equipment prior to completion of seeding all areas available for seeding, as determined by the engineer.

3.0 Basis of Payment. The accepted occurrences of Additional Mobilization for Seeding will be paid for under 618-99.02, ADDITIONAL MOBILIZATION FOR SEEDING, at a fixed unit price of \$600 per

each occurrence. Payment for the initial occurrence to mobilize for seeding, and any additional mobilization costs in excess of the fixed price, shall be considered completely covered under other items.

U. FERTILIZING, SEEDING AND MULCHING

1.0 Fertilizing shall conform to Sec. 801 and more specifically as follows:

<u>Item</u>	<u>Lbs. per Acre</u>
Nitrogen (N)	80
Phosphorus (P ₂ O ₅)	120
Potash (K ₂ O)	40
Lime	800

Statewide – All settings – within the first 30 feet (mow area)

Species	Pounds per Acre
Tall fescue	80 lbs.
Annual ryegrass	10 lbs.
Perennial ryegrass	5 lbs.
White clover	5 lbs.
Oats	10 lbs.
TOTAL	110 lbs.

Seed bed preparation and seeding by hand will be allowed.

3.0 All disturbed areas shall be mulched and conform to Section 802 and more specifically the contractor shall use vegetative mulch. Mulching by hand will be allowed.

4.0 Basis of Payment.


4.1 No direct payment will be made for liming, fertilizing or mulching seeded areas.

4.2 No direct payment will be made to the contractor for the above requirements. All costs incurred by the contractor for labor, equipment and materials in compliance with the above requirements shall be considered incidental to and completely covered by other pay items in the contract.

JOB SPECIAL PROVISIONS TABLE OF CONTENTS

(Job Special Provisions shall prevail over General Provisions whenever in conflict therewith.)

- A. General
- B. Contract Liquidated Damages
- C. Work Zone Traffic Management Plan
- D. Utilities
- E. Project Contact for Contractor/Bidder Questions
- F. Emergency Provisions and Incident Management
- G. Contractor Quality Control
- H. Supplemental Revisions
- I. DBE Program Requirements
- J. Contractor Retained Guardrail
- K. Disposition of Existing Signing
- L. Stormwater Compliance Requirements
- M. e-Construction
- N. Bonded Asphalt Concrete Pavement
- O. Sealing Treatment for Rumbles
- P. High Friction Surface Treatment
- Q. Clean Aggregate for Guardrail

 <p>THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.</p>	MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65102 Phone 1-888-275-6636
	If a seal is present on this sheet, JSP's have been electronically sealed and dated.
	JOB NUMBER: J5P3127 COLE COUNTY, MO DATE PREPARED: 09/22/16
	ADDENDUM DATE:
Only the following items of the Job Special Provisions (Roadway) are authenticated by this seal: All	

JOB
SPECIAL PROVISION

A. GENERAL - FEDERAL JSP-09-02B

1.0 Description. The Federal Government is participating in the cost of construction of this project. All applicable Federal laws, and the regulations made pursuant to such laws, shall be observed by the contractor, and the work will be subject to the inspection of the appropriate Federal Agency in the same manner as provided in Sec 105.10 of the Missouri Standard Specifications for Highway Construction with all revisions applicable to this bid and contract.

1.1 This contract requires payment of the prevailing hourly rate of wages for each craft or type of work required to execute the contract as determined by the Missouri Department of Labor and Industrial Relations, and requires adherence to a schedule of minimum wages as determined by the United States Department of Labor. For work performed anywhere on this project, the contractor and the contractor's subcontractors shall pay the higher of these two applicable wage rates. State Wage Rates, Information on the Required Federal Aid Provisions, and the current Federal Wage Rates are available on the Missouri Department of Transportation web page at www.modot.org under "Bidding". Effective Wage Rates will be posted 10 days prior to the applicable bid opening. These supplemental bidding documents have important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.

1.2 The following documents are available on the Missouri Department of Transportation web page at www.modot.org under "Business"; "Standards and Specifications". The effective version shall be determined by the letting date of the project.

General Provisions & Supplemental Specifications

Supplemental Plans to October 2016 Missouri Standard Plans
For Highway Construction

These supplemental bidding documents contain all current revisions to the published versions and have important legal consequences. It shall be conclusively presumed that they are in the bidder's possession, and they have been reviewed and used by the bidder in the preparation of any bid submitted on this project.

B. CONTRACT LIQUIDATED DAMAGES

1.0 Description. Liquidated Damages for failure or delay in completing the work on time for this contract shall be in accordance with Sec 108.8. The liquidated damages include separate amounts for road user costs and contract administrative costs incurred by the Commission.

2.0 Period of Performance. Prosecution of work is expected to begin on the date specified below in accordance with Sec 108.2. Regardless of when the work is begun on this contract, all work shall be completed on or before the date specified below. Completion by this date shall be in accordance with the requirements of Sec 108.7.1.

Notice to Proceed: March 6, 2017
Completion Date: October 31, 2017

2.1 Calendar Days. The count of calendar days will begin on the date the contractor starts any construction operations on the project.

Job Number	Calendar Days	Daily Road User Cost
J5P3056	54	\$3,200
J5P3127	54	\$3,200

3.0 Liquidated Damages for Contract Administrative Costs. Should the contractor fail to complete the work on or before the completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged contract administrative liquidated damages in accordance with Sec 108.8 in the amount of **\$1,000** per calendar day for each calendar day, or partial day thereof, that the work is not fully completed. For projects in combination, these damages will be charged in full for failure to complete one or more projects within the above specified completion date or calendar days.

4.0 Liquidated Damages for Road User Costs. Should the contractor fail to complete the work on or before the completion date specified in Section 2.0, or within the number of calendar days specified in Section 2.1, whichever occurs first, the contractor will be charged road user costs in accordance with Sec 108.8 in the amount specified in Section 2.1 for each calendar day, or partial day thereof, that the work is not fully completed. These damages are in addition to the contract administrative damages and any other damages as specified elsewhere in this contract.

C. WORK ZONE TRAFFIC MANAGEMENT PLAN

1.0 Description. Work zone traffic management shall be in accordance with applicable portions of Division 100 and Division 600 of the Standard Specifications, and specifically as follows.

1.1 Work Zone Specialist (WZS). The Traffic Management Plan shall name an individual, either employed by the contractor or hired by the contractor, to act as the Work Zone Specialist (WZS) throughout the entirety of the project. Any change in personnel for the WZS shall be submitted in written form to the engineer. This individual will be a trained Work Zone Specialist in accordance with Standard Specifications Section 616.3.3 and will be directly involved with daily traffic management and traffic management planning. It will be the responsibility of the WZS to coordinate daily traffic management with the engineer. The WZS shall maintain daily contact with the engineer either on-site or via telecommunication.

1.2 Maintaining Work Zones and Work Zone Reviews. The WZS shall maintain work zones on a daily basis to ensure safety to the traveling public and the workers; this includes long term work zones that have devices and/or roadway conditions that need to be maintained. If the engineer or a designated MoDOT employee (identified at the preconstruction meeting) notifies the WZS of any safety or traffic delay concerns in the work zone, the WZS shall promptly inspect and work to provide a solution to correct the situation. The WZS shall have personnel reviewing traffic control devices daily and any temporary lane drop traffic control devices for initial set up and during the operation. Missing, damaged or over-turned traffic control devices shall typically be corrected without the need for direction

by the engineer. The WZS is responsible to assure all traffic control devices are maintained in accordance with EPG standards. The WZS is responsible to ensure the work zone is operated within the hours specified by the engineer and will not deviate from the specified hours without prior approval of the engineer. The WZS is responsible to manage work zone delay in accordance with these project provisions. The WZS and engineer shall submit one joint weekly technical review of work zone operations identifying any concerns present and the corrective actions taken. Reviews may be subjected to unannounced inspections by the engineer to corroborate the validity of the ratings. The engineer and WZS will be notified of the results.

1.3 Work Zone Conflict Resolution. Any conflict resolution shall be in accordance with Standard Specifications Section 616.4. Failure to make corrections on time may result in the engineer suspending work. The suspension will be non-excusable and non-compensable regardless if road user costs are being charged for closures.

2.0 Traffic Management Schedule.

2.1 Traffic management schedules shall be submitted to the engineer for review prior to the start of work and prior to any revisions to the traffic management schedule. The traffic management schedule shall include the proposed traffic control measures, the hours traffic control will be in place, and work hours.

2.2 The contractor shall request permission at least two working days prior to lane closures or shifting traffic onto detours, and 14 calendar days prior to the imposition of height, width or weight restrictions. This is to ensure closures do not conflict with other work within the zone of influence and the work zone information on the MoDOT's website can remain real-time.

2.3 The engineer shall be notified as soon as practical of any postponement due to weather, material or other circumstances.

2.4 In order to ensure minimal traffic interference, the contractor shall schedule lane closures for the absolute minimum amount of time required to complete the work. Lanes shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed lane is opened to traffic.

2.5 Traffic Congestion. The contractor shall, upon approval of the engineer, take proactive measures to reduce traffic congestion in the work zone. The contractor shall immediately implement appropriate mitigation strategies whenever traffic congestion reaches an excess of **12 minutes** to prevent congestion from escalating beyond this delay threshold. If disruption of the traffic flow occurs and traffic is backed up in queues equal to or greater than the delay time threshold listed above then the contractor shall immediately review the construction operations which contributed directly to disruption of the traffic flow and make adjustments to the operations to prevent the queues from reoccurring. Traffic delays may be monitored by physical presence on site or by utilizing real-time travel data through the work zone that generate text and/or email notifications where available. The engineer monitoring the work zone may also notify the contractor of delays that require prompt mitigation. The contractor may work with the engineer to determine what other alternative solutions or time periods would be acceptable. The contractor may refer to the Work Zone Analysis Spreadsheet found in the electronic deliverables under the MoDOT Online Plans Room for detailed information on traffic delays.

2.5.1 Traffic Safety.

2.5.1.1 Where traffic queues routinely extend to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway, the contractor shall extend the advance warning area, as approved by the engineer.

2.5.1.2 When a traffic queue extends to within 1000 feet of the ROAD WORK AHEAD, or similar, sign on a divided highway or to within 500 feet of the ROAD WORK AHEAD, or similar, sign on an undivided highway due to non-recurring congestion, the contractor shall deploy a means of providing advance warning of the traffic congestion, as approved by the engineer. The warning location shall be no less than 1000 feet and no more than 0.5 mile in advance of the end of the traffic queue on divided highways and no less than 500 feet and no more than 0.5 mile in advance of the end of the traffic queue on undivided highways.

3.0 Work Hour Restrictions.

3.1 There are six major holiday periods shown below. All lanes shall be scheduled to be open to traffic during these holiday periods, from 12:00 noon on the last working day proceeding the holiday until 9:00 a.m. on the first working day subsequent to the holiday.

Memorial Day
Independence Day
Labor Day
Thanksgiving
Christmas
New Year's Day

3.2 The contractor shall not perform any construction operation on the roadway, including the hauling of material within the project limits, during restricted periods, holiday periods or other special events specified in the contract documents.

3.3 The contractor shall be aware that traffic volume data indicates construction operations on the roadbed between the following hours will likely result in traffic queues greater than 15 minutes. Based on this, the contractors operations will be restricted accordingly unless it can be successfully demonstrated the operations can be performed without a 15 minute queue in traffic. It shall be the responsibility of the engineer to determine if the above work hours may be modified. Working hours for evenings, weekends and holidays will be determined by the engineer.

Route 50 Eastbound:
3:00 p.m. - 6:00 p.m. Monday through Friday

Route 50 Westbound:
6:00 a.m. - 8:00 a.m. Monday through Friday

3.5 The contractor shall not alter the start time, ending time, or a reduction in the number of through lanes of traffic or ramp closures without advance notification and approval by the engineer. The only work zone operation approved to begin 30 minutes prior to a reduction in through traffic lanes or ramp closures is the installation of traffic control signs. Should lane closures be placed or remain in place, prior to the approved starting time or after the approved ending time, the Commission, the traveling

public, and state and local police and governmental authorities will be damaged in various ways, including but not limited to, increased construction administration cost, potential liability, traffic and traffic flow regulation cost, traffic congestion and motorist delays, with a resulting cost to the traveling public. These damages are not easily computed or quantified. Therefore, the contractor will be charged with liquidated damages specified in the amount of **\$1,000 per 15 minute increment** for each 15 minutes that the temporary lane closures are in place and not open to traffic in excess of the limitation as specified elsewhere in this special provision. It shall be the responsibility of the engineer to determine the quantity of unapproved closure time.

3.5.1 The said liquidated damages specified will be assessed regardless if it would otherwise be charged as liquidated damages under the Missouri Standard Specification for Highway Construction, as amended elsewhere in this contract.

4.0 Detours and Lane Closures.

4.1 The contractor shall provide changeable message signs (CMS) notifying motorists of future traffic disruption and possible traffic delays one week before traffic is shifted to a detour or prior to lane closures. The CMS shall be installed at a location as approved or directed by the engineer. The CMS shall be capable of communication with the Transportation Management Center (TMC), if applicable, prior to installation on right of way. All messages planned for use in the work zone shall be approved and authorized by the engineer or its designee prior to deployment. Permanent dynamic message signs (DMS) owned and operated by MoDOT may also be used to provide warning and information for the work zone. Permanent DMS shall be operated by the TMC, and any messages planned for use on DMS shall be approved and authorized by the TMC at least 72 hours in advance of the work.

4.2 At least one lane of traffic in each direction shall be maintained at all times except for brief intervals of time required when the movement of the contractor's equipment will seriously hinder the safe movement of traffic. Periods during which the contractor will be allowed to interrupt traffic will be designated by the engineer.

5.0 Basis of Payment. No direct payment will be made to the contractor to recover the cost of equipment, labor, materials or time required to fulfill the above provisions, unless specified elsewhere in the contract document. All authorized changes in the traffic control plan shall be provided for as specified in Standard Specifications Section 616.

D. UTILITIES

1.0 For informational purposes only, the following is a list of names, addresses, and telephone numbers of the known utility companies in the area of the construction work for this improvement:

<u>Utility Name</u>	<u>Known Required Adjustment</u>	<u>Type</u>
Ameren Missouri Electric 1310 Industrial Drive Jefferson City, MO 65109 Contact: Brody Ash Phone: (573) 681-7528 Email: bash@ameren.com	None – see 1.1.1	Electric
Ameren Missouri Gas 1310 Industrial Drive Jefferson City, MO 65109 Contact: Jake Martin Phone: (573) 681-7550 Email: Jmartin7@ameren.com	None	Gas
AT&T Distribution 4 South Oak Street Eldon, MO 65026 Contact: Brian Maloney Phone: (573) 392-9829 Email: Wm5803@att.com	None – see 1.1.1	Communications
Centurylink 3456 North Ten Mile Drive Jefferson City, MO 65109 Contact: Allen Groner Phone: (573) 634-1686 Email: allen.t.groner@centurylink.com	None – see 1.1.1	Communications
City of Jefferson – Wastewater 320 East McCarty Jefferson City, MO 65101 Contact: Eric Seaman Phone: (573) 634-6410 Email: ESeaman@jeffcitymo.org	None	Sewer
City of Taos 3909 Countryside Park Jefferson City, MO 65101 Phone: (573) 395-4084	None	Sewer

<p>Cole County PWSD#4 7712 Route M Jefferson City, MO 65101 Contact: Will Humphrey Phone: (573) 395-4578 Email: will@colepwsd4.com</p>	<p>None</p>	<p>Water</p>
<p>MoDOT Signals and Lighting P.O. Box 718 Jefferson City, MO 65102 Contact: Kevin Eggemeyer Phone: (573) 526-3207 Email: Kevin.eggemeyer@modot.mo.gov</p>	<p>None – see 1.1.2</p>	<p>Electric</p>
<p>Phillips 66 Pipeline 2116 Idlewood Road Jefferson City, MO 65109 Contact: Kevin Jungmeyer Phone: (573) 636-4984 Email: k.d.jungmeyer@p66.com</p>	<p>None – see 1.1.3</p>	<p>Gas</p>
<p>Three Rivers Electric Cooperative 1324 E. Main Street Linn, MO 65051 Contact: Ted Neuner Phone: (573) 644-9000 Email: TNeuner@threeriverselectric.com</p>	<p>None – see 1.1.1</p>	<p>Electric</p>
<p>Sho-Me Technologies 301 W. Jackson P.O. Box D Marshfield, MO 65706 Contact: Eric Wutke Phone: (417) 859-2615 Email: ewutke@shometech.com</p>	<p>None - see 1.1.1</p>	<p>Communications</p>
<p>Suddenlink Communications Contact: Brent Lovell Phone: (816) 646-3438 Email: Brent.lovell@suddenlink.com</p>	<p>None</p>	<p>Communications</p>

1.1 Known Utility Facilities: The Contractor shall be aware there are numerous utilities present along this corridor. The extents of the utility conflicts are unknown. However if conflicts are encountered the Contractor shall be required to move their operation to another location until the utility can be relocated or the Engineer determines another course of action. There shall be no delay claims until such time the Contractor has no place to work except in areas of utility conflict and as approved by the engineer. The contractor shall be proactive in the discovery of utility conflicts. The contractor is recommended, after award of the project, to have all utilities marked along the project to visually see

where conflicts may occur. Any conflicts discovered and cleared before construction begins will help the contractor's progress on the project. MoDOT utilities staff will assist in relocation of utilities if necessary. There will be no direct pay for compliance to the above specification.

1.1.1 Several utility companies listed above have aerial utility lines in the project limits. These facilities will not be relocated; therefore the contractor shall use caution to not disturb the aerial utility lines with their construction activities. The contractor shall be responsible for any damage to the aerial utility lines in the project limits. There will be no direct pay for compliance to the above specification.

1.1.2 MoDOT has facilities along Route 50 near the Militia Drive interchange. The lighting facilities include pull boxes and conduit that supply power to overhead lighting along Militia Drive. The conduit crosses under Route 50 north and south of the Militia Drive overpass bridge. The MoDOT facilities shall be Missouri One-Call located prior to any guardrail placement or pavement repair in the area. The Contractor shall use caution and not disturb these facilities. The contractor shall be responsible for any damage to the underground utility lines in the project limits. There will be no direct pay for compliance to the above specification.

1.1.3 Phillips 66 Pipeline has an underground gas line that crosses under Route 50, one mile west of the Route M/J Interchange. The contractor shall not perform any guardrail work or pavement repair near the pipeline without a representative of the pipeline on site. The contractor shall use extra caution within these areas to not disturb the pipeline. The contractor shall be responsible for any damage to the gas pipeline underground facilities. There will be no direct pay for compliance to the above specification.

1.2 The contractor agrees that any effects of the presence of the utilities, their relocation, contractor's coordination of work with the utilities and any delay in utility relocation shall not be compensable as a suspension of work, extra work, a change in the work, as a differing site condition or otherwise including but, without limitation, delay, impact, incidental or consequential damages. The contractor's sole remedy for the effects of the presence of utilities, delay in their relocation or any other effects shall be an excusable delay as provided in [Sec 105.7.6](#). The contractor waives, for itself, its subcontractors and suppliers the compensability of the presence of utilities, delay in their relocation and any cost to the contractor, it's subcontractors and suppliers in any claim or action arising out of or in relation to the work under the contract.

1.3 The contractor shall be solely responsible and liable for incidental and consequential damage to any utility facilities or interruption of the service caused by it or its subcontractors operation. The contractor shall hold and save harmless the Commission from damages to any utility facilities interruption of service by it or its subcontractor's operation.

E. PROJECT CONTACT FOR CONTRACTOR/BIDDER QUESTIONS

All questions concerning this project during the bidding process shall be forwarded to the project contact listed below.

Bruce Green, Project Contact
MoDOT - Central Missouri District
1511 Missouri Blvd., P.O. Box 718
Jefferson City, Missouri 65102

Telephone Number 573-751-7688
Email: Bruce.Green@modot.mo.gov

All questions concerning the bid document preparation can be directed to the Central Office – Design at (573) 751-2876.

F. EMERGENCY PROVISIONS AND INCIDENT MANAGEMENT

1.0 The contractor shall have communication equipment on the construction site or immediate access to other communication systems to request assistance from the police or other emergency agencies for incident management. In case of traffic accidents or the need for police to direct or restore traffic flow through the job site, the contractor shall notify police or other emergency agencies immediately as needed. The resident engineer's office shall also be notified when the contractor requests emergency assistance.

2.0 In addition to the 911 emergency telephone number for ambulance, fire or police services, the following agencies may also be notified for accident or emergency situation within the project limits.

Missouri Highway Patrol (Troop F): 573-751-1000 (*55 Cell)	
Cole County Sheriff	573-634-9160
Jefferson City Police	573-634-6400
Jefferson City Fire Depart.	573-634-6401

2.1 This list is not all inclusive. Notification of the need for wrecker or tow truck services will remain the responsibility of the appropriate police agency.

2.2 The contractor shall notify enforcement and emergency agencies before the start of construction to request their cooperation and to provide coordination of services when emergencies arise during the construction at the project site. When the contractor completes this notification with enforcement and emergency agencies, a report shall be furnished to the engineer on the status of incident management.

3.0 No direct pay will be made to the contractor to recover the cost of the communication equipment, labor, materials or time required to fulfill the above provisions.

G. CONTRACTOR QUALITY CONTROL NJSP-15-42

1.0 The contractor shall perform Quality Control (QC) testing in accordance with the specifications and as specified herein. The contractor shall submit a Quality Control Plan (QC Plan) to the engineer for approval that includes all items listed in Section 2.0, prior to beginning work.

2.0 Quality Control Plan.

- (a) The name and contact information of the person in responsible charge of the QC testing.

- (b) A list of the QC technicians who will perform testing on the project, including the fields in which they are certified to perform testing.
- (c) A proposed independent third party testing firm for dispute resolution, including all contact information.
- (d) A list of Hold Points, when specified by the engineer.
- (e) The MoDOT Standard Inspection and Testing Plan (ITP). This shall be the version that is posted at the time of bid on the MoDOT website (www.modot.org/quality).

3.0 Quality Control Testing and Reporting. Testing shall be performed per the test method and frequency specified in the ITP. All personnel who perform sampling or testing shall be certified in the MoDOT Technician Certification Program for each test that they perform.

3.1 Reporting of Test Results. All QC test reports shall be submitted as soon as practical, but no later than the day following the test. Test data shall be immediately provided to the engineer upon request at any time, including prior to the submission of the test report. No payment will be made for the work performed until acceptable QC test results have been received by the engineer and confirmed by QA test results.

3.1.1 Test results shall be reported on electronic forms provided by MoDOT. Forms and Contractor Reporting Excel2Oracle Reports (CRE2O) can be found on the MoDOT website. All required forms, reports and material certifications shall be uploaded to a Microsoft SharePoint® site provided by MoDOT, and organized in the file structure established by MoDOT.

3.2 Non-Conformance Reporting. A Non-Conformance Report (NCR) shall be submitted by the contractor when the contractor proposes to incorporate material into the work that does not meet the testing requirements or for any work that does not comply with the contract terms or specifications.

3.2.1 Non-Conformance Reporting shall be submitted electronically on the Non-Conformance Report form provided on the MoDOT Website. The NCR shall be uploaded to the MoDOT SharePoint® site and an email notification sent to the engineer.

3.2.2 The contractor shall propose a resolution to the non-conforming material or work. Acceptance of a resolution by the engineer is required before closure of the non-conformance report.

4.0 Work Planning and Scheduling.

4.1 Two-week Schedule. Each week, the contractor shall submit to the engineer a schedule that outlines the planned project activities for the following two-week period. The two-week schedule shall detail all work and traffic control events planned for that period and any Hold Points specified by the engineer.

4.2 Weekly Meeting. When work is active, the contractor shall hold a weekly project meeting with the engineer to review the planned activities for the following week and to resolve any outstanding issues. Attendees shall include the engineer, the contractor superintendent or project manager and any foreman leading major activities. This meeting may be waived when, in the opinion of the engineer, a meeting is not necessary. Attendees may join the meeting in person, by phone or video conference.

4.3 Pre-Activity Meeting. A pre-activity meeting is required in advance of the start of each new activity, except when waived by the engineer. The purpose of this meeting is to review construction

details of the new activity. At a minimum, the discussion topics shall include: safety precautions, QC testing, traffic impacts, and any required Hold Points. Attendees shall include the engineer, the contractor superintendent and the foreman who will be leading the new activity. Pre-activity meetings may be held in conjunction with the weekly project meeting.

4.4 Hold Points. Hold Points are events that require approval by the engineer prior to continuation of work. Hold Points occur at definable stages of work when, in the opinion of the engineer, a review of the preceding work is necessary before continuation to the next stage.

4.4.1 A list of typical Hold Point events is available on the MoDOT website. Use of the Hold Point process will only be required for the project-specific list of Hold Points, if any, that the engineer submits to the contractor in advance of the work. The engineer may make changes to the Hold Point list at any time.

4.4.2 Prior to all Hold Point inspections, the contractor shall verify the work has been completed in accordance with the contract and specifications. If the engineer identifies any corrective actions needed during a Hold Point inspection, the corrections shall be completed prior to continuing work. The engineer may require a new Hold Point to be scheduled if the corrections require a follow-up inspection. Re-scheduling of Hold Points require a minimum 24-hour advance notification from the contractor unless otherwise allowed by the engineer.

5.0 Quality Assurance Testing and Inspection. MoDOT will perform quality assurance testing and inspection of the work, except as specified herein. The contractor shall utilize the inspection checklists provided in the ITP as a guide to minimize findings by MoDOT inspection staff. Submittal of completed checklists is not required, except as specified in 5.1.

5.1 Inspection and testing required in the production of concrete for the project shall be the responsibility of the contractor. Submittal of the 501 Concrete Plant Checklist is required.

6.0 Basis of Payment. No direct payment will be made for compliance with this provision.

H. SUPPLEMENTAL REVISIONS JSP-09-01U

Insert Sec 109.15, Sec 109.16 and Sec 109.17, subsequent section renumbered accordingly:

109.15 Seal Coat Price Index. Adjustments will be made to the payments due the contractor for Seal Coat placed in accordance with Sec 409 of the Standard Specifications. Adjustments will be calculated in accordance with Asphalt Cement Price Index of the General Provisions, except as defined herein.

109.15.1 Basis of Payment. To determine the adjustment for any material specified in this provision the following formula will be used.

$$A = B \times (0.68 \times 8.58/2000) \times (D - E)$$

Where:

- A = adjustment for Seal Coat placed during the index period
- B = gallons of seal coat placed during the index period
- D = average index price at the beginning of the period
- E = average index price at the time of bid

0.68 = factor to reduce volume of emulsion to AC only
(use average specific gravity of 1.03 for seal coat)

109.15.2 Optional. This provision is optional. If the bidder wishes to be bound by this provision, the bidder shall execute the acceptance form in the Bid for the Asphalt Cement Price Index. Acceptance of this provision will apply to both the Asphalt Cement Price Index and Seal Coat Price Index. Failure by the bidder to execute the acceptance form will be interpreted to mean election to not participate in the Asphalt Cement Price Index or Seal Coat Price Index.

109.16 Asphalt Underseal Price Index. Adjustments will be made to the payments due the contractor for Asphalt underseal placed in accordance with Sec 625 of the Standard Specifications. Adjustments will be calculated in accordance with Asphalt Cement Price Index of the General Provisions, except as defined herein.

109.16.1 Basis of Payment. To determine the adjustment for any material specified in this provision the following formula will be used.

$$A = B \times (8.66/2000) \times (D - E)$$

Where: A = adjustment for asphalt underseal placed during the index period
B = gallons of asphalt underseal placed during the index period
D = average index price at the beginning of the period
E = average index price at the time of bid
(use average specific gravity of 1.04 for underseal)

109.16.2 Optional. This provision is optional. If the bidder wishes to be bound by this provision, the bidder shall execute the acceptance form in the Bid for the Seal Coat Price Index. Failure by the bidder to execute the acceptance form will be interpreted to mean election to not participate in the Seal Coat Price Index.

109.17 Polymer Modified Emulsion Membrane Price Index. Adjustments will be made to the payments due the contractor for Polymer Modified Emulsion Membrane placed in accordance with Sec 413.30. Adjustment will be calculated in accordance with the Supplemental Asphalt Price Adjustment except as defined herein.

109.17.1 Basis of Payment. To determine the adjustment for any material specified in this provision the following formula will be used.

$$A=B \times (0.9/2000) \times (D - E)$$

Where: A = adjustment for membrane placed during the index period
B = square yards of membrane placed during the index period
D = average index price at the beginning of the period
E = average index price at time of bid

109.17.2 Optional. This provision is optional. If the bidder wishes to be bound by the provision, the bidder shall execute the acceptance form in the Bid for Polymer Modified Emulsion Membrane Price Index. Failure by the bidder to execute the acceptance form will be interpreted to mean election not to participate in the Polymer Modified Emulsion Membrane Price Index.

Delete Sec 403.2.5.2 and substitute the following:

403.2.5.2 Fibers. A fiber additive shall be used as a stabilizer in SMA Mixtures. Fibers shall be uniformly distributed by the end of the plant mixing process. The dosage rate for fibers shall be no less than 0.3 percent by weight of the total mixture for cellulose and no less than 0.4 percent by weight for mineral fibers.

Delete Sec 407 in its entirety and substitute the following:

407.1 Description. This work shall consist of preparing and treating an existing bituminous or concrete surface with bituminous material, in accordance with these specifications.

407.2 Material. All material shall be in accordance with Division 1000, Material Details, and specifically as follows:

Item	Section
Emulsified Asphalt or PG Liquid Asphalt	1015

407.3 Equipment. The contractor shall provide a system for heating and applying the bituminous material. The system shall be designed, equipped, maintained and operated such that emulsified asphalt or liquid asphalt, at even heat, may be applied uniformly on variable widths of surface up to 15 feet with uniform pressure and an allowable variation from any specified rate of ± 0.01 gallon per square yard. The system shall include a calibrated tank and a thermometer for measuring temperature of tank contents. The system shall be equipped with instrumentation that continuously verifies application rates. The calibration of the system shall be approved by the engineer prior to use, and the contractor shall furnish all equipment, material and assistance if calibration is required.

407.4 Construction Requirements.

407.4.1 Preparation of Surface. The existing surface shall be free of all dust, loose material, grease or other foreign material at the time the tack is applied. Any excess bituminous surface mixture or bituminous joint material will be removed by MoDOT without cost to the contractor before the tack is applied.

407.4.2 Application. Asphalt emulsion or PG liquid asphalt shall be applied uniformly with a pressure distributor at the minimum rates indicated in the following table. No dilution of the emulsified asphalt material shall be allowed. The tack coat material shall be heated at the time of application to a temperature in accordance with Sec 1015. The tack coat shall be properly cured and the tacked surface shall be clean of all dirt before the next course is placed.

Tack Coat Application Rates	
Surface Type	Minimum Application Rate (Gal. per sq. yd.)
New Asphalt Pavement	0.05
Existing Asphalt or Concrete Pavement	0.08

407.4.3 Tack. The tack coat shall be applied in such a manner as to cause the least inconvenience to traffic and to permit one-way traffic without tracking of asphalt emulsion. All exposed tack coat shall be covered with bituminous mixture prior to opening to traffic.

407.5 Method of Measurement. Measurement of asphalt emulsion to the nearest 10 gallons will be made in accordance with Sec 1015.

407.6 Basis of Payment. The accepted quantity of tack coat will be paid for at the contract unit price.

Amend Sec 620.10.3.1.1.1, and 620.10.3.1.1.2 to include the following:

620.10.3.1.1.1 Type 1 Preformed Marking Tape in Lieu of Type 2. Type 1 Preformed Pavement Marking Tape will be allowed in lieu of Type 2 Preformed Marking Tape (Grooved) at no additional cost to the Commission. This work shall be in accordance with Sec 620 and accompanying provisions except as modified herein.

620.10.3.1.1.2 Construction Requirements. Grooving will not be required when Type 1 Preformed Marking Tape is used.

Delete Sec 606.30.4 & 606.30.5 and substitute the following:

606.30.4 Method of Measurement. Measurement for crashworthy end terminals will be made for each unit assembled, installed and complete in place. Grading for crashworthy end terminals will be measured in accordance with [Sec 203](#) when roadway and drainage excavation is included in the contract, otherwise grading will be measured in accordance with Shaping Slopes, Class III or as directed on plans.

606.30.5 Basis of Payment. The accepted quantities of Type A, B C, D and E crashworthy end terminals, complete in place, will be paid for at the contract unit price. Payment will be considered full compensation for complete installation including any backup assemblies or other items necessary for proper installation of the end terminal or crash cushion as required. Grading for end terminals will be paid for at the contract unit price for roadway and drainage excavation if included in the contract; otherwise it will be paid for as Shaping Slopes, Class III. If the contractor elects to use a flared Type A crashworthy end terminal, additional embankment as shown on the plans shall be provided at the contractor's expense.

Insert Sec 620.80 by to including the following:

SECTION 620.80 CONTRAST PAVEMENT MARKINGS

620.80.1 Description. This work shall consist of furnishing and installing black contrasting pavement marking for intermittent markings (skips), dotted lines and solid intersection lane lines on new, and newly ground concrete surfaces. This work shall be in accordance with Sec 620 and accompanying provisions except as modified herein

620.80.2 Material. The black contrast marking shall be compatible with the white pavement marking material specified in the plans.

620.80.3 Construction Requirements.

620.80.3.1 The Contrast markings shall be accomplished by placing the black pavement marking according to manufacturer's recommendations.

620.80.3.2 The white marking shall be centered within the black marking such that there will be a 1.5 inch border of black on both sides of the white marking. Tolerances for the width and length of the black and white markings shall be in accordance with Sec 620.2.4.2.

620.80.4 Basis of Payment. There will be no direct payment for compliance with the requirements of this provision.

Delete Sec 1048.10.1.1 and substitute the following:

1048.10.1.1 Application. Application shall be in accordance with the manufacturer's recommendations.

I. DBE PROGRAM REQUIREMENTS NJSP-15-41A

1.0 Description: Insert the following additional program provisions in the Disadvantaged Business Enterprise (DBE) Program Requirements of the General Provisions and Supplemental Specifications to Missouri Standard Specifications for Highway Construction.

13.6 Factors Used to Determine if a DBE Regular Dealer of Liquid Asphalt is Performing a CUF. The DBE must be responsible with respect to materials and supplies used on a contract perform all of the following, pursuant to 49 CFR § 26.55(c)(1) and 7 CSR 10-8.131:

- (a) Negotiating price.
- (b) Determining quality and quantity.
- (c) Ordering the material.
- (d) Paying for the material itself.
- (e) 30% of the work must be performed by the DBE's permanent employees (which does not include owner-operators or leased employees) or those hired by the DBE firm for the project from an independent source other than the prime contractor, such as a union hall. For at least 30% of the work the DBE's owned (not leased) equipment shall be used and the DBE must provide documentation that this owned equipment was used on the project as required by this provision.
- (f) For up to 70% of the remaining work the equipment used by the DBE must be by long term lease (at least one year) with another DBE or non-DBE but not the prime contractor. The DBE must have absolute priority over other businesses or entities to use the long term leased equipment and must display the name and identification number of the DBE.
- (g) The Contractor shall require DBE subcontractors to provide documentation in one of the following formats: bills of lading, hauling tickets, shippers manifest, and/or paid invoices. Regardless of the document format, the document(s) shall include the following information: name

of the carrier, full name of the driver, driver ID number(s), truck and tanker ID or VIN number, and reflect the contract number, job number, county and route.

The contract number, job number, county and route can be reported through a consignee number or lift number, as long as the DBE Subcontractor has provided the consignee number, or lift number, along with project specific information which shall include contract number, job number, county and route.

The documentation must be submitted and generated by the DBE Subcontractor and be printed on letterhead or other similar documentation outlining the contact information for the DBE Subcontractor. In addition the documentation shall indicate the quantity and amount invoiced to the prime contractor (Such as an invoice). **“MoDOT’s DBE Contractor/Subcontractor Project Trucker and Equipment List”** (Form 1) will be provided by MoDOT and shall be completed and submitted to MoDOT by the DBE Subcontractor or Liquid Asphalt Supplier before Asphalt Operations begin. The DBE Subcontractor shall report all trucks and tankers they currently own and all full time drivers that they employ, including all of the drivers numbers for each terminal the drivers pick up from. In addition the DBE Subcontractor shall include a list of “long term” leased equipment, along with drivers and drivers’ numbers to the DBE Subcontractor Project Trucker and Equipment List. The DBE Subcontractor shall attach copies of all current long term lease agreements to the DBE Subcontractor Project Trucker and Equipment List.

(h) DBE Trucking/Hauling regulations do not apply to regular dealers of liquid asphalt.

13.7 When a DBE Regular Dealer of Liquid Asphalt is Not Eligible for DBE Credit.

(a) “If its role is limited to that of an extra participant in a transaction, contract or project through which funds are passed in order to obtain the appearance of DBE participation.” 49 CFR § 26.55(c)(2)

(b) If the type of transaction does not allow the DBE subcontractor to perform one of the four required functions, such as a prime contractor deciding the price of a commodity to be supplied by the DBE, that transaction is not eligible for DBE credit.

(c) Work that is performed with trucks that are not owned nor under a lease of at least one year by the DBE will not be eligible for DBE credit.

(d) A lack of documentation verifying that at least one DBE owned (not leased) tractor and tanker/trailer was used to haul liquid asphalt on the project will result in no DBE credit given on that project.

13.8 This form will be completed by the inspector from the project office during the time of the project. MoDOT will use the *MoDOT DBE Job-Site Review CUF Determination Form* to verify CUF was performed on the project, a copy of which is available on the MoDOT Contractor Resource website.

J. CONTRACTOR RETAINED GUARDRAIL JSP-04-11

1.0 Description. All guardrail indicated on plans for removal from this project shall become the

property of the Contractor.

2.0 Basis of Payment. All costs incurred for complying with this provision shall be considered completely covered by the contract unit price for Item No. 202-20.10, Removal of Improvements.

K. DISPOSITION OF EXISTING SIGNING

1.0 Description. All signing indicated for removal in the plans, shall be covered by the contractor and transported to the MoDOT Maintenance Lot located at 5617 Red Eagle Drive, Jefferson City, MO 65109. The contractor shall exercise reasonable care in the handling of the signs during removal and transportation. Should any of the signs be damaged by the contractor's negligence, it shall be replaced at the contractor's expense. The contractor shall contact Kyle Fischer, at 573-291-1925, 24 hours before delivery of the signs to the maintenance lot.

2.0 Basis of Payment. Payment for removal and transportation of these signs, as shown in the plans, shall be considered as and completely covered by the contract unit price for Item No. 202-20.10, "Removal of Improvements", per lump sum.

L. STORMWATER COMPLIANCE REQUIREMENTS JSP-15-04A

1.0 Description. The Contractor shall comply with the terms of the United States of America v. Missouri Highways and Transportation Commission Consent Decree (Consent Decree) that are identified as the responsibility of the Contractor or subcontractor, and with the terms of this provision. Viewing of the Consent Decree is available on the MoDOT Land Disturbance webpage under Contractor Resources, or by going to the web address www.modot.org/LD.

1.1 Applicability. The Consent Decree and this provision apply to any project that includes land disturbance of areas totaling greater than one (1) acre on the project site. The project site consists of all areas designated on the plans, including temporary and permanent easements. The Consent Decree and this provision do not apply to Contractor staging, plant, or borrow areas that are not located on MoDOT right of way (Off-site). The Contractor is responsible for obtaining its own separate land disturbance permit for Off-site areas. This provision is in addition to any other stormwater, environmental, and land disturbance requirements specified elsewhere in the contract.

2.0 Stormwater Training for Contractor Employees. The Contractor's on-site project manager, designated Water Pollution Control Manager (WPCM), as defined in Section 3.0, and WPCM delegate, shall complete MoDOT Stormwater Training prior to serving in those roles. If someone other than the Contractor's project manager is given the authority to manage the grading or erosion control operations, the project manager(s) for those operations shall also complete MoDOT Stormwater Training. MoDOT Stormwater Training is also required for any other person who the Contractor gives authority to take measures to prevent or minimize the consequences of non-compliance with the Stormwater requirements, as defined in Section 3.1(a) of this provision.

2.1 The Commission will provide MoDOT Stormwater Training to the Contractor employees specified in Section 2.0 at a location and time determined by MoDOT. There will be no fee for attending the training; however, the Contractor shall be responsible for all other cost related to the training, such as travel expenses, if necessary, and wages for its employees. The time to complete the training is

anticipated to be no more than 6 hours. As long as the Consent Decree is in effect, MoDOT will provide periodic trainings at various locations around the state, as needed, to ensure contractors and bidders have the opportunity to maintain the number of WPCMs they need to comply with this provision.

2.2 Those who require MoDOT Stormwater Training per Section 2.0 shall complete the training prior to beginning any land disturbance work. Thereafter, training shall occur at least once every two (2) years. The training is not project-specific. Any Contractor employee who receives the training will be qualified to perform the WPCM duties on any MoDOT project for a period of two (2) years.

2.3 MoDOT will document the names and dates that contractor employees attend MoDOT Stormwater Training and will retain those records for the period of time specified in the Consent Decree. Duplicate record keeping by the contractor is not required.

3.0 Water Pollution Control Manager (WPCM). Prior to the Pre-Activity meeting for Grading/ Land Disturbance, the Contractor shall designate a Water Pollution Control Manager (WPCM) to fulfill the duties and responsibilities listed in Section 3.1 until final stabilization occurs. The Contractor's on-site project manager may also serve as the WPCM or that role may be assigned to another manager employed by the contractor or a subcontractor. The Contractor shall also maintain a WPCM delegate to temporarily fulfill the WPCM duties in the absence of the primary WPCM (e.g. illness, vacation, other leave).

3.1 Duties of the WPCM:

- (a) Be familiar with Stormwater Requirements including the National Pollutant Discharge Elimination System (NPDES), the current MoDOT State Operating Permit for construction stormwater discharges/ land disturbance activities, the Project-specific Stormwater Pollution Prevention Plan (Project SWPPP), the Corps of Engineers Section 404 Permit, when applicable, the Consent Decree, and this provision. The Project SWPPP includes: a title page with project-specific information, the general SWPPP posted on the MoDOT land disturbance website, the Project Erosion & Sediment Control Plan, all applicable special provisions, and all applicable specifications and standard drawings;
- (b) Complete the stormwater training set forth in Section 2.0;
- (c) Attend the Pre-Activity for Grading/ Land Disturbance Meeting or, if hired after the meeting has occurred, be familiar with the conference decisions;
- (d) Review and sign the Project-specific SWPPP and all updates thereto within time periods set out in the Consent Decree;
- (e) Visit and review the project site for compliance with Stormwater Requirements at least once per week from the start of any grading operations until final stabilization is achieved and permit is closed;
- (f) Be authorized by the Contractor to supervise all work performed by the Contractor and subcontractors that involves compliance with Stormwater Requirements, including the authority to order work be stopped on a Project, implement MoDOT-directed changes in work related to

Stormwater Requirements, and order the taking of, measures to cease, correct, prevent, or minimize the consequences of non-compliance with Stormwater Requirements;

- (g) Review and certify electronically each MoDOT inspection report for the Project within three (3) days of receiving each report to ensure it conforms with report requirements in the National Pollution Discharge Elimination System Stormwater (NPDES SW) Permit, Project SWPPP and the Consent Decree and ensure that all Stormwater Deficiencies noted on the report are corrected within the time required;
- (h) Recommend in writing within three (3) days of discovering any changes in site conditions and Best Management Practices (BMPs) that require an update to the Project-specific SWPPP; and
- (i) Be the point of contact relating to Stormwater Requirements and the Consent Decree between the Contractor, Subcontractors and MoDOT.

4.0 Pre-Activity Meeting for Grading/Land Disturbance and Required Hold Point. At each Project, a Pre-Activity Meeting for Grading/Land Disturbance shall be held prior to the start of any land disturbance and shall include a physical visit and review of the project site. Discussion items at the pre-activity meeting shall include a review of the project SWPPP, the planned order of grading operations, proposed areas of initial disturbance, identification of all necessary BMPs that shall be installed prior to commencement of grading operations, and any issues relating to compliance with the Stormwater requirements that could arise in the course of construction activity at the project.

4.1 Contractor employees who shall attend the Pre-Activity Meeting for Grading/Land Disturbance include the WPCM for the Project and the person(s) designated the authority to manage the grading and erosion control operations.

4.2 Following the pre-activity meeting for Grading/land disturbance, and subsequent installation of the initial BMPs identified at the pre-activity meeting, a Hold Point shall occur prior to the start of any land disturbance operations to allow the engineer and WPCM the time needed to perform an on-site review of the installation of the BMPs to ensure compliance with the SWPPP is met. Land disturbance operations shall not begin until authorization is given by the engineer.

5.0 Compliance with the NPDES SW Permit and Project SWPPP. On all projects, the Contractor shall comply with all applicable Stormwater Requirements which are defined as, but are not limited to:

- (a) Consulting with the engineer on recommended design revisions to the Project SWPPP to accommodate the Contractor's staging plan, implementation, managing, and maintaining BMPs or other control measures to prevent or minimize sediment and other pollutants in stormwater runoff in accordance with contract specifications or any relevant manufacturer specifications and good engineering practices, including but not limited to the manuals (*Note: two manuals cited in the MoDOT permit are "Developing your stormwater pollution prevention plan: A guide for construction activities" and "Protecting Water Quality: A Field Guide to erosion, sediment and stormwater best management practices for development sites in Missouri"*) and any other applicable standards for sedimentation basins, stabilization, rock dams, brush checks, construction entrances, and other BMPs;

- (b) Installing all BMPs at the locations and relative times specified in the Project SWPPP; and
- (c) Complying with the Missouri Water Quality Standards and with effluent limitations in Section E.1 of the NPDES SW Permit. Measurement of effluent is not required except as specified in E.2.

5.1 Stormwater Deficiency Corrections. Per terms of the Consent Decree, Stormwater Deficiencies identified on the MoDOT Land Disturbance Inspection Report shall be corrected within 7 days of the inspection date to avoid stipulated penalties, except that more time might be granted by the engineer when weather or field conditions prohibit the corrective work. If the Contractor does not initiate corrective measures within 5 calendar days of the inspection date or any extended period granted by the engineer, all work shall cease on the project except for work to correct these deficiencies, unless otherwise allowed by the engineer. All impact costs related to this halting of work, including, but not limited to stand-by time for equipment, shall be borne by the Contractor. Work shall not resume until the engineer approves the corrective work.

6.0 Inspection Protocol. The Contractor and all subcontractors shall review and adhere to MoDOT's written Stormwater Inspection Protocol, found on the MoDOT Land Disturbance webpage (www.modot.org/LD). The Inspection Protocol is applicable to all Projects under the consent decree. The MoDOT Resident Engineer will serve the role of Stormwater Resident Engineer, or a delegate will be named in their absence.

6.1 Inspection Reports. MoDOT will provide one or more Environmental Construction Inspectors (ECI) to perform the weekly and post run-off inspections and other duties described in paragraph 17 of the Consent Decree. The ECI will enter the inspection reports into a web-based Stormwater Compliance database. The WPCM will have access to this database to view all report information, including any noted deficiencies, and to certify the report as required in Section 3.1 (g.). Automated email reminders of pending reports that need to be certified and for deficiencies that need to be corrected will be sent to the WPCM. The Contractor may designate other employees or subcontractor employees to have viewing access to this database and to receive the email reminders. Completion of MoDOT Stormwater Training is necessary in order to receive the email reminders. The WPCM and other users shall be equipped with an electronic device (desktop computer, laptop, tablet, smartphone, etc.) with a browser and internet access to connect to the database. The contractor shall be responsible for providing the electronic devices.

7.0 Stipulated Penalties. If the Contractor fails to comply fully and timely with the requirements of the Consent Decree, stipulated penalties will be assessed to the Commission. For matters under the Contractor's responsibility and control the following stipulated penalties will be assessed to the Contractor and MoDOT will withhold payment pursuant to the following:

Violation	Stipulated Penalty Amount
Failure to Designate or Maintain WPCM at each Project in Accordance with Section 3.0.	\$750 for the initial violation (each person not designated) and then \$750 for each fourteen (14) day period that person is not designated.
Failure to complete MoDOT Stormwater Training by an Individual Required to be Trained in Accordance with Section 2.0, such as the WPCM or Project Manager.	\$750 per person for each missed training. This \$750.00 per person violation shall continue to accrue for each fourteen (14) day period that the person fails to timely receive the applicable training

Failure of WPCM to Review and Certify an Inspection Report in Accordance with Inspection Protocol as set forth in Section 6.	\$250 per inspection report not reviewed or signed.
Failure to Comply with Any NPDES SW Permit or SWPPP Requirement.	\$1000 per violation for the first ten (10) days of the violation; \$2500 per violation for days 11-20; \$3500 per violation for days 21 and beyond.
Failure to Correct a Stormwater Deficiency Identified in a MoDOT Inspection Report, or Otherwise Discovered by the WPCM, within the Time Required by the NPDES SW Permit or SWPPP.	\$1000 per deficiency for the first ten (10) days after correction was required; \$2500 per deficiency for days 11-20 after correction was required; \$3500 per deficiency for days 21 and beyond after correction was required.

8.0 Information Collection and Retention. The EPA, its representatives and its agents shall have the right of entry into any facility covered by this Consent Decree, at all reasonable times, upon presentation of credential, to:

- (a) monitor the progress of activities required under the Consent Decree;
- (b) verify any data or information submitted to the United States in accordance with the terms of the Consent Decree;
- (c) obtain samples and, upon request, splits of any samples taken by MoDOT or its representatives, contractors, or consultants;
- (d) obtain documentary evidence, including photographs and similar data; and
- (e) assess MoDOT's compliance with the Consent Decree.

8.1 Until three (3) years after the termination of the Consent Decree, Contractors and the agents of the Contractors shall preserve all non-identical copies of all documents, records, or other information (including documents, records, or other information in electronic form) in its or its Contractors' or agents' possession or control, or that come into the Contractor's or agent's possession or control, and that relate to MoDOT's performance of its obligations under the Consent Decree or to the Contractor's performance of its obligations under the Consent Decree. This information-retention requirement shall apply regardless of any contrary corporate or institutional policies or procedures.

9.0 Basis of Payment. Payment for compliance with this provision will be made per week. All cost associated with the weekly on-site project reviews by the WPCM, compliance with this provision and the Consent Decree, including all other duties of the WPCM and delegate, and all expenses to attend training, will be considered fully covered under 806-99.28, Water Pollution Control Manager. Separate payment will be made for erosion and sediment control devices, and for permanent and temporary seeding and mulching, when payment for those items are provided elsewhere in the contract.

9.1 Method of Measurement. Measurement of the number of full weeks (7 days) will begin on the date of the first MoDOT Inspection Report following initial land disturbance and will continue until the engineer declares final stabilization has been achieved, except that no measurement will be made for any period of time past the contract completion date, or adjusted completion date, when liquidated damages are being assessed for failure of the Contractor to complete the work on time.

M. E-CONSTRUCTION

1.0 Description. e-Construction is a paperless construction administration delivery process that includes electronic submission of construction documents, approval of documents with digital signatures, and communication between stakeholders by mobile devices. e-Construction saves both time and money for all stakeholders involved, simplifies document storage, and eliminates waste of paper and other resources. This provision does not apply to the contract or other contract execution documents.

2.0 Document Submittals.

2.1 The contractor shall submit all required documents to MoDOT electronically, except as described in section 2.2 of this provision. Documents to be submitted electronically include, but are not limited to, Change Orders, Request to Subcontract Work (C-220), Project Payrolls, Progress Schedules, Value Engineering proposals, Safety Plans, Quality Plans, Pre-Construction conference submittals, etc. All documents shall be submitted in standard pdf format, except when otherwise directed by the engineer.

2.2 The Affidavit for Compliance with the Prevailing Wage Law and the Contractor's Affidavit Regarding Settlement of Claims (Form C-242) require a notarization and therefore, by law, must be submitted on paper.

2.3 The engineer will submit project documents to the contractor via email or through other secure file sharing sites, except that the Contractor Performance Questionnaire will be submitted by certified mail.

2.4 Documents that require multiple signatures, such as change orders, must include all required signatures on the original electronic document, without scanning.

2.5 Project Payrolls from subcontractors shall be digitally signed by the subcontractor. Payrolls shall be submitted as separate files per contractor per pay period.

3.0 Digital Signature.

3.1 All electronic documents that require signature, such as those listed in section 2.1, must be signed electronically. Scanning an ink-signed document is not considered a valid digital signature.

3.2 All users who are authorized to sign documents for the contractor shall submit their Digital Signature Certificate (Public Key .fdf file) to the Division of Construction prior to signing any documents. This file is used to validate the user's signature on documents. An authorization letter is also required for each person authorized to sign documents. A Digital Signature for Contractors Quick Reference Guide (QRG) is available on MoDOT's Engineering Policy Guide at <http://epg.modot.mo.gov/> (click on QRG in the left hand column).

4.0 Communication. The contractor shall be able to communicate and exchange information with MoDOT staff by email and mobile phone.

5.0 Basis of Payment. No payment will be made for compliance with this provision.

N. BONDED ASPHALTIC CONCRETE PAVEMENT NJSP-15-11 (8/20/2014)

1.0 Description. This work shall consist of the placement a Polymer Modified Emulsion Membrane prior to a bituminous overlay of hot asphaltic concrete pavement. The Polymer Modified Emulsion Membrane shall be spray applied immediately prior to the application of the hot asphaltic concrete pavement so as to produce a homogeneous surface in accordance with Secs 401, 402, or 403.

2.0 Materials. The Polymer Modified Emulsion Membrane shall be in accordance with Sec 1015.20.6.2.

3.0 Construction Requirements. The asphaltic concrete pavement shall be placed in accordance with Secs 401, 402, or 403, except as modified herein.

3.1 Equipment. No wheel, track or other part of the paving machine or any hauling equipment shall come in contact with the Polymer Modified Emulsion Membrane before the asphaltic concrete pavement mixture is applied.

3.2 Application of Polymer Modified Emulsion Membrane.

3.2.1 The Polymer Modified Emulsion Membrane shall be sprayed at a temperature of 120 - 180°. The sprayer shall accurately and continuously monitor the application rate and provide a uniform coverage across the entire width to be overlaid. The target application rate of the asphalt emulsion membrane shall be 0.20 gallons per square yard. The Engineer may make adjustments to the application rate based upon the existing pavement surface conditions and the recommendations of the Polymer Modified Emulsion Membrane supplier; however, the application rate shall be within +/- 0.07 gallon per square yard of the target application rate.

3.2.2 The application rate of the Polymer Modified Emulsion Membrane shall be verified by dividing the volume (of Polymer Modified Emulsion Membrane used) by the area of paving for that day.

3.2.3 No water shall be added to the Polymer Modified Emulsion Membrane.

4.0 Method of Measurement. Measurement of the Polymer Modified Emulsion Membrane shall be based on the volume in gallons in accordance with Sec 1015.

5.0 Basis of Payment. The accepted quantity of Polymer Modified Emulsion Membrane shall be paid for at the contract unit price 407-99.12, Misc. Polymer Modified Emulsion Membrane, per gallons.

O. SEALING TREATMENT FOR RUMBLES

1.0 Description. This work shall consist of furnishing and applying a surface sealing treatment to the existing roadway as shown on the plans. The surface treatment shall contain a mixture of cationic asphalt emulsion, latex polymer, mineral fines, water, and other additives as needed.

2.0 Mix Design.

2.1 At least 30 days prior to placing the surface sealing treatment on the project, the contractor shall

submit a mix design for approval to Construction and Materials. One gallon of the asphalt emulsion and 2500 grams of mineral fines representing the gradation shall be submitted with the mix design.

2.2 Required Information. At a minimum the Surface Sealing mix design shall contain the following information on the job mix formula:

- (a) Emulsified asphalt source and properties required
- (b) Mineral fines source
- (c) Mineral fines gradation required
- (d) Mixture performance test results required
- (e) Additives and their sources required

2.3 Mix Design Gradation Requirement. The fine mineral that comprise the combined gradation shall have 100 % of the material passing the No. 30 (600 µm) (sieve. For spraying applications, the following mix gradation shall be required:

Sieve	Percent Passing
No. 30 (600 µm)	100
No. 50 (300 µm)	80-100
No. 100 (150 µm)	90-100
No. 200 (75 µm)	95-100

2.4 Mixture Performance Requirements. The mixture shall meet the following requirements.

Testing Requirement	Min.	Max.	Test Method
Maximum Wet-Track Abrasion Loss, grams per square meter.	--	80 g/m ²	TB 100 (ISSA) Modified ^a
Asphalt Content by Ignition Method, percent	30%	--	AASHTO T-308-08 ^b
Percent Solids, Asphalt Residue by Evaporation, percent	40%	--	AASHTO T59, Section 6

^aThis method is modified to a three day soak and samples prepared per MoDOT TM 86.

^bTo account for high percentage of binder, sample size should be adjusted based on laboratory oven capability.

2.5 Required Additives. A minimum of 3% latex polymer by weight of wet mixture is required in the surface sealant treatment and shall be listed in the job mix formula.

2.6 Other Additives. Any other material added to the mixture or to any of the component materials

shall be listed in the job mix formula.

3.0 Material Certification.

3.1 The materials used in the mix design shall be certified to meet the following specifications.

3.2 Bituminous Material. The bituminous material shall be an asphalt emulsion in accordance with the following table. The bituminous material shall show no separation after mixing. The emulsion shall be sampled in accordance with AASHTO T 40.

Asphalt Emulsion (CSS)			
	Min.	Max.	Test Method
Viscosity, Saybolt Furol at 25 C, s	15	100	AASHTO T 72
Particle charge test	Positive ^b		AASHTO T 59
Residue, %	60	--	AASHTO T 59
Test on Residue from Distillation	Min.	Max.	Test Method
Penetration, 25 C, 100 g, 5 s,	30	100	AASHTO T 49

^bIf the particle charge test is inconclusive, material having a maximum pH value of 6.7 will be acceptable.

3.6 Water. Water shall be potable and free of harmful soluble salts.

4.0 Construction Requirements.

4.1 The surface sealing mixture may be mixed and applied through mobile distribution equipment as described herein.

4.2 Mixing Equipment. All materials shall be thoroughly mixed as to produce a homogenous surface treatment. Individual volume or weight controls for proportioning each material in the mix shall be provided. Materials shall be added by a calibrated controlled device capable of monitoring the amount of material used at the time.

4.3 Distribution Equipment. The Distributor shall be equipped with a full sweep agitation system, a pumping system designed to handle fine aggregate mixes, and sufficient power to operate the full spray system and the agitation system at the same time. The Distribution equipment shall be equipped with a monitoring system that ensures the even distribution of material and measures the application rate of the mix.

4.4 Storage Tanks. If the mix is being delivered from a central mixing plant, then a job site storage tank shall have the minimum capacity of the entire transport load. The storage tank shall have an internal full sweep mixing system having a mixing capability of providing a homogenous mix representing the mix design at any given location within the tank.

4.5 Environmental Protection. The contractor shall comply with all federal, state, and local laws and

regulations controlling pollution of the environment.

4.6 Weather Limitations. Bituminous material shall not be placed on any wet surface or when the ambient temperature or the temperature of the pavement on which it is to be placed is below 60° F. Temperatures shall be obtained in accordance with MoDOT Test Method TM 20.

4.7 Surface Preparation. The surface shall be thoroughly cleaned immediately prior to placing the surface treatment.

4.8 Protection of Other Surfaces. All curbs, manhole covers, and ADA facilities shall be protected from the spray or laydown of the bituminous mixture during placement.

4.9 Dilution. The bituminous material shall not be diluted in the field with water or other additives except as approved by the manufacturer.

4.10 Placement. Placement of the mix shall be in one pass on rumble strips or chip seal surfaces only. The minimum total coverage shall be 0.18 gallons per square yard. **4.11 Opening to Traffic.** After the sealant application, the roadway shall remain closed until the surface is tack-free and capable of being open to traffic without tracking.

4.12 Basis of Acceptance.

4.12.1 Quality Control. Two samples shall be collected during production on a project. One sample shall be retained for the engineer. The contractor shall test the other sample and verify the mix design in accordance with Section 2.4 of this specification and submit the test results to the engineer.

4.12.2 Field Performance. The finished surface sealant treatment shall be evaluated by the engineer based on the following criteria. Any of the following shall be considered unacceptable material.

- (a) The presence of loose aggregate or synthetic materials that may cause damage to traveling vehicles.
- (b) A final surface with insufficient coverage or delamination.

5.0 Method of Measurement. Final measurement of the surface treatment will not be made except for authorized changes during construction, or where appreciable errors are found in the contract quantity. Where required, measurement of the surface treatment, complete in place, will be made to the nearest square yard. The revision or correction will be computed and added to or deducted from the contract quantity.

6.0 Basis of Payment. The accepted quantity of surface treatment, in place, will be paid for at the contract unit (square yard) price. No separate payment will be made for any additional construction methods or processes. Manufacturer shall report the unit weight (lbs. per gallon) of the surface sealing material on the bill of lading.

P. HIGH FRICTION SURFACE TREATMENT NJSP-15-13B

1.0 Description. This work shall consist of furnishing and placing a High Friction Surface Treatment

(HFST) on asphalt or concrete pavement.

1.1 The HFST shall be comprised of surface preparation and a minimum of a single layer using a Binder Resin System which holds a surface applied aggregate firmly in place. The Binder Resin System shall include Polymeric or Methl Methacrylate (MMA) Resins.

2.0 Material.

2.1.1 **Resin Binder System.** Resin Binder Systems shall be recommended by the manufacturer as suitable for use on the intended pavement surface and for the potential range of atmospheric exposure.

2.1.2 The contractor shall furnish and install a Resin Binder System that meets the criteria in (AASHTO PP 79-14 Table 1):

Table 1 - Resin Binder System			
Property	Test Method	Requirements	
		Polymeric Resin	MMA
Ultimate Tensile Strength	AASHTO M-235	2500-5000 psi	1500-5000 psi
Elongation at break point	AASHTO M-235	30-70%	30-70%
Compressive Strength	ASTM C 579	1000 psi min. at 3 hours 5000 psi min. at 7 days	1000 psi min. at 3 hours 2000 psi min. at 7 days
Water Absorption	AASHTO M-235	1% max.	1% max.
Durometer Hardness (Shore D)	ASTM D-2240	60-80	40-75
Viscosity	ASTM D-2556	Class C: 7-30 poises	Class C: 12-20 poises
Gel Time	AASHTO M-235	Class C: 10 minutes min.	Class C: 10 minutes min.
Cure Rate (Dry through time)	ASTM D-1640	3 hrs. max.	3 hrs. max.
Adhesive Strength at 24 hours	ASTM D 4541	250 psi min. or 100% substrate failure	250 psi min. or 100% substrate failure

2.1.3 Independent laboratory reports per formulation shall be provided, documenting that the resin binder meets the requirements of this specification. A sample of the resin binder or components lot/batch shall be supplied upon request.

2.1.4 At the request of the engineer, the manufacturer of the Resin Binder System shall certify that the Resin Binder System meets the requirements of this specification. Such certification shall consist of either a copy of the manufacturer’s test report or a statement by the manufacturer, accompanied by a copy of the current test results, that the Resin Binder System has been sampled and tested. Such certification shall indicate the date of testing and shall be signed by the manufacturer.

2.2.1 Aggregate. The contractor shall furnish and install a high friction aggregate that is clean, dry and free from deleterious material. The high friction aggregate shall be Calcined Bauxite for this project.

2.2.2 The calcined bauxite aggregate shall meet the criteria in Table 2:

Table 2 - Calcined Bauxite Aggregate		
Property	Test Method	Requirement
Resistance to Degradation	AASTHO T-96	20% max.
Aggregate Grading	AASHTO T-27	No. 4 Percent Passing 100% min. No. 6 Percent Passing 95% min. No. 16 Percent Passing 5% max.
Moisture Content	AASHTO T-255	0.2% max.
Aluminum Oxide	ASTM C-25	87% min.

2.2.3 All aggregates shall be furnished in appropriate packaging that is clearly labeled and protects the aggregate from any contaminates on the jobsite and from exposure to rain or other moisture.

2.2.4 At the request of the engineer, the manufacturer of the aggregate shall certify that the aggregate meets the requirements of this specification. Such certification shall consist of either a copy of the manufacturer's report or a statement by the manufacturer, accompanied by a copy of the current test results, that the aggregate has been sampled and tested. Such certification shall indicate the date of testing and shall be signed by the manufacturer.

2.2.5 Test methods should be in accordance with AASHTO PP 79-14.

3.0 Construction Requirements. A manufacturer's representative of the Resin Binder System shall be present at the jobsite during all construction operations relating to the preparation and placement of the HFST. All construction operations relating to the HFST shall meet the recommendations of the manufacturer's representative. Final approval of all HFST placement operations will be given by the engineer.

3.1 Weather Limitations. Resin Binder system shall not be placed on any wet surface or when the ambient temperature or the temperature of the pavement is above or below the manufacturer's recommendations or when the anticipated weather conditions would prevent the proper application of the surface treatment as directed by the manufacturer's representative. Temperatures shall be obtained in accordance with MoDOT Test Method TM 20.

3.2 Surface Preparations. The surface shall be thoroughly cleaned immediately prior to installation of the HFST. The surface shall be clean, dry and free of all dust, oil, debris and any other material that might interfere with the bond between the resin binder material and the existing surface as recommended by the manufacturer's representative.

3.2.1 The contractor shall pre-treat joints and cracks greater than ¼ inch in width and depth with the mixed Resin Binder System. Once the resin binder in the pre-treated areas has gelled, the installation of the HFST may proceed.

3.2.2 Asphalt Pavement. Clean asphalt pavement surfaces using mechanical sweepers and high pressure air wash with sufficient oil traps. Mechanically sweep all surfaces to remove dirt, loose

aggregate, debris, and deleterious material. Vacuum sweep or air wash using a minimum of 180 cfm of clean and dry compressed air, all surfaces to remove all dust, debris, and deleterious material. HFST shall not be applied to newly placed asphalt pavement surfaces that are less than 30 days old.

3.2.3 Concrete Pavement. Clean concrete pavement surfaces by shot blasting and vacuum sweeping. Shot blast all surfaces to remove all curing compounds, loosely bonded mortar, surface carbonation, and deleterious material. The prepared surface shall comply with the International Concrete Repair Institute (ICRI) standard for surface roughness CSP 5. After shot blasting, vacuum sweep or air wash, with a minimum of 180 cfm of clean and dry compressed air, all surfaces to remove all dust, debris, and deleterious material.

3.2.4 All existing edge line pavement markings that are adjacent to the HFST location shall be covered and protected as approved by the engineer prior to performing surface preparation. HFST shall not be placed over existing pavement markings or rumble strips. Lane line pavement markings that conflict with the HFST installation shall be removed by methods approved by the manufacturer's representative. Any existing edge line pavement markings that are damaged during the HFST application process shall be replaced at the contractor's expense.

3.3 HFST shall be allowed to cure for the minimum duration as recommended by the binder component supplier's specifications and during that time the application area shall be closed to all vehicles and contractor's equipment traffic. After placement and cure of the HFST, the contractor shall test the finished surface in accordance with ASTM D7234 to detect unbonded areas.

3.4 Excess and loose aggregate shall be removed from the traveled way and shoulders in such a way that the HFST is not damaged or disturbed. Excess aggregate that can be reused shall be reclaimed by a vacuum sweeper. The recovered aggregate shall be clean, uncontaminated and dry, if it is to be re-used in the HFST application. All reclaimed aggregate must be in conformance with the requirements in Section 2.0. Material.

3.5 Utilities, drainage structures, curbs and any other structures within or adjacent to the treatment location shall be protected against the application of the HFST materials.

3.6 Surface Friction Test. The surface friction of the completed HFST shall meet a minimum requirement of 65 FN40R from the ASTM E274 test. MoDOT will perform this test, at the expense of the Commission, within 7 calendar days after completion of the HFST. In order to allow for adequate scheduling time for the surface friction test, the contractor shall provide an anticipated completion date of the HFST for each segment of roadway being treated in this contract. The contractor shall provide this date(s) to the engineer a minimum of two weeks prior to any anticipated completion date of the HFST.

3.6.1 Any surface that fails to conform to the above friction requirement must be removed and replaced at the contractor's expense within 24 hours after being notified by the engineer.

3.7 Surface Quality Verification. The engineer will check the HFST surface for areas of debonding or excessive loss of aggregate fourteen days after completion of the HFST. Any deficiencies found shall be corrected at the contractor's expense.

4.0 Application Methods. HFST shall be applied in accordance with the manufacturer's recommendations. The HFST can be applied by either mechanical or manual techniques.

4.1 The Resin Binder System shall be blended and mixed in the ratio per the manufacturer's specification (+/- 2% by volume) and shall be continuously applied once blended.

4.1.1 The Resin Binder System shall be applied at a uniform thickness of 50-65 mils (25-32 square feet per gallon). Coverage rate is based upon expected variances in the surface profile of the pavement.

4.1.2 The operation shall proceed in such a manner that will not allow the mixed material to separate, cure, dry, be exposed or otherwise harden in such a way as to impair retention and bonding of the high friction aggregate.

4.1.3 The high friction aggregate shall be immediately applied at a rate of 12-15 pounds per square yard (achieving saturation) in such a manner that there is no disruption to the leveled binder. It is the responsibility of the contractor to ensure full embedment of the high friction aggregate.

4.1.4 Wet spots shall be covered with the high friction aggregate prior to the gelling of the Resin Binder System.

4.1.5 Walking, standing on, or any form of contact or contamination with the wet uncured Resin Binder System without spiked shoes as approved by the engineer, prior to application of the aggregate, will result in that section of Resin Binder System being removed and replaced at the contractor's expense.

4.1.6 Applications on high speed highways such as interstate, interstate ramps, and bridge decks will require additional sweeping three days after the initial installation is completed to remove excess and loose aggregate from the traveled way and shoulders.

5.0 Method of Measurement. Final measurement of the completed HFST will not be made except for authorized changes during construction, or where appreciable errors are found in the contract quantity. When required, measurement of HFST, complete in place, will be made to the nearest square yard. The revisions or correction will be computed and added to or deducted from the contract quantity.

6.0 Basis of Payment. The accepted quantity of HFST, in place, will be paid for at the contract unit price bid for Item Number 413-99.05, "High Friction Surface Treatment-Bauxite", per square yard. The contract price per square yard of HFST shall include full compensation for all labor, materials, tools, equipment, testing and incidental items necessary to complete the described work.

Q. CLEAN AGGREGATE FOR GUARDRAIL

1.0 Description. This work consists of furnishing and placing clean aggregate over the existing surface of the Route 50 median within the limits of the pier protection guardrail for the Militia Drive overpass bridge.

2.0 Material. The contractor shall furnish an Aggregate for Drainage – Grade 4, Gradation A or 1" clean quarry-run aggregate from an approved source as approved by the engineer.

3.0 Placement. The aggregate shall be placed within the limits of the guardrail as shown on the Guardrail Modification Special Sheet 6 of 6, shall cover the existing surface with a minimum depth of 2"

and shall be blended into the existing ground at the face of the existing guardrail. The aggregate shall be placed to maintain the existing drainage and shall not obstruct any existing drainage structures.

3.1 The existing guardrail indicated for use in place on the special sheet shall not be removed or altered without prior approval from the engineer; any damaged, altered, or removed rail within the use in place limits shown shall be restored with no direct pay to the contractor.

4.0 Basis of Payment. The accepted quantity of clean aggregate to be placed, including all labor, material, tools, equipment, and incidental items shall be inclusive to and completely covered the contract unit price for Item Number 304-99.05, "Furnishing and Placing Clean Aggregate – 2" Thick", per square yard.