

DATE: June 22, 2018  
TO: ALL GENERAL CONTRACTORS BIDDING  
FROM: BFA, Inc.  
RE: STP-5500(678)

#### Addendum #1

This Addendum is an integral part of the contract documents and shall be treated as such. Contractor shall acknowledge receipt of this addendum on the Bid Form.

#### CHANGES TO THE BID FORM

- Changed the Quantity for Line Item#12 Type A Crashworthy End Terminal from 2 to 4.
- Changed the Quantity for Line Item#9 Guard Rail – Type A from 60 to 0.
- Changed the Quantity for Line Item#24 4 In. Yellow Standard Waterborne Pavement Marking Paint from 553 to 552.
- For clarification, “WITH BLACK FINISH” has been added to Line Item# 10, 11, and 12.

See attached revised Itemized Bid Form.

#### CLARIFICATION

- For clarification on the Bridge Plans Sheet 3 of 19, a coating system is not required.

*End of Addendum #3*

**ROADWAY ITEMS**

LINE	ITEM #	DESCRIPTION	UNITS	QTY	UNIT PRICE	TOTAL
1	201-30.00	CLEARING AND GRUBBING	AC	0.1		
2	202-20.10	REMOVAL OF IMPROVEMENTS	LS	1		
3	203-50.00	UNCLASSIFIED EXCAVATION	CY	410		
4	203-60.00	COMPACTING EMBANKMENT	CY	76		
5	304-05.04	TYPE 5 AGGREGATE FOR BASE (4 IN THICK)	SY	633		
6	401-12.09	BITUMINOUS PAVEMENT PG64-22 (BP-1)	TON	69		
7	401-30.00	BITUMINOUS PAVEMENT PG64-22 (BASE)	TON	275		
8	407-10.05	TACK COAT	GAL	64		
9	606-10.10	GUARD RAIL - TYPE A	LF	0		
10	606-10.69	MGS BRIDGE APPROACH TRANSITION SECTION, WITH BLACK FINISH	EA	4		
11	606-24.00	BRIDGE ANCHOR SECTION (THREE BEAM), WITH BLACK FINISH	EA	4		
12	606-30.14	TYPE A CRASHWORTHY END TERMINAL, WITH BLACK FINISH	EA	4		
13	611-30.20	FURNISHING TYPE 2 ROCK BLANKET	CY	216		
14	611-30.40	PLACING TYPE 2 ROCK BLANKET	CY	216		
15	618-10.00	MOBILIZATION	LS	1		
16	627-40.00	CONTRACTOR FURNISHED SURVEYING AND STAKING	LS	1		
17	805-20.00A	SEEDING	AC	0.1		
18	806-10.17	TEMPORARY SEEDING AND MULCHING	AC	0.1		
19	806-10.19	SILT FENCE	LF	617		
<b>Roadway Total</b>						

**SIGNING/STRIPING ITEMS**

LINE	ITEM #	DESCRIPTION	UNITS	QTY	UNIT PRICE	TOTAL
20	616-10.05	CONSTRUCTION SIGN	SF	271		
21	616-10.20	CHANNELIZER (DRUM-LIKE) WITH LIGHT	EA	10		
22	616-10.31	TYPE III MOVABLE BARRICADE WITH LIGHT	EA	6		
23	620-60.00B	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT	LF	553		
24	620-60.01B	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT	LF	552		
<b>Signing/Striping Total</b>						

**BRIDGE ITEMS**

LINE	ITEM #	DESCRIPTION	UNITS	QTY	UNIT PRICE	TOTAL
25	206-10.00	CLASS 1 EXCAVATION	CY	62.5		
26	216-05.00	REMOVAL OF BRIDGES	LS	1		
27	702-10.10	STRUCTURAL STEEL PILES (10 in)	LF	156		
28	702-12.10	GALVANIZED STRUCTURAL STEEL PILES (10 in)	LF	172		
29	702-50.01	DYNAMIC PILE TESTING	EA	2		
30	702-50.02	PILE WAVE ANALYSIS	EA	2		
31	702-70.00	PILE POINT REINFORCEMENT	EA	8		
32	703-20.03	CLASS B CONCRETE (SUBSTRUCTURE)	CY	26.8		
33	703-42.12	SLAB ON STEEL	SY	189		
34	703-42.15	BARRIER CURB (TYPE D)	LF	126		
35	703-46.20	FORM LINERS	SY	40		
36	711-05.00	TEMPORARY COATING - CONCRETE BENTS AND PIERS (WEATHERING STEEL)	LS	1		
37	711-06.00	AESTHETIC CONCRETE STAIN	LS	1		
38	712-11.22	FABRICATED STRUCTURAL LOW ALLOY STEEL (I-BEAMS) A709 GRADE 50W	LBS	27490		
39	712-36.10	SLAB DRAIN	EA	10		
40	715-10.01	VERTICAL DRAIN AT END BENTS	EA	2		
41	716-10.00	PLAIN NEOPRENE BEARING PAD	EA	8		
					<b>Bridge Total</b>	
					<b>TOTAL PROJECT</b>	