

January 29, 2018

ADDENDUM NO. 2

Notice to All Persons and Firms Proposing
to Submit a Bid or Furnish Materials for
Baur Boulevard-Guelbreth Lane Infrastructure
St. Louis County Project No. AR/CR-1582
Federal Project No. STP-4900(625)

The construction contract for this project has been revised as follows:

No. 1

Delete Special Provision No. 100.70.2 "COORDINATION WITH RAILROAD" and replace with the following:

100.70.5 RAILROAD PERMITS, AGREEMENTS, AND LICENSES

- A. The Contractor shall obtain all necessary permits, agreements, and licenses for work within railroad right-of-way at the railroad crossing(s) listed below:

Crossing No. 1 – Baur Boulevard

- Contact Name: Nik Shepard
- Railroad name: Progressive Rail, Inc.
- Contact Phone Number: 715-379-4686

- B. All permit, agreement, and license applications shall require the approval of St. Louis County Department of Transportation before submittal to any railroad company or agent of the railroad company. The Contractor shall be required to submit all necessary permit, agreement, and license applications at least seven (7) days in advance of work in any railroad's right-of-way. All applications shall be submitted for review to the Utility Coordinator, (James Brown 314-615-8199), for St. Louis County. The Contractor shall allow five (5) business days for St. Louis County to complete the review for all applications.
- C. No work shall be performed within the railroad's right-of-way until an approved copy of each permit, agreement, and license; as applicable; is provided to St. Louis County.

- D. All work performed by the Contractor within any railroad's right-of-way shall be in accordance with the provisions as set out within the railroad permit, agreement, and/or license. Payment for permits, agreements, and licenses shall be made for each railroad crossing under Bid Item Number 107-02.00, "Railroad Permits, Agreements and Licenses". Payment under this item shall include application fees, administrative labor, compliance with the permit/agreement conditions, and insurance requirements of the railroad permit/agreement. The County shall not provide additional compensation for any resubmittals for railroad permits or agreements due to contractor's actions or delays in the scheduling of work

No. 2

Add: Attached Form, "PROGRESSIVE RAIL INCORPORATED RIGHT OF WAY RELEASE FORM" to Construction Contract Supplemental Documents.

No. 3

Add: Bid Item No. 107-02.00 "RAILROAD PERMITS, AGREEMENTS AND LICENSES"

REVISED ITEMIZED BID SHEETS NOS. 1 OF 7 THROUGH 7 OF 7 ARE ATTACHED AND REFLECTS THE CHANGES NOTED IN ITEM NO. 3 ABOVE. FAILURE TO SUBSTITUTE THE ITEMIZED BID SHEETS MAY RESULT IN REJECTION OF THE BID.

ATTENTION BIDDERS: THE ADDENDUM ACKNOWLEDGEMENT IN THE BID DOCUMENTS MUST BE COMPLETED AND SUBMITTED WITH ALL BID PROPOSALS.



Joseph W. Kulesa, P.E.
Division Manager, Design

JWK/JAB/jlh

PROGRESSIVE RAIL INCORPORATED RIGHT-OF-WAY RELEASE FORM

In consideration of Progressive Rail Incorporated, hereinafter referred to as CARRIER, solely as an accommodation to me (us), permitting me (us) the undersigned permission to enter the right-of-way on or about _____, 2018 on CARRIER'S line of railroad at or near _____ in _____ (Mile Post _____), hereby waive all claims for, and release CARRIER from any damages or penalties by reason of my being injured or killed, or suffering loss of or damage to any of my property or effects, while on or attempting to board or alight from said train, or while on or about any of CARRIER'S premises or facilities, whether such injury, death, loss or damage be caused by the carelessness or negligence of CARRIER or of the officers, agents, servants or employees thereof, or otherwise; and I further agree to wholly indemnify and forever save harmless CARRIER, and the successors, assigns, officers, agents, servants and employees thereof, from and against any such claim; and I hereby agree that this release may be pleaded as a complete defense to any action for damages or penalties which may be brought, instituted or taken by me, my heirs, executor administrator, widow, child or children, against CARRIER or the successors, assigns, officers, agents, servants or employees thereof.

Flagging requests require a minimum three (3) day notice prior to scheduling personnel. Contact Nik Shepard @ 1-715-379-4686 for all Flagging Requests.

I have hereunto affixed my signature and agree to all charges incurred upon invoicing.

Dated: _____

Company: _____

Address : _____

Phone Number: _____

Printed Name: _____

Signature: _____

+++++

Approved: _____

Nik Shepard
General Manager – Crossings & Signals
Progressive Rail Inc.

ITEMIZED BID BID OPTION 1 OF 1

FEDERAL PROJECT NO. STP-4900(625)
COUNTY PROJECT NO. AR/CR-1582

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
ROADWAY ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
107-02.00	Railroad Permits, Agreements, and Licenses	EACH	1		
201-20.23	Tree Removal, Over 15"	EACH	7		
202-20.10	Removal of Improvements	L.S.	1		
203-10.00	Class "A" Excavation	C.Y.	269.4		
203-10.30	Land Disturbance Permits	L.S.	1		
304-05.04	Type 5 Aggregate Base (4" Thick)	S.Y.	1847.7		
404-12.67	Superpave Asphaltic Concrete Mixture SP125 (PG 64-22)DLP	TON	2444.2		
404-21.33	Superpave Asphaltic Concrete Mixture SP95 (PG 70-22)C (Wedge and Level)	TON	634.5		
405-30.10	Type "C" Bituminous Concrete (Pavement)	TON	145.2		

2 ADDENDUM NO. 2

ITEMIZED BID BID OPTION 1 OF 1

PAGE 2 OF 7

FEDERAL PROJECT NO. STP-4900(625)
COUNTY PROJECT NO. AR/CR-1582

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
ROADWAY ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
405-30.20	Type "D" Bituminous Concrete (Pavement)	TON	1.9		
405-30.30	Type "X" Bituminous Concrete (Base)	TON	122.3		
407-10.27	Tack-Emulsified Asphalt (SS-1H)	GAL.	4000		
412-10.02	Pavement Surfacing and Texturing (0" to 2"), Concrete or Asphalt	S.Y.	13052		
412-10.04	Pavement Surfacing and Texturing (0" to 4"), Concrete or Asphalt	S.Y.	10826		
509-19.08	Concrete Base Repair (8" Non-reinforced, Removal and Replacement), Includes Curb, Very Early Strength	S.Y.	1021.8		
603-10.35	Adjust Water Service Valve Box to Grade	EACH	3		
604-20.30	Adjusting Manhole to Grade	EACH	1		
604-90.40	Adjust Inlet Stone to Grade	EACH	8		

2

ADDENDUM NO. 2

**ITEMIZED BID
BID OPTION 1 OF 1**

PAGE 3 OF 7

**FEDERAL PROJECT NO. STP-4900(625)
COUNTY PROJECT NO. AR/CR-1582**

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
ROADWAY ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
604-90.50	Replace Precast Inlet Stone and Adjust to Grade	EACH	8		
604-90.52	Replace Inlet Sill	EACH	2		
604-90.55	Replace Inlet Lid	EACH	1		
608-10.90	Remove and Replace Concrete Median/Island	S.Y.	10		
608-50.97	Remove and Replace Paved Approach (7")	S.Y.	332.4		
609-10.93	Remove and Replace Curb and Gutter (Various Widths), Vertical/Mountable	L.F.	2906		
609-20.11	Integral Curb (6" Height and Under)	L.F.	65		
612-30.10	Standard Traffic Control Devices	L.S.	1		
612-60.92	Arrow Panel, Type "B" (Noiseless), Rental	EACH	6		

**ITEMIZED BID
BID OPTION 1 OF 1**

FEDERAL PROJECT NO. STP-4900(625)
COUNTY PROJECT NO. AR/CR-1582

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
ROADWAY ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
619-00.00	Mobilization	L.S.	1		
803-10.00	Sodding	S.Y.	25		
803-20.00	Strip Sodding	S.Y.	1375		
806-45.00	Inlet Protection	L.S.	1		
SUBTOTAL - ROADWAY ITEMS					

COUNTY TRAFFIC SIGNAL ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
904-24.01	Signal Head, Type 1S, Pedestrian	EACH	2		
904-28.07	Post, Signal, w/Sq. Pedestal Base and Post Cap, 7' Maximum Total Height, Aluminum	EACH	5		
904-45.01	Controller Unit Only, w/Internal Fiber Optic Modem, TS2, Type 2	EACH	1		

2

ADDENDUM NO. 2

**ITEMIZED BID
BID OPTION 1 OF 1**

FEDERAL PROJECT NO. STP-4900(625)
COUNTY PROJECT NO. AR/CR-1582

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
COUNTY TRAFFIC SIGNAL ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
904-49.22	Detector, Pedestrian Push Button, APS, Freezeproof	EACH	8		
904-51.00	Conduit, 1"	L.F.	22		
904-52.00	Conduit, 2"	L.F.	54		
904-74.99	Conduit Repair (locate broken conduit, excavate, remove existing cable, repair/replace conduit, reinstall cable, backfill and restore) (Does not include sidewalk or pavement removal and replacement)	EACH	1		
904-84.00	Wire, Stranded Ground, #6 Gauge	L.F.	90		
904-85.05	Cable, Detector Loop, #14 Gauge, 1 Conductor, w/Tube Jacket (In Conduit and Pull Boxes)	L.F.	30		
904-85.06	Cable, Detector Loop, #14 Gauge, 1 Conductor, w/Tube Jacket (In Sawed Slot)	L.F.	420		
904-85.18	Cable, Push Button and/or Detector Loop Lead-In, #18 Gauge, 2 Conductor (Shielded)	L.F.	470		
904-85.34	Cable, Communication, #18 Gauge, 4 Conductor (APS)	L.F.	250		

**ITEMIZED BID
BID OPTION 1 OF 1**

FEDERAL PROJECT NO. STP-4900(625)
COUNTY PROJECT NO. AR/CR-1582

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
COUNTY TRAFFIC SIGNAL ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
904-88.01	Pull Box, Single, Concrete	EACH	1		
904-91.43	Base, Type P-3, Concrete	EACH	5		
SUBTOTAL - COUNTY TRAFFIC SIGNAL ITEMS					

PEDESTRIAN AND BICYCLE ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
201-20.11	Clearing Vegetation from the Pedestrian Access Route	L.S.	1		
412-20.00	Sidewalk Grinding	EACH	1		
608-60.04	Concrete Sidewalk (4" Thick)	S.Y.	50		
608-60.06	Concrete Sidewalk (6" Thick)	S.Y.	51.1		
608-60.93	Remove and Replace Concrete Curb Ramp	EACH	72		

**ITEMIZED BID
BID OPTION 1 OF 1**

FEDERAL PROJECT NO. STP-4900(625)
COUNTY PROJECT NO. AR/CR-1582

ITEM NO.	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
PEDESTRIAN AND BICYCLE ITEMS - ENGINEER'S ESTIMATE-ADDENDUM NO. 2					
608-60.94	Remove and Replace Concrete Sidewalk (4" Thick)	S.Y.	673.5		
608-60.96	Remove and Replace Concrete Sidewalk (6" Thick)	S.Y.	72.3		
608-60.98	Truncated Domes for Curb Ramps (New Construction)	S.F.	40		
SUBTOTAL - PEDESTRIAN AND BICYCLE ITEMS					
PROJECT TOTAL - BID OPTION 1 OF 1					