

Steven V. Stenger
County Executive



Daniel W. Dreisewerd, P.E., PTOE
Acting Director

Stephanie Leon Streeter, P.E.
Deputy Director

November 13, 2017

ADDENDUM NO. 3

Notice to All Persons and Firms Proposing to Submit a Bid or Furnish Materials for
West Adams Avenue Resurfacing and Adams Avenue-Ballas Road – ARS Infrastructure
St. Louis County Project No. AR-1681 and AR-1479
Federal Project No. STP-5641(603) and STP-5641(602)

The construction contract for this project has been revised as follows:

No. 1

Summary of Quantity Sheet (Sheet 2 of 20) has been revised to reflect the correct Bid Item description. Bid Item 404-12.71 correct description worded as follows “Superpave Asphaltic Mixture SP125 (PG70-22) CLP”

REVISED SUMMARY QUANTINTY SHEET 2 OF 20 IS ATTACHED AND REFLECTS THE CHANGES NOTED IN ITEM NO. 1 ABOVE.

ATTENTION BIDDERS: THE ADDENDUM ACKNOWLEDGEMENT IN THE BID DOCUMENTS MUST BE COMPLETED AND SUBMITTED WITH ALL BID PROPOSALS.



Joseph W. Kulesa, P.E.
Division Manager, Design

JWK/CJE:jlh

Attachments: Summary of Quantity Sheet (Sheet 2 of 20)

SUB-TOTALS	TOTAL	UNIT	ITEM NO.	DESCRIPTION	REMARKS	SUB-TOTALS	TOTAL	UNIT	ITEM NO.	DESCRIPTION	REMARKS
				ROADWAY ITEMS							
		L.S.	202-20.10	REMOVAL OF IMPROVEMENTS	Not shown on B sheets.						
		L.F.	202-22.95	SAWCUT (ANY DEPTH/MATERIAL)							
		L.S.	203-10.30	LAND DISTURBANCE PERMIT	Not shown on B sheets.						
		S.Y.	304-05.04	TYPE 5 AGGREGATE BASE (4" THICK)	INCLUDES 10% EXTRA FOR CONTINGENCY						
		TON	404-12.71	SUPERPAVE ASPHALTIC CONCRETE MIXTURE SP125 (PG 70-22)CLP	INCLUDES 10% EXTRA FOR CONTINGENCY						
		TON	404-21.92	SUPERPAVE ASPHALTIC CONCRETE MIXTURE SP95 (PG 70-22)C (WEDGE COURSE)	INCLUDES 10% EXTRA FOR CONTINGENCY						
		TON	405-30.30	TYPE "X" BITUMINOUS CONCRETE (PAVEMENT) (8.5" BASE)	INCLUDES 10% EXTRA FOR CONTINGENCY						
		TON	405-30.20	TYPE "D" BITUMINOUS CONCRETE (PAVEMENT) (2.5" OVERLAY)							
		GAL	407-10.27	TACK-EMULSIFIED ASPHALT (SS-1H)	INCLUDES 10% EXTRA FOR CONTINGENCY						
		S.Y.	412-10.00	PAVEMENT SURFACING AND TEXTURING							
		EA.	603-10.35	ADJUST WATER SERVICE VALVE BOX TO GRADE	Not shown on B sheets.						
		EA.	604-20.30	ADJUSTING MAN-HOLE TO GRADE	Not shown on B sheets.						
		EA.	604-90.54	CLEAN STORM SEWER DRAINAGE STRUCTURES							
		L.F.	606-10.10	GUARDRAIL, TYPE "A"							
		EA.	606-30.96	CRASHWORTHY GUARDRAIL TERMINAL, MODIFIED (37.5' LENGTH)							
		S.Y.	608-50.97	REMOVE AND REPLACE PAVED APPROACH (7")							
		L.F.	609-30.10	ASPHALT CURB							
		L.S.	612-30.10	STANDARD TRAFFIC CONTROL DEVICES	Not shown on B sheets.						
		S.Y.	613-30.01	PARTIAL DEPTH PAVEMENT REPAIR, TYPE X BITUMINOUS (INCLUDES MILLING, CONCRETE OR ASPHALT)							
		EA.	612-60.92	ARROW PANEL, TYPE "B" (NOISELESS), RENTAL							
		L.S.	619-00.00	MOBILIZATION	Not shown on B sheets.						
		L.F.	726-23.36	36" CLASS III REINFORCED CONCRETE PIPE CULVERT (GASKET TYPE)							
		EA.	732-00.36	36" FLARED END SECTION							
		S.Y.	803-20.00	STRIP SODDING							
		L.S.	806-45.00	INLET PROTECTION	Not shown on B sheets.						
				TRAFFIC SIGNAL ITEMS							
		EA.	904-24.01	SIGNAL HEAD, TYPE 1S, PEDESTRIAN							
		EA.	904-28.07	POST, SIGNAL, W/SQ. PEDESTAL BASE AND POST CAP, 7' MAXIMUM TOTAL HEIGHT, ALUMINJM							
		EA.	904-45.01	CONTROLLER UNIT ONLY, W/ INTERNAL FIBER OPTIC MODEM, TS2, TYPE 2							
		EA.	904-45.10	CABINET DOOR LOCKING ASSEMBLY,ELECTRONIC, (WITH POWER SUPPLY, AUXILLARY POWER INPUT , ELECTRONIC SOLENOID, AND CARD READER WITH KEY PAD)							
		EA.	904-49.22	DETECTOR, PEDESTRIAN PUSH BUTTON, APS, FREEZEPROOF							
		L.F.	904-51.00	CONDUIT, 1"							
		L.F.	904-52.00	CONDUIT, 2"							
		EA.	904-74.99	CONDUIT REPAIR (LOCATE BROKEN CONDUIT, EXCAVATE, REMOVE EXISTING CABLE, REPAIR/REPLACE CONDUIT, REINSTALL CABLE, BACKFILL AND RESTORE) (DOES NOT INCLUDE SIDEWALK OR PAVEMENT REMOVAL AND REPLACEMENT)							
		L.F.	904-84.00	WMRE, STRANDED GROUND, #6 GAUGE							
		L.F.	904-85.05	CABLE, DETECTOR LOOP, #14 GAUGE, 1 CONDUCTOR, W/TUBE JACKET (IN CONDUIT AND PULL BOXES)							
		L.F.	904-85.06	CABLE, DETECTOR LOOP, #14 GAUGE, 1 CONDUCTOR, W/TUBE JACKET (IN SAWED SLOT)							
		L.F.	904-85.18	CABLE, PUSH BUTTON AND/OR DETECTOR LOOP LEAD-IN, #18 GAUGE, 2 CONDUCTOR (SHIELDED)							
		EA.	904-85.34	CABLE, COMMUNICATION, #18 GAUGE, 4 CONDUCTOR (APS)							
		EA.	904-91.43	BASE, TYPE P-3, CONCRETE							
		EA.	904-95.10	OPENING DRILLED IN EXISTING CONCRETE PULL BOX							
		EA.	904-95.40	ADJUSTMENT OF CONCRETE SINGLE PULL BOX							
		EA.	904-95.42	ADJUSTMENT OF CONCRETE DOUBLE PULL BOX							
				PEDESTRIAN AND BICYCLE ITEMS							
		EA.	608-60.08	CONCRETE SIDEWALK, CURB RAMP							
		S.Y.	608-60.94	REMOVE AND REPLACE CONCRETE SIDEWALK (4" THICK)							