



Weis Design Group

16296 Westwoods Business Park Drive
Ellisville, Missouri 63021
www.weisdesigngroup.com
(636) 207-0832
(618) 874-0320
f. (636) 207-0328

City of Ferguson
110 Church Street
Ferguson, MO 63135

Carson/Ferguson/Church/Dade Improvements STP No. 5583(604)

WDG No. 9703-13-3

ADDENDUM #1

Page 1 of 4 (including attachments)

Date: May 1, 2017

To: All Contract Bidders of Record

Acknowledge receipt of this Addendum by inserting its number in the Bid Proposal Form. Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents and is attached. It modifies them as follows:

MODIFY SHEETS, SPECIFICATIONS, BID PROPOSAL OF ADDENDUM #1 AS FOLLOWS:

GENERAL INFORMATION:

1. Due to the project not being advertised on MoDOT's website three weeks before the set bid date of May 4, 2017, the bid date will be changed to May 11, 2017 at 11 A.M.

BID SHEET

SCHEDULE 4

SECTION: ROADWAY

LINE ITEM #4:

1. Replace line item "Mill existing asphalt pavement (6' wide sections, 1/2" deep, per plans" with **"Mill ex. asphalt pavement along edges at curb & gutter (0" deep @ 6', 1.5" @ edges)"**
2. Replace quantity with **5100 SY**.

LINE ITEM #5:

1. Replace line item "Mill Existing Asphalt Pavement (Full width from County ROW to end of rounding - 7/8" avg.)" with **Mill Existing Asphalt Pavement (Full Width of County ROW to end of rounding – 1.5" avg.)**

LINE ITEM #6:

1. Replace line item "Mill Existing Asphalt Bridge deck (1/2" deep)" with **"Mill Existing Asphalt Bridge deck (1" deep)"**

LINE ITEM #11:

1. Change quantity of "Remove and Replace Existing Curb Inlet Tops" to **15**.

LINE ITEM #13:

1. Replace line item "7/8" Avg. UBAWS in driving lanes" with **"BP-2 Asphalt Concrete Surface Course – 1.5" average depth (1.75" at CL, 1.25" at edges) in driving lanes (3 passes minimum)"**.
2. Replace quantity with **1527 TN**.

LINE ITEM #14:

1. Replace line item "5/8" Avg. UBAWS on shoulders" with **"BP-2 Asphalt Concrete Surface Course – 1" average depth (1.25" at inside edge, 0.75" at outside edge) on shoulders"**
1. Replace quantity with **394 TN**.

DRAWINGS

1. On sheets 5.10 – 5.16, remove all references to UBAWS overlay and replace with **"BP-2 Asphalt Concrete Surface Course – 1.5" average depth (1.75" at CL, 1.25" at edges) in driving lanes (3 passes minimum)"** or **"BP-2 Asphalt Concrete Surface Course – 1" average depth (1.25" at inside edge, 0.75" at outside edge) on shoulders"**, as appropriate.

SPECIFICATIONS

1. Remove JSP Section K: **ULTRA-THIN ASPHALT WEARING COURSE (ST. LOUIS COUNTY SPECIAL PROVISION 1100.10.4)**

QUESTIONS/ANSWERS

1. **Question:** How big is the "BUS ZONE" lettering on Church St and is it painted?

Answer: The lettering is 24" tall and shall be yellow acrylic waterborne paint.

2. **Question:** Are signs included with the Share the Road pavement symbol line item?

Answer: No, there are no Share the Road signs on this project.

3. **Question:** Do the Share the Road pavement symbols need to include the diamonds?

Answer: No, solid lines are acceptable.

END OF ADDENDUM #1 – ATTACHMENTS TO FOLLOW

Attachments: Bid Sheet Schedule 4

**CITY OF FERGUSON MISSOURI
CARSON/FERGUSON/CHURCH/DADE STREET IMPROVEMENTS**

Item Description	Quantity	Unit	Unit Price	Extended Price
SCHEDULE 4 - FERGUSON AVENUE (5,600') Elizabeth to W. Florissant				
ROADWAY				
1 Mobilization	1	LS	\$	\$
2 Leveling Course	25	TN	\$	\$
3 Slab jacking	20	TN	\$	\$
4 Mill ex. asphalt pavement along edges at curb & gutter (0" deep @ 6', 1.5" @ edges)	5,100	SY	\$	\$
5 Mill Existing Asphalt Pavement (Full width from County ROW to end of rounding - 1.5" avg.)	366	SY	\$	\$
6 Mill Existing Asphalt Bridge deck (1" deep)	936	SY	\$	\$
7 Remove and Replace Rolled Concrete Curb and Gutter - 1.5' wide (includes subgrade)	105	LF	\$	\$
8 Butt Joint	7	EA	\$	\$
9 Adjust Water Valve to Grade	7	EA	\$	\$
10 Adjust Gas Valve to Grade	4	EA	\$	\$
11 Remove and Replace Existing Curb Inlet Tops	15	EA	\$	\$
12 Adjust Existing Manhole Top	6	EA	\$	\$
13 BP-2 Asphalt Concrete Surface Course - 1.5" Avg. depth (1.75" @ CL, 1.25" @ edges) in driving lanes (3 passes minimum)	1,527	TN	\$	\$
14 BP-2 Asphalt Concrete Surface Course - 1" Avg. depth (1.25" @ inside edge, 0.75" @ outside edge) on shoulders	394	TN	\$	\$
15 Remove & Replace Concrete slabs	508	SY	\$	\$
			SUBTOTAL	\$
BIKE / PEDESTRIAN FACILITIES				
1 Share the Road symbols	22	EA	\$	\$
			SUBTOTAL	\$
STRIPING/SIGNAGE/SIGNALS				
1 4" Wide Solid White Acrylic Waterborne Pavement Marking Paint Striping	11,260	LF	\$	\$
2 4" Wide/Double/Solid Yellow Acrylic Waterborne Pavement Marking Paint Centerline Striping	6,400	LF	\$	\$
3 White Turn Arrow Acrylic Waterborne Pavement Marking Paint	12	EA	\$	\$
4 White Stop Bar (24" w.) Acrylic Waterborne Pavement Marking Paint	14	LF	\$	\$
5 Temporary Traffic Control Signs	110	SF	\$	\$
6 Channelizer (TRIM-LINE)	132	EA	\$	\$
7 Install "No Left Turn Sign" on mast arm & cover Left Turn signal beacons on W. Florissant	1	LS		
8 Traffic Barrels (for W. Florissant left turn lane)	10	EA		
9 Install New Vehicle Loop Detectors in New 1" Conduit drilled through pavement (@ Elizabeth Ave)	1	LS	\$	\$
10 Install New Vehicle Loop Detectors in New 1" Conduit drilled through pavement (@ W. Florissant Ave.)	1	LS	\$	\$
			SUBTOTAL	\$

TOTAL SCHEDULE 4 - FERGUSON AVE. \$

TOTAL CONSTR. COST SCHEDULES 1-4 \$