

**ADDENDUM NO. 2
VERNON COUNTY
STOKES ROAD OVER LITTLE
DRY WOOD CREEK PROJECT
Project #BRO-NBIL-B108(42)**

Date: 9/15/2016

To All Plan Holders:

The Vernon County Commission hereby issues the following plan ADDENDUM

The following changes, additions, or deletions are hereby made a part of the Contract Documents for the above noted project, fully and completely as if the same were fully contained therein. All other terms conditions and specifications of the original Invitation to Bid remain unchanged.

CHANGES TO THE CONTRACT DOCUMENTS:

Unit Bid Item: New Seal Coat Quantities and Seasonal Placement

Seal Coat

The seal coat quantities originally indicated in the plans shall be upgraded to include a second seal coat using the same application rate for both applications. The new total quantities will be **1460 gal of Emulsified Asphalt Seal Coat, and 2810 SY of Seal Coat Aggregate, Grade B1.**

If the weather conditions and ambient temperature for placing asphaltic products are not conducive to placement of the surfacing, the new surface placement may be delayed until May of 2017.

After the construction of the new roadway and bridge, the existing Stokes Road roadway can be re-opened to traffic until the new surface is placed on the relocated roadway. The new surface and the "Double" Seal Coat may be placed and completed in May of 2017, thereby revising the working days for placement of the surfacing to the end of May.

Sealed bids for the above project shall be received on the 20th Day of September, 2016 as stated on the original Advertisement.

Signed by the Contractor _____,
_____, 2016