

ADDENDUM NO. 1

ISSUED BY: HOWE COMPANY, LLC
MACON, MO

DATE: July 27, 2016

FOR: LEWIS COUNTY BRIDGE NO. 02900091 REPAIR

The attached revisions hereby supersede any and all data with which they may conflict as indicated on the Drawings, Specifications and related documents issued in the original set. Each trade is responsible for changes in its work caused by changes in the work of other trades. This addendum is a part of and shall be attached to the original set of plans and specifications for the work.

THIS ADDENDUM SHALL BECOME A PART OF THE BID DOCUMENTS NOTED ABOVE. RECEIPT OF THIS ADDENDUM SHALL BE ACKNOWLEDGED ON THE BID FORM.

A NEW BID FORM IS ISSUED WITH THIS ADDENDUM.

THE CONCRETE QUANTITY HAS BEEN REVISED TO 84 CUBIC YARDS AND INCLUDES BOTH THE 30" WIDE FOOTINGS AND 18" THICK PILE ENCASEMENT WALLS.

A BID ITEM FOR TURF REINFORCEMENT MAT WAS ADDED.

ALL BIDDERS SHALL USE THE BID FORM ISSUED WITH THIS ADDENDUM AND THEY SHOULD REVISE THE CONCRETE QUANTITY ON THE PLANS.

THERE IS NO CHANGE IN THE BID OPENING DATE AND TIME.

[Handwritten signature]
7/27/2016

LEWIS COUNTY BRIDGE NO. 02900091
BID FORM - ISSUED BY ADDENDUM #1
ROADWAY ITEMS BY CONTRACTOR

BRIDGE REPAIR
PAGE 1

LINE	ITEM	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT
1	201	Clearing and Grubbing	ACRE	0.33		
2	202	Removal of Improvements	L.S.	1	XXXXXXXXXX	
3	203	Embankment in Place	C.Y.	8,583		
4	203	Unclassified Excavation	C.Y.	5,081		
5	310	4" Layer Crushed Stone Roadway Aggregate	S.Y.	538		
6	616	Movable Barricades	EACH	4		
7	616	Construction Signs	EACH	4		
8	618	Mobilization	L.S.	1	XXXXXXXXXX	
9	805	Seeding	ACRE	0.47		
10	806/JSP	Silt Fence	L.F.	421		
11	806/JSP	Straw Wattles	L.F.	102		
12	806/JSP	Turf Reinforcement Mat	S.Y.	1244		
13	903	Permanent Type 3 Object Marker	EACH	4		

LEWIS COUNTY BRIDGE NO. 02900091
BID FORM - ISSUED BY ADDENDUM #1
BRIDGE ITEMS BY CONTRACTOR

BRIDGE REPAIR
PAGE 2

14	JSP	1 1/4"-1 1/2" Clean Crushed Stone	C.Y.	330		
15	JSP	Mechanically Reinforced Embankment	C.Y.	1778		
16	JSP	Biaxial Geogrid	S.Y.	861		
17	JSP	6" Layer of 3" Crushed Stone (Work Pads/Access Road)	S.Y.	861		
Sub-Total Roadway Items =						

BRIDGE ITEMS BY CONTRACTOR

18	501	Class B-1 Substructure Concrete	C.Y.	84		
19	611.3	MoDOT Type 2 Rock Blanket	C.Y.	1,297		
20	624	MoDOT Permanent Erosion Control	S.Y.	2,104		
21	702	HP 10 x 42 Piling	L.F.	240		
22	702	Pile Points	EACH	8		
23	706	Reinforcing Steel	LBS.	10,557		

LEWIS COUNTY BRIDGE NO. 02900091
BID FORM - ISSUED BY ADDENDUM #1
BRIDGE ITEMS BY CONTRACTOR

BRIDGE REPAIR
PAGE 3

24	JSP	Remove and Replace Guardrail	L.S.	1	XXXXXXXXXX	
----	-----	------------------------------	------	---	------------	--

25	JSP	Clean and Paint Piles	L.S.	1	XXXXXXXXXX	
----	-----	-----------------------	------	---	------------	--

26		Intermediate Bent Enclosure Bent 2 & Bent 3	L.S.	1	XXXXXXXXXX	
----	--	--	------	---	------------	--

Sub-Total Bridge Items =

MISCELLANEOUS ITEMS

21	627	Contractor Surveying and Staking	L.S.	1	XXXXXXXXXX	
----	-----	----------------------------------	------	---	------------	--

Sub-Total Misc. Items =

TOTAL CONTRACTOR =

BID SUBMITTED BY: _____

REPRESENTING: _____

ADDENDUM # INITIAL TO SHOW ACKNOWLEDGEMENT

1	_____
_____	_____
_____	_____
_____	_____