

BID ADDENDUM 1

**Eatherton Road Pedestrian Bridge Over Route 100
TAP-5500(680)**

CITY OF WILDWOOD

The following modifications have been made to the Project Construction Plans and /or Special Provisions.

Item 1: Plan Sheet S1.1 & S1.2 Clarification

See Sheets S1.2 and S1.2 for a graphical depiction of the ϕ values. $\phi_b = 24^\circ$ and is the undisturbed retained backfill. $\phi_r = 34^\circ$ and is the Select Granular Backfill behind the wall. This is based on new terminology in MoDOT's latest standard plans for MSE walls.

Item 2: Plan Sheet 3, C1, C2, C3, S1.1, S2.1, EL-02, L-001, & EC-1 Clarification

Plan sheets illustrate a small return wall on either side of the abutment. This short return is part of the MSE wall to tie into the bridge bent. The length of this return and top and bottom elevations are intentionally excluded to allow for flexibility in the layout for different MSE wall types and different bridge geometries.

Item 3 Plan Sheet S1.1 & S1.2 Clarification

There is a conflict in the stationing on the MSE Walls. Ignore the stations listed on the top of wall in the Elevation view. The stationing in the plan view is correct as follows:

- Sheet S1.1 - Sta. 10+53.62 and Sta. 10+68.78 are correct
- Sheet S2.1 - Sta. 10+83.67 and Sta. 10+98.86 are correct

Item 4 Wall Design Surcharge Clarification

The full traffic surcharge is required for the wall design since maintenance vehicles will have regular access on the bridge and around the walls.

Item 5 Plan Sheet 2 and BID FORM PROPOSAL Page 12

Remove BID PROPOSAL FORM Page 12 and replace it with the attached BID PROPOSAL FORM Page 12.

Remove the words "Buffalograss Sodding" from the Landscaping Items description on Plan Sheet 2 and replace with the words "Kentucky Bluegrass Sodding".

Item 6 JOB SPECIAL PROVISIONS, R. PEDESTRIAN TRUSS SUPERSTRUCTURE, 1.2 Qualified Suppliers

Add the following supplier to the list of Pre-approved Manufacturers:

Big R Bridge
19060 Weld County Road 66
Greeley, CO 80631
1-800-234-0734

| | Description | Unit | Quantity | Unit Cost | Sub Total |
|---|---|------|----------|-----------|-----------|
| 7251000 | CORRUGATED METAL PIPE PILE SPACERS | EA | 6 | | |
| 8061005 | ROCK DITCH CHECK | L.F. | 120 | | |
| 8061019 | SILT FENCE | L.F. | 530 | | |
| | TEMPORARY PEDESTRIAN ACCESS | S.Y. | 110 | | |
| | SEAT WALL | L.F. | 67 | | |
| | FENCE | L.F. | 270 | | |
| | SHADE STRUCTURE | L.S. | 1 | | |
| | SCOUR PROTECTION | S.F. | 560 | | |
| | BLACK POWDER COATING FOR GUARDRAIL | L.S. | 1 | | |
| TOTAL = | | | | | |
| LANDSCAPING ITEMS | | | | | |
| 8034000 | KENTUCKY BLUEGRASS SODDING | S.Y. | 1,527 | | |
| 8089901 | LANDSCAPING | L.S. | 1 | | |
| TOTAL = | | | | | |
| SIGNALS/LIGHTING/SIGNING/STRIPING ITEMS | | | | | |
| 9039901 | REMOVE AND RELOCATE EXISTING SIGNS | L.S. | 1 | | |
| TOTAL = | | | | | |
| *BID ALTERNATIVE 1: PLAZAS AND DECK LIGHTING | | | | | |
| 9019901 | ELECTRIC METER AND LIGHTING CONTROL PANEL | L.S. | 1 | | |
| 9019901{1} | PLAZAS AND DECK LIGHTING | L.S. | 1 | | |
| TOTAL = | | | | | |
| *BID ALTERNATIVE 2: TRUSS AND STRUCTURE LIGHTING | | | | | |
| 9019901{2} | TRUSS AND STRUCTURE LIGHTING | L.S. | 1 | | |
| TOTAL = | | | | | |

(Signature)

(Print Name)

(Company Name)

(Address)

(Telephone Number)

(Fax Number)