



ADDENDUM NO. 1

TO: All Holders of Plans and Contract Documents for Hickory Street Sidewalk Improvements Project, Phase II Project, TAP-9900(736) Mount Vernon, Missouri

ISSUED: April 4, 2016

Name of Bidder:

Receipt Acknowledged By

Gentlemen:

This Addendum is hereby made a part of the Contract Documents to the same extent as if it were originally included herein. This Addendum shall be inserted in the Contract Documents and submitted with the Bid, and includes the following items:

CONTRACT DOCUMENTS:

- 1) The bid schedule is hereby replaced with the attached revised bid schedule. Revision was made to the Seeding & Mulch quantity.
- 2) Job Special Provision #3, 'Inspection and Acceptance Testing', Delete "at the contractor's expense." Testing will be conducted by the consultant and paid for by the Lawrence County Commission as outlined in their existing engineering services agreement. Acceptance testing will **NOT** be conducted at the contractor's expense.

GENERAL INFORMATION:

- 1) The City of Mount Vernon will provide the contractor a place within the city limits to dispose of debris from removals of existing improvements.
- 2) All existing curbing to be removed as shown on the plans. Any removals necessary to complete the project but not quantified in the removal of improvements pay item, shall be considered incidental to the project.

PLANS:

- 1) Quantity for Seeding & Mulch on Sheet 2A & Sheet 2B of the plans shall hereby be revised to 0.27 AC.
- 2) Sheet 10 of the plans erroneously notates the post height at 14'-0" under the Street Light Pole Specifications. The correct post height is 16'-0" as dimensioned in the detail.
- 3) Sheet 10 of the plans erroneously states that the refractor shall be designed for an IES type V distribution. Refractor shall be designed for an IES type III distribution.

Sincerely,
Anderson Engineering, Inc.

J. Andrew Eckhart, P.E.

218 5th Street, Monett, Missouri 65708 • Phone: 417.236.0112 • E-mail: info@andersonengineeringinc.com

CIVIL ENGINEERING • SURVEYING • STRUCTURAL • GIS • MUNICIPAL • GEOTECHNICAL/DRILLING • MATERIALS

ITEMIZED BID SCHEDULE

HICKORY ST. SIDEWALK IMPROVEMENTS, PHASE II
MT. VERNON, MISSOURI

PAGE 1

NAME OF BIDDER: _____

Bidder assures and acknowledges that each unit or lump sum bid price includes the cost of all adjacent, incidental, related, and companion items which are shown on the drawings, called for in the specifications, or otherwise necessary to provide a complete The OWNER reserves the right to increase, decrease, or delete from the Project quantities of work at the Unit Bid Price or Lump Sum Price in order to bring the total contract price to the budgeted project expenditures. The bidder should complete the following sections in accordance with Section 102.7. The bidder proposes to furnish all labor, materials, equipment, services, etc. required for the performance of the work as follows:					
HICKORY STREET SIDEWALK IMPROVEMENTS, PHASE II, TAP-9900(736)					
Item No.	Description	Unit	Quantity	Unit Price	Amount
1	MOBILIZATION	LS	1		
2	SEEDING & MULCH	AC	0.27		
3	LED LUMINAIRE W/ DECORATIVE POLE AND BASE	EA	7		
4	CONDUIT, 2" SCHEDULE 40 PVC	LF	1,002		
5	CABLE, 8 AWG	LF	5,910		
6	REMOVAL OF IMPROVEMENTS	LS	1		
7	CONCRETE SIDEWALKS, 4" THICK	SY	1,014		
8	CONCRETE SIDEWALKS, DRIVEWAY ENTRANCES, 8" THICK	SY	317		
9	STANDARD 2' 6" CURB & GUTTER	LF	2,097		
10	ADA DETECTABLE WARNING STRIPS	SF	146		
11	TYPE 5 AGGREGATE BASE	SY	1,913		
12	HIGH BUILD ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 6" WHITE	LF	212		
13	HIGH BUILD ACRYLIC WATERBORNE PAVEMENT MARKING PAINT, 30" WHITE	LF	102		
14	TEMPORARY TRAFFIC CONTROL SIGNING	SF	41		
15	SIDEWALK BARRICADES	EACH	4		
16	TYPE I DITCH CHECKS	EACH	12		
17	SILT FENCE	LF	315		
Total Base Bid Amount					

THE ITEMS LISTED HEREINAFTER ARE TO BE BID AS ALTERNATES AND ADD ALTERNATES. THESE ITEMS WILL BE CONSIDERED BY THE OWNER AND THE ENGINEER FOR THE PROJECT, SUBJECT TO AVAILABLE FUNDING. THE BID WILL BE AWARDED BASED ON THE PRIORITIZED ALTERNATES TO THE LOWEST RESPONSIVE AND RESPONSIBLE BIDDER. SEE 'ALTERNATES' JOB SPECIAL PROVISION IN CONTRACT DOCUMENTS FOR ADDITIONAL INFORMATION.

ALTERNATE 1: SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON SIGNAL W/FOUNDATION (STA. 7+20)

HICKORY STREET SIDEWALK IMPROVEMENTS, PHASE II, TAP-9900(736)					
Item No.	Description	Unit	Quantity	Unit Price	Amount
A1-1	SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON SIGNAL W/FOUNDATION	EA	2		
Alternate 1 Amount					
Total Base Bid Amount + Alternate 1					