

## **ADDENDUM NO. 1**

# **Greentrails Drive South Reconstruction 2013-PW-06**

Addendum Number 1, attached, is hereby issued. In accordance with section 13 of the Notice to Contractors, addendum acknowledgement is confirmed by including the applicable updated bid documents in the bid submittal and signing and submitting the bid.

March 2016
Department of Public Services
City of Chesterfield, Missouri

#### CITY OF CHESTERFIELD, MISSOURI

#### GREENTRAILS DRIVE SOUTH RECONSTRUCTION

#### **MARCH 24, 2016**

#### ADDENDUM NO. 1

This Addendum is hereby made a part of the Contract Documents for the above referenced project. It supplements and modifies the Project Plans and Bidding Documents previously published.

#### A. CONSTRUCTION PLANS

- 1. Title sheet revised to update correct pagination (see attached)
- 2. Page 2 revised to update geotextile quantities (see attached)

#### B. PROJECT MANUAL:

- 1. Itemized Bid Form. Updated geotextile quantity. Remove and replace Itemized Bid Form with the attached updated Itemized Bid Form.
- 2. DBE Submittal Forms. The percent DBE participation was not provided on the forms. This project includes a 15% DBE goals as shown elsewhere in the DBE requirements. Remove and replace DBE Submittal Form page 1 of 3 with the attached DBE Submittal Form page 1.
- 3. JSP-HH. Section 4.12. Remove and replace with the following:
  - **4.12** All joints shall be placed at right angles to, or radial to, the centerline of the pavement unless directed otherwise. Where both lanes of pavement are to be removed and replaced, a tied keyway shall be provided along the centerline joint per the Construction Details. Dowel bars shall be set in centerline joints in cul-de-sacs and eyebrows, supported to one-half the depth of the pavement.
- 4. JSP-II. Add the following section.
  - **1.4** Streetlights called out on the plans as TBR&R or TBR&RBO shall be handled in the following manner. The contractor shall contact Ameren prior to

the start of the project and communicate the proposed schedule of work affecting the streetlights. Ameren will be responsible for removing the streetlights in order to avoid impacts to the contractor's progress, and then will reinstall the streetlights upon completion of the contractor's work. The contractor shall communicate with Ameren after the concrete removals have been made, as there is a potential for street lighting cable to be affected by the roadway excavation. This cable relocation will also be the responsibility of Ameren. After Ameren and the contractor complete their work within the roadway limits but before finish grading and sod placement takes place, the contractor shall contact Ameren to schedule installation of the streetlight poles prior to sodding. Any damage to newly-placed sod caused by the contractor failing to contact Ameren will require sod replacement at the sole cost of the contractor. No payment will be made to the contractor for this coordination, nor shall any payments for delays (perceived or actual) be made.


- 5. JSP-XX. Section 1.0. Add the following permit requirements:
  - d) St. Louis County Right of Way Permit (detour signage) and Construction Permit (pavement tie-ins)


#### C. CLARIFICATIONS

- 1. Pre-Bid Meeting Agenda is attached for reference.
- 2. Proposed pavement is 7" Portland cement concrete pavement with Type B longitudinal joints as shown on pages 10 and 11 of the construction plans.
- 3. Grated Trough
  - i. The grates for the proposed grated trough at approximate Sta. 47+75 do not extend across the entire roadway. See detail on Sheet 33 of the construction plans. It is anticipated that there will be 6 grates on each side of the street, 12 grates total for the grated trough.
  - ii. The grated trough bid item includes the required inlet, A2 joints, grates, etc. to make a complete and usable grated trough.
- 4. Linear Grading Class 1 is typically indicative of minimal cut and fill. This project will generate excess material. See JSP H regarding excess material.
- 5. There are no pavement lugs included in this project.
- Trees to be removed (TBR) and trees to use in place (UIP) are shown on the project plans. Some trees between the existing back of curb and sidewalk will remain and are indicated as such on the construction plans.

#### **END OF ADDENDUM NO. 1**

## FEDERAL PROJECT NO. STP-5410(619)





NUMBER_	DESCRIPTION
1	TITLE AND INDEX SHEET
2 - 9	SUMMARY OF QUANTITIES
10 - 11	TYPICAL SECTIONS
12	REFERENCE TIES AND
	ALIGNMENT INFO
13 - 21	MAINLINE PLAN AND PROFILE SHEETS
22 - 24	SIDE ROAD PLAN AND PROFILE SHEETS
25 - 30	INTERSECTION GEOMETRICS AND WARPING SHEETS
31	STORM SEWER PROFILES
32	WATER QUALITY DETAILS
~~33~~~	GRATED TROUGH DETAILS
34 - 35	STRIPING AND SIGNAGE
36 - 41	EROSION CONTROL
42 - 45	TRAFFIC CONTROL 5
<b>46 - 95</b>	CROSS SECTION SHEETS
4	
	<u> </u>

LOCATOR MAP

Missouri River

PROJECT LOCATION

#### PROJECT SPECIFIC INFORMATION

#### BENCHMARKS USED IN PROJECT

"SQUARE" CUT IN THE NORTHEAST CORNER OF THE BASE FOR A SUBDIVISION MONUMENT ("LADUE WOODS").

- . THIS PROJECT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ST. LOUIS COUNTY TRANSPORTATION DEPARTMENT STANDARD DRAWINGS (LATEST VERSION) AND THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (LATEST EDITION), BOTH AVAILABLE FOR DOWNLOAD OFF THE ST. LOUIS COUNTY WEBSITE, AS WELL AS THE PROJECTS JOB SPECIAL PROVISIONS INCLUDED IN THE BID PROPOSAL.
- . IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO CONTACT BOTH MISSOURI ONE CALL (DIGRITE) AND EACH INDIVIDUAL UTILITY THAT MAY NOT BE PART OF THE MISSOURI ONE-CALL PROGRAM TO ARRANGE FOR INDIVIDUAL UTILITY LOCATES
- 3. PRIOR TO OBTAINING A CONSTRUCTION PERMIT FROM THE METROPOLITAN SEWER DISTRICT, THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE THE DISTRICT WITH A COPY OF AN EXECUTED CERTIFICATE OF INSURANCE INDICATING THAT THE PERMITTEE HAS OBTAINED AND WILL CONTINUE TO CARRY COMMERCIAL GENERAL LIABILITY AND COMPREHENSIVE AUTO LIABILITY AND EXPLAINED AS TO A COMPREHENSIVE AUTO LIABILITY INSURANCE. THE REQUIREMENTS AND LIMITS SHALL BE AS STATES AND REGILLATIONS AND ENGINEERING DESIGN REQUIREMENTS FOR SANITARY AND STORMWATER DRAINAGE FACILITIES, FEBRUARY 2006, SECTION 10.090.

ANY FUTURE LAND DISTURBANCE AND/OR INCREASE IN IMPERVIOUS AREA ON THIS SITE MAY REQUIRE ADDITIONAL STORM WATER MANAGEMENT PER MAD REGULATIONS IN PLACE AT THAT TIME (INCLUDING TOTAL LAND DISTURBANCE AND/OR IMPERVIOUSNESS ADDED ON THIS PLAN P-30004-00).

DETENTION FOR ANY FUTURE DEVELOPMENT SHALL INCLUDE THESE IMPROVEMENTS AS WELL.



#### SCALES.

PROFILE CROSS SECTION: PIPE PROFILE

1" = 20' HORIZ. & 5' VERT = 5' HORIZ. & 5' VERT. 1" = 20' HORIZ, & 5' VERT

APPARENT LENGTH 4,381.46 FEET EQUATIONS AND EXCEPTIONS 0.00 FEET TOTAL CORRECTIONS 0.00 FFFT NET LENGTH OF PROJECT 4,381.46 FEET STATE LENGTH 0.83 MILES FEDERAL LENGTH 0.83 MILES DESIGN CRITERIA FUNCTIONAL CLASSIFICATION: COLLECTOR DESIGN YEAR: 2014/2015

LENGTH OF PROJECT / DESIGN CRITERIA

10+14 57

53+96.03

SOUTH GREENTRAILS DRIVE

BEGINNING OF PROJECT


END OF PROJECT

CURRENT ADT (YEAR) 790 (2009) DESIGN ADT (YEAR): 1,200 (2025) DIRECTIONAL DISTRIBUTION (D) = N/A TRUCK PERCENTAGE (T) = DESIGN SPEED (V) = 30 MPH POSTED SPEED (V) = 25 MPH

INDERGROUND FACILITIES, STRUCTURES AND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS: AND, THEREFORE THEIR LOCATIONS MUST BE CONSIDERED APPROXIMATE ONLY. IT IS POSSIBLE THERE MAY BE OTHERS, THE EXISTENCE OF WHICH IS PRESENTLY NOT KNOWN OR SHOWN. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THEIR EXISTENCE AND EXACT LOCATION AND TO AVOID

#### MSD CERTIFICATION

THE EXISTING SEWER LENGTHS, SIZES, FLOWLINES, DEPTHS OF STRUCTURES AND SEWERS AND LOCATIONS WITH RESPECT TO XISTING OR PROPOSED EASEMENTS HAVE BEEN MEASURED. THE RESULTS OF THOSE MEASUREMENTS ARE SHOWN ON THIS SET OF FINAL MEASUREMENT PLANS, SINCE THE WYE LOCATIONS HAVE BEEN PLOTTED FROM INFORMATION PROVIDED BY THE SEWER CONTRACTOR OR OTHER SOURCES, I DISCLAIM ANY RESPONSIBILITY FOR THAT SPECIFIC INFORMATION.



M.S.D. P-NUMBER: P-0030288-00 M.S.D. BASE MAP 17R. 18R REVIEW ENGINEER: EUGENE W. JOHNSON

APPROVED: JAMES ECKRICH, P.E. PUBLIC WORKS DIRECTOR CITY ENGINEER DATE:

CITY PROJECT NO. 2013-PW06 EDERAL PROJECT NO. STP-5410(619) 5753-14 P-0030288-00






CITY ENGINEER

GREENTRAILS I RECONSTRU

A SCHUMANI

J DOHRMANN

SHEET SEQUENCE: 1 OF 95



UNLESS NOTED

APPROVAL DATE:

207-10.0	207-10.00 LINEAR GRADING, CLASS 1								
LOCATION	STATION	STATION	LENGTH						
			(STA.)						
GREENTRAILS	10+14.57	53+96.03	43.9						
COBBLE HILL	198+82.23	201+62.52	2.9						
MANOR	300+00.00	300+91.15	1.0						
COOPERSTOWN	399+41.35	400+00.00	0.6						
HARTWELL	499+30.91	500+00.00	0.7						
BRANCHPORT	599+47.32	600+00.00	0.6						
DINSMOOR	697+57.82	702+15.01	4.6						
TEALCREST	799+43.32	800+00.00	0.6						
MINITREE	999+39.22	1000+00.00	0.7						
TOTAL =			55.6						

<u> EARTHWORK - FOR INFORMATI</u>	ONAL PURP	OSES ONLY		
LOCATION		UNCLASSIFIED EXCAVATION*	COMPACTING EMBANKMENT*	HAUL OFF*
		(C.Y.)	(C.Y.)	(C.Y.)
GREENTRAILS		9,133	1,242	7,891
COBBLE HILL		218	56	162
MANOR		51	6	45
COOPERSTOWN		11	1	10
HARTWELL		24	2	22
BRANCHPORT		4	0	4
DINSMOOR		1,001	62	939
TEALCREST		8	1	7
MINITREE		13	3	10
EARTHWORK FOR AMENDED SOIL		5,013	0	5,013
	TOTALS =	15.476	1.373	14.103

NOTE: NO SHRINKAGE FACTOR APPLIED. \*NO DIRECT PAYMENT FOR THIS BID ITEM WILL BE MADE. TABULATION IS FOR INFORMATIONAL PURPOSES ONLY.

205-00.99 MODIFIED SUBGRADE - STRUCTURAL GEOGRID*						
LENGTH	WIDTH	AREA				
(FT.)	(FT.)	(S.Y.)				
200	36	800				
TOTAL =	TOTAL =					

*ACTUAL QUANTITY	IS CONTINGENT UPON MEASURED VALUE IN THE	
FIELD. SEE JSP.		

203-60.10 UNSUITABLE MATERIAL*								
LENGTH	WIDTH	DEPTH	VOLUME					
(FT.)	(C.Y.)							
200	36	1	267					
TOTAL =	267							
*ACTUAL QUA	NTITY IS CONT	INGENT UPON	MEASURED					

*ACTUAL QUANTITY IS CONTINGENT UPON MEASURED
VALUE IN THE FIELD. SEE JSP.

803-10.99 MAILBOXES					
LOCATION	MAILBOX				
	(EACH)				
VARIES	34				
TOTAL =	34				

								$\sim$
CONCRE	TE PAVEMENT							
SHEET	STATION	STATION	ROUTE	LENGTH	WIDTH	304-05.04	502-11.07	624-10.02
						TYPE 5 AGGREGATE BASE (4" THICK)	CONCRETE PAVEMENT (7* NON- REINFORCED)	GEOTEXTILE FABRIC, STABILIZATION AND SEPARATION, CLASS 2 (MEDIUM WEIGHT)
				(L.F.)	(FT)	(S.Y.)	(S.Y.)	(S.Y.)
							(	
13	BOP	14+50.00	GREENTRAILS	435	26 & 36	1699	1556.3	1699
14	14+50.00	19+50.00	GREENTRAILS	500	36	2081	1916.9	2081
14	199+25.00	199+82.75	COBBLE HILL	58	25.5	217	205.2	217
14	200+17.25	200+75.00	COBBLE HILL	58	25.5	223	211.4	223
14	300+17.25	300+91.15	MANOR	74	26	263	243.8	263
15	19+50.00	24+75.00	GREENTRAILS	525	36	2165	2010.8	2165
15	399+41.35	399+82.75	COOPERSTOWN	41	27	179	173.7	179
16	24+75.00	30+00.00	GREENTRAILS	525	36	2170	2010.9	2170
16	499+30.91	499+81.00	HARTWELL	50	27	206	196.8	206
16	599+47.32	599+82.75	BRANCHPORT	35	26	150	146.5	150
17	30+00.00	35+00.00	GREENTRAILS	500	26 & 36	1910	1751.4	1910
17	699+25.00	699+87.10	DINSMOOR	62	25.5	233	214.3	233
17	700+12.25	701+00.00	DINSMOOR	88	25.5	304	291.3	304
18	35+00.00	40+25.00	GREENTRAILS	525	36	2183	2012.2	2183
18	799+43.32	799+82.75	TEALCREST	39	26	156	149.9	156
19	40+25.00	45+75.00	GREENTRAILS	550	VARIES	2459	2263.7	2459
19	999+39.22	999+81.00	MINITREE	42	20	148	140.3	148
20	45+75.00	51+00.00	GREENTRAILS	525	26 & 36	1854	1659.4	1854
21	51+00.00	EOP	GREENTRAILS	296	26	977	870.7	977
22	198+82.23	199+25.00	COBBLE HILL	43	25.5	131	114.0	131
22	200+75.00	201+62.52	COBBLE HILL	88	25.5	266	239.4	266
23	697+57.83	699+25.00	DINSMOOR	167	25.5	515	452.4	515
23	701+00.00	702+15.10	DINSMOOR	115	25.5	346	306.1	346

StL Cnty = LATEST EDITION OF ST. LOUIS COUNTY STANDARDS FOR HIGHWAY CONSTRUCTION  ${\tt MoDOT} = {\tt LATEST} \ {\tt EDITION} \ {\tt OF} \ {\tt MISSOURI} \ {\tt STANDARDS} \ {\tt FOR} \ {\tt HIGHWAY} \ {\tt CONSTRUCTION}, \ {\tt BY} \ {\tt THE} \ {\tt MISSOURI} \ {\tt DEPT} \ {\tt OF} \ {\tt TRANSPORTATION}$ JSP = JOB SPECIAL PROVISIONS, AS ATTACHED IN THE PROJECT MANUAL

CONSTRUCTION SIGNS ARE FOR USE IN TRAFFIC CONTROL AND ARE TEMPORARY. RELOCATION OF THE SIGNS DURING VARIOUS STAGES OF CONSTRUCTION IS CONSIDERED INCIDENTAL TO QUANTITY OF CONSTRUCTION SIGNAGE.

BID FOR PIPE INCLUDES EXCAVATION AND GRANULAR BACKFILL AS REQUIRED IN THE SPECIFICATIONS

REMOVAL OF IMPROVEMENTS = 1 LUMP SUM
MOBILIZATION = 1 LUMP SUM
CONTRACTOR FURNISHED SURVEYING AND STAKING = 1 LUMP SUM
DESTRUCTION AND SHAPE
RESTORATION = 1 LUMP SUM

\*CONCRETE PAVEMENT (7" NON-REINFORCED) IS PAID TO THE FLOWLINE OF THE INTEGRAL CURB.

703-90.15 MODULAR BLOCK WALL (H<4')							
SHEET	STATION	STATION	ROUTE	SIDE	AREA		
					(S.F.)		
17	32+75.59	32+96.59	GREENTRAILS	LT	66		
17	32+75.75	32+96.75	GREENTRAILS	RT	66		
17	33+41.76	33+60.62	GREENTRAILS	LT	62		
17	33+47.49	33+71.11	GREENTRAILS	RT	72		
TOTAL =					266		

P-0030288-00 MSD BASE MAP: 17R, 18R

CITY PROJECT NO. 2013-PW06

EDERAL PROJECT NO. STP-5410(619)

E-W GATEWAY TIP NO. 5753-14



3/23/16



JAMES ECKRICH, P.E. PUBLIC WORKS DIRECTOR CITY ENGINEER OUANTITIES 1 OF 8)

RD.) Ś GREENTRAILS DRIVE S RECONSTRUCTION (WHITE RD. TO LADUE RI

DESIGNE A SCHUMANN

DRAWN: A. SCHUMANN CHECKED

SUMMARY OF (

.I DOHRMANN SHEET SEQUENCE:

2 OF 95

# Greentrails Drive South Reconstruction - Chesterfield, MO STP-5410(619)

ITEMIZED BID FORM								
ITEM NO.	JSP	DESCRIPTION		QUANTITY	BID PRICE		EXTENSION	
		ROA	ADWAY	Y ITEMS				
201-20.10	S, T	CLEARING AND GRUBBING	L.S.	1				
201-20.99	S	TREE REMOVAL (CONTINGENT)	EACH	0				
202-20.10	H, U, CC	REMOVAL OF IMPROVEMENTS	L.S.	1				
202-20.99	II	RESTORATION	L.S.	1				
203-60.10	DD	UNSUITABLE MATERIAL	C.Y.	267				
205-00.99	EE	MODIFIED SUBGRADE - STRUCTURAL GEOGRID	S.Y.	800				
207-10.00	GG	LINEAR GRADING, CLASS 1	STA.	55.6				
304-05.04		TYPE 5 AGGREGATE BASE (4" THICK)	S.Y.	20,835				
502-11.07	НН	CONCRETE PAVEMENT (7" NON-REINFORCED)	S.Y.	19,137				
502-90.99	RR	TYPE A2 JOINT	L.F.	834				
603-10.99	JJ	ADJUST SERVICE VALVE TO GRADE	EACH	30				
604-12.01		SINGLE CURB INLET, UNTRAPPED	EACH	5				
604-20.30		ADJUST MANHOLE TO GRADE	EACH	3				
604-22.32	SS	GRATED TROUGH (32')	EACH	1				
604-26.50		CONVERT CURB INLET TO AREA INLET AND ADJUST TO GRADE	EACH	2				
604-90.50		REPLACE PRECAST INLET TOP AND ADJUST TO GRADE	EACH	22				
604-90.52		REPLACE INLET SILL	EACH	22				
605-10.10	KK	CLASS "A" UNDERDRAIN	L.F.	262				
607-30.20	AAA	ALUMINUM HANDRAIL	L.F.	243				
608-50.06	LL	PAVED APPROACH (6")	S.Y.	1,294				
608-50.99	MM	DRIVEWAY EXTENSION	S.Y.	360				
609-20.99	K	INTEGRAL CURB (MOUNTABLE 6" HEIGHT)	L.F.	8,768				
611-30.99	L	MSD TYPE 5 ROCK BLANKET	S.Y.	28				
612-10.30	NN, OO	MOVEABLE BARRICADE (STANDARD)	EACH	25				
616-10.05	NN, OO	CONSTRUCTION SIGNS	S.F.	347				
616-10.25	NN, OO	CHANNELIZERS	EACH	228				
616-10.95	NN, OO	EDGE DROP-OFF TREATMENT	L.F.	9,148				
617-10.90	NN, OO	TEMPORARY CONCRETE MEDIAN BARRIER, TYPE A (INCLUDES END SECTIONS)	L.F.	170				
619-00.00		MOBILIZATION	L.S.	1				
L	·	ļ.						

# Greentrails Drive South Reconstruction - Chesterfield, MO STP-5410(619) ITEMIZED BID FORM (continued)

		ITEMIZED BI	א ע	JKIVI (C	ontinuea)	
		ROADWA	Y ITEM	IS (continu	ıed)	
624-10.02	FF	GEOTEXTILE FABRIC, STABILIZATION AND SEPARATION, CLASS 2 (MEDIUM WEIGHT)	S.Y.	20,835		
627-40.00	G	CONTRACTOR FURNISHED SURVEYING AND STAKING	L.S.	1		
703-90.15		MODULAR BLOCK WALL (H<4')	S.F.	266		
726-13.12		12" CLASS III REINFORCED CONCRETE PIPE CULVERT	L.F.	488		
731-00.42		PRECAST CONCRETE MANHOLE, 42"	EACH	1		
732-00.12		12" RCP FLARED END SECTION	EACH	1		
803-10.00		SODDING	S.Y.	8,785		
803-10.99	ZZ	MAILBOXES	EACH	34		
804-20.99	М	AMENDED SOIL	S.Y.	5,013		
806-16.99	N	DRY SWALE WITH UNDERDRAIN	L.F.	816		
806-45.99	PP	SWPPP DESIGN, INSTALLATION, MAINTENANCE, AND REMOVAL	L.S.	1		
808-90.99	R	STREET TREES	EACH	45		
					Roadway Subtotal:	
		SIGNING, STRIPING,	SIGNA	LS, AND LI	IGHTING ITEMS	
621-20.17	Р	PERMANENT PAVEMENT MARKINGS, PAINT	S.F.	157		
621-20.99	Р	PERMANENT PAVEMENT STRIPING, PAINT (4" YELLOW)	L.F.	8,520		
621-20.99	Р	PERMANENT PAVEMENT STRIPING, PAINT (4" WHITE)	L.F.	5,190		
621-20.99	Р	PERMANENT PAVEMENT STRIPING, PAINT (6" WHITE)	L.F.	420		
903-10.99	0	PERMANENT SIGNING	S.F.	205		
		Sig	ning, St	riping, Sign	als, and Lighting Subtotal:	
		BIKE AND	PEDES	STRIAN IT	EMS	
608-60.04	J, Q	CONCRETE SIDEWALK	S.Y.	5,191.0		
608-60.98	CCC	TRUNCATED DOMES FOR CURB RAMPS (NEW CONSTRUCTION)	S.F.	360		
				Dile	e and Pedestrian Subtotal:	

BID TOTAL:		

## **DBE Submittal Forms**

(6)	<u>DBE Submittal Forms:</u> This form must be submitted by 4 p.m. three (3) business days after bid opening.
	(A) <u>DBE Contract Goal</u> : By submitting this bid, the bidder certifies that the bidder is familiar with the DBE Program Requirements in this contract. The contract DBE goal for the amount of work to be awarded is 15% of the total federal project price. The bidder shall also complete the DBE Submittal Form in accordance with the program requirements.
	(B) <u>DBE Participation</u> : The bidder certifies that it will utilize DBE's as follows:
	% OF TOTAL FEDERAL CONTRACT
	NOTE: Bidder must fill in the above blank. If no percentage is specified, the bidder certifies that it agrees to, and will comply with the contract goal. If a percentage below the contract goal is specified, then the bidder must submit complete documentation of good faith efforts to meet the DBE contract goal, immediately below.
	(C) <u>Certification of Good Faith Efforts to Obtain DBE Participation</u> : By submitting its signed bid, the bidder certifies under penalty of perjury and other provisions of law, that the bidder took each of the following steps to try to obtain sufficient DBE participation to achieve the Commission's proposed DBE Contract Goal: (Attach additional sheets if necessary).

Fig 136.9.9 1 of 3 Jan 2012



## Pre-Bid Meeting Greentrails Drive South Reconstruction 2013-PW-06 STP-5410(619)

3/23/2016 10:00 AM Chesterfield City Hall

#### **GENERAL ITEMS**

- Attendance Sheet
- Project Overview
  - Reconstruction of Greentrails Drive South between Ladue Road and White Road.
  - Removal and replacement of approximately 19,130 square yards of pavement, 8,768 lineal feet of curb with 7-inch Portland cement concrete (PCC) pavement with a 6" mountable curb, over 4-inches of Type 5 Aggregate over a geotextile layer on a prepared subgrade.
  - Work will also include removal and replacement of existing 4' wide sidewalk with 5' wide sidewalk, as well as storm sewers, underdrains, expansion joints, striping, restoration, traffic control, paved approaches and driveway extensions, curb ramps, and all other necessary and incidental work to make for a complete and usable roadway.
  - Staged construction will be required to maintain traffic on Greentrails Drive South during the construction of this project. Greentrails Drive will be one-way, south bound, for the project. North bound traffic will be detoured.
- Project Contacts
  - o HR Green, Inc.
    - Jason Dohrmann, PE
    - **636-812-4209**
    - jdohrmann@hrgreen.com
  - City of Chesterfield
    - Zachary Wolff, PE
    - **•** 636-537-4757
    - zwolff@chesterfield.mo.us

#### **BIDDING AND AWARD**

- Schedule
  - o Bids Due and Bid Opening: 10:00am April 6<sup>th</sup>, 2016 Chesterfield City Hall
  - Project will be awarded to the lowest, responsive, and responsible bidder with MoDOT concurrence

- o Notice of Award: Tentatively April 21, 2016 (pending City Council schedule)
  - Required submittals See JSP E, 7.0
- o Notice to Proceed: Tentatively May 9<sup>th</sup>, 2016
- o Time of Completion 180 calendar days (November 2016)

#### Bid Submittal

- Federally funded project
  - Prevailing Wage
  - MoDOT's Qualified Contractor List (if not on the list, must submit to MoDOT at least 7 days prior to the bid opening)
  - 10-Hour OSHA
  - DBE: 15% participation goal
  - On the Job Training: 1 slot at 1000 hours
    - Additional OJT information and forms can be found on MoDOT's website, See JSP D.
  - ADA Compliance
  - Buy America
- See the Bidder's Checklist in the Bid Packet
- Any addenda will be e-mailed, posted to MoDOT's bidding website and the City's website, you will be asked to confirm receipt of any and all addenda
- Bid Quantities are approximate and are subject to change.

#### CONSTRUCTION

#### • Residents:

- The City, as always, wants to keep the inconveniences and safety hazards to our residents to a minimum. All excavations will need to be barricaded when unattended and storage areas will need to be kept clear. Contractor vehicles are not to be parked in intersections and should not block the path of traffic unless being loaded/unloaded.
- o Keep all trash picked up and don't have after work gatherings in the area.
- Notification
  - Contractor to provide written notification to residents a minimum of 48 hours in advance of work that will limit access to driveways. (door hanger, letter, etc.)
    - City will place step stakes that can be utilized for construction notices.
    - Door to door notifications are encouraged by field personnel.
- Minimize construction traffic in the adjacent residential neighborhoods. Utilize Ladue Road and White Road for access to the site.
- Work Areas & Phasing
  - o The project is divided into 2 phases. Phases 1 is the west side of Greentrails Drive

and Phase 2 is the east side of Greentrails Dr.

 The contractor must complete all work, including clean-up activities, in each phase before moving to the next phase. It may be possible to get permission to move into the next phase, however, the contractor should not expect this permission.

#### • Permits – See JSP XX

- DNR Land Disturbance
- o MoDOT Right-of-way
- o MSD Construction
- o St. Louis County Right-of-way/construction

#### • Utilities – See JSP QQ

- Utility adjustment work is necessary and either has been completed or is in progress.
   Main utility adjustments at Greentrails Dr./Dinsmoor Intersection
- Existing facilities (valve box, grade rings, etc.) may need adjusted to grade by the Contractor.
- o Contractor responsible for notifying Missouri One-Call.

#### • Traffic Control – See JSP OO and plan sheets 42 to 45

- Awarded Contractor will be required to submit a traffic management plan including phasing, materials, and construction sequence prior to starting work.
- Temporary Traffic Control is inclusive of any temporary pavement marking to maintain traffic control prior to final pavement striping.
- o Detour route must remain clearly marked throughout construction.

#### Payments

- The City's site inspector, HR Green, is required to make measurements of all work performed. It is highly recommended that the contractor meet with the inspector each day to verify the measured quantities.
- o The Contractor will prepare monthly pay estimates for the City to review/approve.
- Pay Estimates will need to be submitted on the City's Pay Application form and will need to be accompanied by the following at a minimum:
  - Partial lien waivers
  - Certified payroll
  - OJT Monthly Trainee Report

#### Work Hours

- o Work hours are limited to between 7:00 am and 6:00 pm Monday through Friday.
- Work hours can be extended to 9:00 pm solely for the purpose of making the initial saw cuts for jointing newly placed pavement.
- Work hour restrictions include equipment startup, deliveries, and loading/unloading equipment.

#### Trees

- o Replacement (JSP R): Coordinate with owners to select replacement tree species.
  - In conjunction with the construction notice, City will request residents select replacement tree species and notify the City and/or Contractor.
- o Clearing and Protection (JSP S): Protection of tree to remain is critical.

#### • Truck Restrictions (JSP VV)

All loads are restricted to a maximum gross vehicle weight of 65,000 pounds.
 Concrete trucks are limited to a maximum load of 8 cubic yards. These restrictions will be enforced.

#### • Testing and Inspection (See JSP YY)

- HR Green will provide construction inspection and is responsible for materials testing. There will also be a City inspector assigned to the project.
- Subgrade must be compacted and observed prior to placement of fabric and base rock. Unsuitable subgrade will be removed and replaced.
- Base rock must be tested for proper compaction and thickness prior to concrete placement.
- Concrete cylinders will be made with each pour. At a minimum 2 cylinders will be tested at each of the following times: 3 days, 5 days, and 28 days. Additional cylinders can be prepared at the contractor's request for early strength tests. Pavement may be cored after a phase has been completed to check pavement thickness.
- A straight edge will be run along the traffic lanes to test smoothness of the pavement.
   See JSP W.

#### • Concrete (See JSP HH)

- o Full depth saw cuts are required at the limits of removal.
- The addition of a finishing aid to the surface of freshly placed concrete will not be permitted. The use of a 10 foot paver's straightedge will be required on all pours. The use of a Fresno paddle is required.
- o 7" PCC pavement (Type B longitudinal joints).
- o Damaged and Defective Pavement (JSP HH, 8.0)
  - Damaged and defective pavement requiring replacement shall be replaced with a high early strength concrete mix.
  - The high early mix has minimum strengths of 2,500 in 24 hours and 3,000 in 48 hours.
  - Replacement slabs not meeting these requirements will be deducted from the pay quantities

#### • Storm Sewer and Inlets

- o New storm sewer subject to MSD permit and inspection
- o Underdrains are to be installed as shown on the drawings and at locations directed by

the inspector.

- o Rebuilding or replacing inlet sill, top, and/or adjustments to grade, will be determined after excavation of the pavement.
- o Grated Trough (JSP SS): Includes all items necessary for Grated Trough (inlet, A2 joints, etc.)

#### • Backfill (JSP HH, 6.0) and Amended Soils (JSP M)

- Backfill behind curbs is required before opening the pavement to traffic and excavation of the opposite side of the street. Backfill shall be compacted. Backfill includes filling isolated low spots between the back of curb and sidewalk to promote proper drainage.
- o Amended Soils: 2" thick compost layer tilled in to backfill.

#### • Dry Swale with Underdrain (JSP N)

- o Includes all elements necessary for construction including excavation, piping, bioretention media, sand, gravel, observation well, and piping.
- o Protect from any runoff and sediment until roadway is complete.

#### • Driveway Access (JSP AA)

- Work must progress so that no residential driveway is out of service more than 10 days.
- o Several driveways must remain accessible throughout construction.
- In the event of rain that would extend a closure beyond 10 days, driveways must be rocked in to allow residents entry to their driveway unless otherwise approved by the resident.
- o Commercial driveways shall remain open unless other arrangements are approved in writing with the property owner.

#### • Stormwater Pollution Prevention Plan (JSP PP)

- o Contractor is responsible for SWPPP installation, maintenance, and removal.
- o DNR Permit
- Weekly inspection shall be conducted and reports submitted to the City.

#### • Sidewalk and Curb Ramps (JSP J)

- o Remove and replace nearly all existing 4' sidewalk with new 5' wide sidewalk.
- o Sidewalk and curb ramps must meet ADA requirements.
  - Contractor is responsible for layout and compliance, inspectors will assist.

#### **QUESTIONS**