

## **ADDENDUM NO. 1**

### **ROCK CREEK GREENWAY TRAIL – PHASE 1 PROJECT TP1571 Federal Project No. STP-3313(409)**

GLADSTONE, MISSOURI

DATE: January 25, 2016

This Addendum forms a part of the Contract described above. The original Contract Documents and any prior addenda remain in force and effect except as modified by the following which shall take precedence over any provisions in the prior documents

#### **Addendum No. 1:**

##### **Project Manual:**

##### **JSP-30 “Pedestrian Signal Installation”**

- The City of Gladstone has had preliminary conversations with Kansas City Power and Light regarding the feed for the power supply required in both the base bid and bid alternates. Power shall originate from KCP&L Pole No. 276874 located near the trail crossing on the south side of NE 64<sup>th</sup> Street. The unit price for the power supply and foundation in both the base bid and bid alternates shall include coordination with KCPL, the meter can and disconnect, conduit, and conductor to the new transformer. KCPL shall be responsible for all connections to their system. The City of Gladstone will be responsible for all fees required from KCPL to provide service.
- This shall be an Accessible Pedestrian Signal (APS). The pedestrian push button shall include audible features and a come complete with a 9”x12” R10-3E sign with black finish.
- The pedestrian countdown signal shall be housed in a 16” polycarbonate enclosure.

##### **JSP-31 “Large Block Retaining Wall” contained in the Project Manual:**

- Add the following: The design of the large block retaining wall shall include global stability analysis.
- Change the finish of the block from weathered limestone to split face limestone.

**Project Drawings:**

Sheet 15 of 22 "Typical Section – Bid Alternate No. 1":

- It is the intent of the City of Gladstone to construct the proposed wall a minimum of 1-foot above the elevation of the trail on the creek side. The wall in this area shall include a double-faced top block and cap block. The top block and cap block shall be securely fastened to the remainder of the wall to prevent movement from trail users and high stream flows.

Sheet 21 of 22 "40' Pre-Fabricated Bridge Detail":

- Change the length of the bridge shown on Sheet 21 of 22 from 40-feet to 45-feet to match the plan view and Bid Form.

\*\*\*\*\*

Each Bidder shall acknowledge receipt of this addendum by fixing his signature below, by noting this addendum on his Proposal, and by attaching this addenda to his Bid.

City of Gladstone , 7010 N. Holmes, Gladstone, Missouri 64118

**ACKNOWLEDGEMENT**

The undersigned acknowledges receipt of this addendum and the Bid submitted is in accordance with information, instructions and stipulations set forth herein.

Bidder \_\_\_\_\_

By: \_\_\_\_\_

Date: \_\_\_\_\_