

July 23, 2015

To: Plan Holders for Improvements to the

Rosecrans Memorial Aiport

St. Joseph, Missouri

MoDOT Project No. 13-012A-2

Air National Guard Project No. ULYB132006

Transmitted herewith is Addendum **No. 3** to the Issued for Bid Contract Documents, Specifications and Plans dated June 23, 2015 for Improvements to the Rosecrans Memorial Airport.

Schedule I: Replacement of Assault Strip Runway 13/31



Sincerely,

Jviation, Inc.

Ryan B. Lorton, P.E. Project Manager

Addendum No. 3

July 23, 2015

To: Contract Documents,
Specifications, and Plans
MoDOT Project No. 13-012A-2
Air National Guard Project No. ULYB132006
Dated: June 23, 2015

ADDENDUM NO. 3

TO

CONTRACT DOCUMENTS, SPECIFICATIONS AND PLANS FOR IMPROVEMENTS TO THE ROSECRANS MEMORIAL AIRPORT ST. JOSEPH, MISSOURI MODOT PROJECT NO. 13-012A-2 AIR NATIONAL GUARD PROJECT NO. ULYB132006

Bidders are informed that the above referenced Contract Documents, Specifications and Plans are modified as follows as of July 23, 2015:

1. CONTRACT DOCUMENTS

Section: Requests for Bids/Invitation for Bids

Page: 1

Revision: First sentence: Revise the bid opening date to read as follows:

"3:00 p.m. (CST), Tuesday, August 4, 2015"

Section: Section 1: Notice to Bidders

Page: 1

Revision: First sentence: Revise the bid opening date to read as follows:

"3:00 p.m. (CST), Tuesday, August 4, 2015"

2. ATTACHMENTS

- Pre-Bid Agenda and Sign-In Sheet

The last time for questions has been extended to Friday, July 24, 2015, at 5:00 p.m. CST. A fourth Addendum is anticipated to be issued by July 28, 2015, to address the questions received to date.

END OF ADDENDUM NO. 3



ROSECRANS MEMORIAL AIRPORT REPLACEMENT OF ASSAULT STRIP RUNWAY 13/31 PRE-BID CONFERENCE

MoDOT PROJECT NO. 13-012A-2 AIR NATIONAL GUARD PROJECT NO. ULYB 132006

DATE: July 15, 2015 TIME: 11:00 A.M.

1. RECORDING OF ATTENDEES

A. Recording of attendees, firm represented, address, phone number and email.

2. INTRODUCTIONS & PROJECT DESCRIPTION

- A. Airport Representative
 - Abe Forney Airport Manager
- B. ANG Representative
 - Lt Col Grace Link Base Civil Engineer
- C. Airport Engineering Jviation, Inc.
 - Ryan Lorton Project Manager
- D. MoDOT Aviation
 - Tamara Pitts Project Manager
- E. Project Schedule
 - Schedule I Replacement of Assault Strip Runway 13/31
- F. Work Items

Schedule I – Replacement of Assault Strip Runway 13/31

Mobilization	1 LS
Unclassified Excavation	18,500 CY
9" Fly Ash Treated Subgrade	41,810 SY
Class C Fly Ash	2,600 TON
Culvert Protection	3 EA
Ditch Check	22 EA
6" Cement Treated Permeable Base Course	41,810 SY
Geotextile Fabric	41,810 SY
Bituminous Asphalt Pavement (BP-1)	225 TON
13" Portland Cement Concrete Pavement	41,180 SY

Full Depth Pavement Removal (Concrete on Concrete)	27,480 SY
Full Depth Pavement Removal (Asphalt on Concrete)	14,100 SY
2" Asphalt Butt Joint	620 SY
Bituminous Tack Coat	90 GAL
Type 3 Rock Lining	60 CY
Temporary Airport Runway Pavement Marking (White)	25,940 SF
Temporary Airport Taxiway Pavement Marking (Yellow)	2,260 SF
Temporary Airport Taxiway Pavement Marking (Red)	256 SF
Permanent Airport Runway Pavement Marking (White)	25,940 SF
Permanent Airport Taxiway Pavement Marking (Yellow)	2,260 SF
Permanent Airport Pavement Marking (Red)	256 SF
Permanent Airport Pavement Marking (Black)	7,225 SF
Pavement Marking Removal	1,630 SF
Crack and Joint Sealing	5,000 LF
Pavement Friction Sealcoat Surface Treatment	4,620 SY
18" RCP Storm Pipe – Class V	112 LF
24" RCP Storm Pipe – Class V	218 LF
30" RCP Storm Pipe – Class V	218 LF
18" RCP FES – Class V	8 EA
24" RCP FES – Class V	2 EA
30" RCP FES – Class V	2 EA
Install 6-Inch Perforated Polyethylene Pipe	9,365 LF
Install 6-Inch Non-Perforated Polyethylene Pipe	1,560 LF
Install 6-Inch Underdrain Cleanout	26 EA
Install 6-Inch Underdrain Inspection Pit	22 EA
Install 6-Inch Underdrain Outfall	22 EA
Seeding	25 AC
Mulching	25 AC
Install L-806 Supplemental Windcone	1 EA
#8 AWG, L-824C, 5000 Volt Wire	41,450 LF
#6 AWG, XHHW, 600 Volt Wire	5,720 LF
#6 AWG Bare Copper Counterpoise, Including Ground Rods	13,980 LF
Remove 2" Conduit (DEB)	12,860 LF
Remove Concrete Encased Conduit or Duct Bank	190 LF
2" Sch. 40 PVC Conduit, installed in Trench (DEB)	13,560 LF
2" Sch. 40 PVC Conduit, installed in Trench (CE)	100 LF
2-3" Sch. 40 PVC Conduit, installed in Trench (CE)	
2" Sch. 40 HDPE Conduit, installed by Directional Boring	
1.5" Sch. 40 PVC Light Base Drain	240 LF
Encase Existing DEB Cable in Split Duct and Concrete Encase	50 LF

•	Install L-880 PAPI System	2 EA
•	Remove Elevated R/W or T/W Light, including Light Base	47 EA
•	Remove Night Vision Goggle (NVG) Light	13 EA
•	Remove In-Pavement R/W Edge Light, including Light Base	20 EA
•	Remove Junction Box	22 EA
•	Remove Electrical Manhole	4 EA
•	Remove Airfield Sign, including Concrete Base	3 EA
•	Install L-861T(L) Taxiway Edge Light on L-867B Light Base	32 EA
•	Install L-861(L) Runway Edge Light on L-867B Light Base	46 EA
•	Install L-861(L) Runway Edge Light on L-867D Light Base	1 EA
•	Install L-861E(L) Runway End Light on L-867B Light Base	16 EA
•	Install L-867D Junction Box	2 EA
•	Reinstall Existing 1-mod Airfield Sign on new Concrete Base	1 EA
•	Reinstall Existing 2-mod Airfield Sign on new Concrete Base	1 EA
•	Reinstall Existing 3-mod Airfield Sign on new Concrete Base	1 EA
•	Reinstall New Constant Current Regulator	1 LS
•	Modifications to Lighting Control System	1 LS
•	Install L-853 Retroreflective Marker	59 EA

3. BID OPENING

A. Date: Tuesday, July 28, 2015 at 3:00 P.M. (CST)

B. Location: City of St. Joseph

City Hall

Purchasing, Room 201 1100 Frederick Ave. St. Joseph, MO 64501

C. Bid Bond: 5% of bid amount – Section 2, Instructions to Bidders, Paragraph 4 and Section 20-10 Bid Guaranty.

D. Contract Proposal: Proposal Form starts on page B-1. Submit pages B-1 through B-13 with bid.

E. Award: Notice to Bidders, Section 1, Page 3 and Section 30 Award and Execution of Contract.

4. DBE GOALS

A. 10% of Contract Amount.

5. ESTIMATED CRITICAL CONTRACT DATES

- A. Contract Award: Summer 2015 (ESTIMATED) –The signature of the bidder on the proposal form indicates that within thirty (30) calendar days from acceptance of its bid offer it will execute a contract with the Owner and, if indicated in this solicitation, furnish a project specific Certificate of Insurance naming the Owner as Additional Insured, furnish Performance and Payment Bonds and any other documents required by the Contract Documents.
- B. Notice to Proceed: Refer to Section 80-2. Per Addendum No. 2, the majority of construction is anticipated in the spring of 2016.

Project Time: 120 Calendar Days. Refer to Section 80-08 for more information.

6. BONDING

A. Payment Bond: 100% of Bid Amount, Refer to Section 30-6
B. Performance Bond: 100% of Bid Amount, Refer to Section 30-6

7. BUY AMERICAN REQUIREMENTS

A. See Section 4 – Supplementary Provisions, Part A Federal and State Provisions for Buy American Requirements. Buy American Certification required to be submitted as part of the Bid Proposal Form.

8. INSURANCE REQUIREMENTS

Refer to Section 4, Part C Local Provisions, Paragraph 12 for Contractor's Liability Insurance.

A. The Contractor shall pay for and maintain during the life of this contract adequate Workmen's Compensation, Public Liability and Property Damage Insurance. The Contractor is charged with the responsibility for adequate and proper coverage for all his subcontract operations. Contractor shall furnish to the Sponsor satisfactory proof of carriage of the insurance required.

9. FEDERAL AND STATE WAGE RATES (DAVIS BACON ACT)

A. The higher of the Federal wage and State wage rates are required for this project for work completed under Schedule I. Refer to Section 4, Part D Federal and State Wage Rates.

10. ENGINEER'S FIELD OFFICE

A. See Section 60-05.

11. LIQUIDATED DAMAGES

A. As compensation for non-use, the Contractor shall be assessed a liquidated damage of \$1,500/calendar day(s) for each day that the work remains uncompleted beyond the contract period.

SECTION 80-08 FAILURE TO COMPLETE ON TIME.

SCHEDULE I	LIQUIDATED DAMAGES COST	ALLOWED CONSTRUCTION TIME
Schedule I – Stage 1A	\$1,500/Calendar Day	120 Calendar Days
Schedule I - Stage 1B	\$1,500/Calendar Day	40 Calendar Days
Schedule I – Stage 2	\$1,500/Calendar Day	14 Calendar Days

Work in Stage 1B and Stage 2 shall be performed concurrently with work in Stage 1A. The maximum construction time for the overall project is 120 calendar days.

Please see the Phasing Sheets, G006 through G008, of the Construction Drawings for more information on the scheduling/sequencing of work.

Permitting the Contractor to continue and finish the work or any part of it after the time fixed for its completion, or after the date to which the time for completion may have been extended, will in no way operate as a waiver on the part of the Owner of any of its rights under the contract.

12. PROJECT STAGING

- A. Stage 1A: The work in this stage includes all work that is north of the glideslope critical area. Runway 17/35 open. Glideslope on.
- B. Stage 1B: The work in this stage includes all work that is inside the glideslope critical area north of the Runway 31 threshold. Runway 17/35 open. Glideslope off.
- C. Stage 2: The work in this stage includes all work south of the Runway 31 threshold as well as the airfield lighting home run conduit and wire work as shown on Sheet G008. Runway 17/35 closed between the hours of 10:00 p.m. to 6:00 a.m. for this stage.

13. MISCELLANEOUS

- A. Construction Materials: Sales Tax Exemption. Refer to Section 4, Part C Local Provisions, Paragraph 14 Sales and Use Taxes.
- B. Survey Requirements Refer to Section 50-06, Construction Layout and Stakes.
- C. Contractor Access: Around the north end airport perimeter road as shown on the Construction Safety Drawings.
- D. Acceptance Testing: Responsibility of Engineer.
- E. Waste Area- Contractor shall dispose of all waste materials offsite. See Note 12 on Sheet G004.
- F. Haul Route- Sheet G004, Note 9. The Contractor shall be responsible for any damage to existing facilities or roads. Repairs shall be made at no additional cost to the Sponsor.
- G. Questions will be taken via written format only to Jviation, Inc. until Wednesday, July 22, 2015 at 5:00 p.m. (CST).

14. QUESTIONS

15. PROJECT SITE TOUR



931 Wildwood Drive, Suite 101 Jefferson City, MO 65109 Phone: 573.636.3200

Fax: 573.636.320]

Pre-Bid Meeting Sign In

Meeting Date / Location:

July 15, 2015 / Rosecrans Memorial Airport

Project Name:

Replacement of Assault Strip Runway 13/31

Time:

11:00 a.m.

MoDOT Project #:

13-012A-2

ANG Project #:

ULYB132006

Name	Company	Telephone No.	E-mail
BRYAN LORTON BRYAN WATTENBARGE	EMERY SAPITION INC.	573-418-1450 Ello 221 3500	BYAN, WASTENBARGER CENERYS AFR. COM
Mark Haines	Koss Construction Co.	785 228 2928	mah @ Kossconstruction.com
Tim Bennett	Chester Bross	573-201-5958 816-364-3976	timbernatt a chross group, com
Dune Herring	Printela Electric	816-279-1800	forme o pinule electric inc. com
Rick Mattson	Midland Surveying	816 - 233 - 7900	mattson @ midland survey com
Brandon Reed	KAT Excavation	816-918-5948	BREED & KATEXCAUATION. COM
matt Oswald	Lehman Construction	573-796-8101	quotes @ Lehman Constactionle
Pat Schroede	Seal-G-Matic Paus longon	216 741- 2646	pachroed @ som propag. 10 m
Tony Bahr	ANG	\$16-236.3040	Theo. A. Bahr. ett @ mail. mil
MARY Mentacmery	City of St. Joseph	816-271-5400	MMontgomery, Ci, ST-Joseph M. US
Tamma Benbrick	City of St. Joseph	816-271-5330	thembrick @cli.st-joseph.mo.us
Jamara Pitts	Modot	573-526-5571	tamara. (, Hs @ gradot. no gov