



# WEIS DESIGN GROUP

## FACSIMILE TRANSMITTAL SHEET

Date June 25, 2015 From Paul Spotanski  
To All Plan Holders Project # 0501-11-1  
Affiliation City Of Rock Hill Total Pages 5  
Fax # \_\_\_\_\_  
Regarding Addendum #1 Bismark Avenue Improvements  
☐ Urgent ☐ Review & Comment ☐ As Requested ☐ For Your File ☒ For Your Use

Cc:

### Comments

Addendum #1.

---

**CONFIDENTIALITY NOTE:** The pages of this facsimile transmission contain information from P.H. Weis & Associates, Inc. which is confidential and/or privileged. The information is intended to be for the use of the individual or entity named on this cover sheet. If you are not the intended recipient, be aware that any disclosure, copying, distribution or use of the contents of this information is prohibited. If you have received this facsimile in error, please notify this office by telephone immediately so that we can arrange for the retrieval of the original documents at no cost to you.

---

16296 Westwoods Business Park Drive • Ellisville • Missouri • 63021-4504  
636-207-0832 Missouri • 618-874-0320 Illinois • 636-207-0328 Fax  
E-mail • [phwa@phweis.com](mailto:phwa@phweis.com) Website: [www.phweis.com](http://www.phweis.com)



# Weis Design Group

16296 Westwoods Business Park Drive  
Ellsville, MO 63021  
phwa@phweis.com  
(636) 207-0832  
f. (636) 207-0328

## ADDENDUM #1

RE: City of Rock Hill  
Bismark Avenue Improvements  
STP No. 5577(631)  
WDG No. 0501-11-1

Pages 1 of 1

Date: June 25, 2015

To: All Contract Bidders of Record

**Acknowledge receipt of this Addendum by inserting its number in the Bid Proposal Form.** Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents and is attached. It modifies them as follows:

### **MODIFY SHEETS, SPECIFICATION, BID PROPOSAL OF ADDENDUM #1 AS FOLLOWS:**

#### **CLARIFICATION:**

- Attachment "A"
  1. No. 19 changes to Type "BP-1" 3" Asphalt Concrete Surface Course.
  2. No. 20 Changes to 7 1/2" Plant Mix Bituminous Base Course (MoDOT).
  3. No. 22 Changes to 8" of 3" Minus Aggregate (Compacted).
  4. Item No. 58 change to - Electrical 1" Conduit (Includes Trenching).

#### **BID PROPOSAL:**

- Remove Attachment "A" of the Bid Proposal Insert revised Attachment "A" Pages 1,2,3

# CITY OF ROCK HILL, MO.

## Bismark Avenue

No.	Item Description (Roadway)	Quantity	Unit	Unit Price	Extended Price
1	MOBILIZATION	1	LS		\$
2	TRAFFIC CONTROL BARRICADES	3	EA		\$
3	TRAFFIC CHANNELIZER (TRIM-LINE)	40	EA		\$
4	TEMPORARY TRAFFIC CONTROL SIGNS	277.5	SF		\$
5	REMOVE APRONS AND REPLACE WITH CONCRETE	642	SY		\$
6	REMOVE AND REPLACE CONCRETE DRIVEWAYS	288	SY		\$
7	REMOVE AND REPLACE ASPHALT DRIVEWAYS	304	SY		\$
8	REMOVE AND REPLACE GRAVEL DRIVEWAYS	44	SY		\$
9	SAWCUT EXISTING PAVEMENT (FULL DEPTH)	254	LF		\$
10	ASPHALT PAVEMENT REMOVAL (ROADWAY & INCLUDES SUBGRADE)	5,794	SY		\$
11	CURB REMOVAL	1,539	LF		\$
12	CONCRETE SIDEWALK REMOVAL	572	SY		\$
13	REMOVE AND REPLACE 4' HIGH WOOD FENCE	104	LF		\$
14	REMOVE WALL	72	LF		\$
15	EXCAVATION & GRADING	6,022	CY		\$
16	SILT SOCKS	34	LF		\$
17	SILT FENCE	150	LF		\$
18	SURVEYING/LAYOUT, CONSTRUCTION STAKING AND MONUMENT REPLACEMENT	1	LS		\$
19	TYPE "BP-1" 3" ASPHALT CONCRETE SURFACE COURSE	996	TN		\$
20	7 1/2" PLANT MIX BITUMINOUS BASE COURSE (MODOT)	2,488	TN		\$
21	4" OF 1" MINUS AGGREGATE (COMPACTED)	1,274	TN		\$
22	8" OF 3" MINUS AGGREGATE (COMPACTED)	2,550	TN		\$
23	ROLLED CONCRETE CURB AND GUTTER (1' - 6" WIDE)	4,156	LF		\$
24	P.C.C. SIDEWALK (4" THICK)	968	SY		\$
25	NEW CURB RAMPS	80	SY		\$
26	NEW TRUCATED DOMES	192	SF		\$
27	NEW MODULAR BLOCK WALL	257	SF		\$
28	ROAD SIDE BIO-SWALE - 2.5' THICK BIORETENTION SOIL MEDIA	138	CY		\$
29	ROAD SIDE BIO-SWALE - 6" THICK SAND (ASTM C-33 FINE AGGREGATE)	45	TN		\$
30	ROAD SIDE BIO-SWALE - 6" THICK 3/8" DIA. GRAVEL (ASTM C-33 NO. 8)	45	TN		\$

# Bismark Avenue

No.	Item Description (Roadway)	Quantity	Unit	Unit Price	Extended Price
31	ROAD SIDE BIO-SWALE - 6" THICK 3/4" DIA. GRAVEL (ASTM C-33 NO. 6 OR 67)	45	TN		\$
32	ROAD SIDE BIO-SWALE - MSD TYPE 1 GEOTEXTILE FABRIC	237	SY		\$
33	ROAD SIDE BIO-SWALE - 6" DIA. SCHEDULE 40 PVC DRAIN PIPE	98	LF		\$
34	ROAD SIDE BIO-SWALE - 6" DIA. SCHEDULE 40 PVC PERFORATED PIPE	253	LF		\$
35	ROAD SIDE BIO-SWALE - 6" DIA. SCHEDULE 40 PVC RISER DRAIN PIPE	16	LF		\$
36	ROAD SIDE BIO-SWALE - 6" ATRIUM GRATE	4	EA		\$
37	ROAD SIDE BIO-SWALE - BIO-SWALE SIGN	4	EA		\$
				SUB-TOTAL	\$
No.	Item Description (Landscaping)	Quantity	Unit	Unit Price	Extended Price
38	TREE REMOVAL (2" TO 6" DIAMETER)	4	EA		\$
39	TREE REMOVAL (8" TO 12" DIAMETER)	6	EA		\$
40	TREE REMOVAL (14" TO 25" DIAMETER)	7	EA		\$
41	BRUSH/SHRUB REMOVAL (CLEARING AND GRUBBING)	1,154	SF		\$
42	SODDING	2,752	SY		\$
				SUB-TOTAL	\$
No.	Item Description (Utilities)	Quantity	Unit	Unit Price	Extended Price
43	ADJUST VALVE BOXES, METER BOXES, STOP BOXES, SANITARY CLEANOUTS, ETC.	25	EA		\$
44	ADJUST MANHOLE TOPS TO GRADE	13	EA		\$
45	ADJUST SINGLE CURB INLETS TO GRADE	3	EA		\$
46	ADJUST AREA INLETS TO GRADE	1	EA		\$
47	REMOVE AND REPLACE YARD DRAINS	3	EA		\$
48	WATER SERVICE LINE ADJUSTMENT	5	EA		\$
49	NEW WATER SERVICE LINE RECONNECTION AT MAIN	5	EA		\$
50	ADJUSTING SANITARY SEWER LATERAL	5	EA		\$
51	NEW SANITARY SEWER LATERAL RECONNECTION AT SEWER	5	EA		\$

# CITY OF ROCK HILL, MO.

## Bismark Avenue

No.	Item Description (Roadway)	Quantity	Unit	Unit Price	Extended Price
				<b>SUB-TOTAL</b>	<b>\$</b>
<b>No.</b>	<b>Item Description (Safety)</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Extended Price</b>
52	REMOVE AND REPLACE STREET SIGNS	21	EA		\$
53	THERMOPLASTIC YELLOW DOUBLE SOLID 4" WIDE CENTERLINE STRIPING	4,265	LF		\$
54	THERMOPLASTIC WHITE 12" WIDE CROSSWALK STRIPING	563	LF		\$
55	THERMOPLASTIC WHITE 24" WIDE STOP BAR STRIPING	7	EA		\$
56	NEW STREET LIGHTS (INCLUDES FOUNDATION, FIXTURE AND BULB)	11	EA		\$
57	STREET LIGHTING CONTROL PANEL WITH METER	1	EA		\$
58	ELECTRICAL 1" CONDUIT (INCLUDES TRENCHING)	2,332	LF		\$
59	ELECTRICAL WIRE SET (INCLUDES 2 - #8 & #10 GROUND)	2,332	LF		\$

<b>SUB-TOTAL</b>	<b>\$</b>
------------------	-----------

<b>TOTAL PROJECT COST</b>	<b>\$</b>
---------------------------	-----------