



City of
MARYLAND HEIGHTS

11911 Dorsett Road
Maryland Heights, MO 63043
t: 314.291.6550
f: 314.291.7457
www.marylandheights.com

DATE **April 24, 2015**

ADDENDUM NO. 1

Notice to All Persons and Firms proposing to Submit a Bid or Furnish Materials for City of Maryland Heights **Progress Parkway Bid No. 2015-06 (Federal Project No. STP-5401(670))**.

The City of Maryland Heights is making the following and/or clarification to the specifications for this project.

- 1. The following changes have been made to the City-Contractor Agreement Article IV titled The Contract Sum and Payment is being replaced in its entirety with the following:**

ARTICLE IV

The Contract Sum and Payments

The City shall pay the Contractor for the performance of the Contract a sum, not-to-exceed \$_____ for the performance of the contract, subject to additions and deductions provided herein, based on actual quantities of work completed under each bid item at the unit prices made in the itemized bid form which is as an exhibit to the contract as follows:

(1) Retainage may be initiated during contract performance if the engineer determines that certain events have occurred including:

a. The occurrence of a cause for withholding payment specified in the Missouri prompt Pay Act, 34.057 RSMo. Retainage withheld under these circumstances will be as allowed under statute.

(2) If retainage is initiated during contract performance, the amount which is allowed under 34.057 RSMo will be deducted from the total amount of remaining work items of each estimate. The retainage will be released as follows:

As soon as practical after final acceptance of the work, and after final quantities have been computed or computations have reached a point where final quantities can be closely estimated, the retained percentage will be paid to the contractor. A portion of any retained percentage may be released after the project is open to all through traffic, or the work has been essentially completed. Prior to release of any retained percentage the contractor shall file with the City:

- a. An affidavit, on a form acceptable to the City, to the effect that payments have been made and all claims have been released for all material, labor and other items covered by the contract bond.
- b. The written consent of the surety to such payment.

c. Any other documents which may be required by the contract.

2. Can polypropylene pipe be considered as an equal alternative to the specified reinforced concrete pipe?

Polypropylene pipe, as approved by The Metropolitan St. Louis Sewer District, can be considered as an alternative to the specified reinforced concrete pipe.

3. What type of locator is the City expecting for the 4" future conduit for the signals?

The contract shall provide a trace wire over the 4" conduit and mark the curb with an arrow cut in the curb over the top of the conduit. The tracer wire shall be brought to the surface to a ground flush fixture approved by the City to allow for connection to the tracer wire. The cost for the tracer wire is considered incidental for the 4" conduit.

4. What are you expecting for the Temporary Detection Bid Item?

The city will expect the contractor to follow the St. Louis County Department of Highways & Traffic specifications Section 904.5.24.4 Maintenance of Vehicle Detection Systems during Construction

5. Can a Vyking Wall System be considered for the permanent modular block retaining wall for this project?

The Vyking Wall system may be used for the permanent modular retaining wall for this project. The Vyking Wall system has been approved by the Missouri Department of Transportation and St. Louis County Public Works Department

6. Modular Block Retaining Wall Color.

The modular block retaining wall in the detention basin (parcel 6) shall be Timberwood Charcoal or a substantially similar color instead of gray color as specified in the JSP Section 1.2 Modular Block Retaining Wall. All other modular block retaining walls shall be gray in color as specified.

CITY OF MARYLAND HEIGHTS



L.G. Loos, P.E.
Engineering Manager