

April 20, 2015

To: Plan Holders for Improvements to the Mountain View Airport Mountain View, Missouri MoDOT Project No. 14-104B-1

Transmitted herewith is Addendum **No. 1** to the Contract Documents, Plans and Specifications dated March 27, 2015 for Improvements to the Mountain View Airport, Mountain View, Missouri, MoDOT Project No. 14-104B-1.

## **SCHEDULE I:**

Runway 10/28 Crack Repair and Seal Coat

Sincerely,

Jviation, Inc.

Ryan B. Lorton, P.E.





## ADDENDUM NO. 1 TO CONTRACT DOCUMENTS, PLANS AND SPECIFICATIONS FOR IMPROVEMENTS TO THE MOUNTAIN VIEW AIRPORT MOUNTAIN VIEW, MISSOURI MODOT PROJECT NO. 14-104B-1

To All Bidders: You are requested to make all changes and/or additions contained in this addendum to the Bidding Documents. Failure to acknowledge this Addendum in Proposal shall result in rejection of bid. Bidders are informed that the above referenced Contract Documents, Plans and Specifications are modified as follows as of April 20, 2015:

## 1. QUESTIONS

Question: Will the existing crack sealing material need to be removed?

Response: At the direction of the resident engineer, the existing crack sealing

material that is brittle and non-adhering shall be removed prior to placing new crack sealing material. Existing crack sealing material that is in good condition may be heat lanced and sealed instead of routing. This shall be

incidental to Item MO-622a Crack and Joint Sealing.

\*\* END OF ADDENDUM NO. 1\*\*