



### **ADDENDUM NUMBER 3**

Project Number 89005536

Project Title Rehabilitation of Bridge S096B11048, Roadway Widening and Intersection Improvements at Blue Parkway and Eastwood Trafficway - Fed Nos BRM-3301 (470) and STP-3301 (457) - Bid No. 2

County Jackson

ISSUE DATE: **April 7, 2015**

Bidders are hereby notified that the Bidding and Contract Documents for the above project, for which Bids are to be received on **Tuesday, April 14, 2015**, are amended as follows:

Information to Bidders The following is provided to Bidders for information only:

1. Attached is copy of attendance, notes and agenda.

**NOTE: Bidders must acknowledge receipt of this Addendum by listing the number and date, where provided, on the Bid Form - Document 00410.**

Rehabilitation of Bridge S096B11 048, Roadway Widening and Intersection Improvements  
At Blue Parkway and Eastwood Trafficway  
City Project No. 89005536  
Pre Bid Meeting  
April 3, 2015  
Sign In Sheet

No.	Name	Representing	Email
1	Dick Montgomery	T#B	rmontgomery@tb-engr.com
2	Daniel Gibson	L.G. Borcus and Sons, Inc.	daniel.gibson@borcus.com
3	Brad Boyles	Mega Industries Corp.	megabids@megaKC.com
4	Angi DeGraeve	LEKECO	angi@lexeco.com
5	Kim Wilson	JM Foley Const Co	Kim.Wilson@JMFoley.com
6	EO ANDRE	RADMAKER Bros.	EANDRE@RADMAEX.COM
7	Hank Cunningham	Pyramid Exc.	hank@pyramidexcavation.com
8	BRAD BEUDEN	Little Joe's Asphalt	brad@littlejoesasphalt.com
9	Damon L Hodges	City of KCMO	damonhodges@kcmo.org
10	Chad Thompson	" "	Chad.Thompson@KCMO.org
11			
12			
13			
14			
15			
16			

**City Project No. 89005536**  
**Rehabilitation of Bridge S096B11 048, Roadway Widening and Intersection**  
**Improvements at Blue Parkway and Eastwood Trafficway**  
**Federal Project Nos. BRM-3301(470) and STP-3301(457)**  
**Pre Bid Meeting Agenda**  
**April 3, 2015**

**1. Project Manager:**

Damon Hodges, PE  
18<sup>th</sup> Floor, City Hall  
414 E. 12<sup>th</sup> Street  
Kansas City, MO 64106

**2. Description of Work:**

Improvements to Blue Parkway from Fairway Avenue to Bennington Avenue to rehabilitate Bridge S096B11 048, add an additional left turn lane on Blue Parkway, a right turn lane on Eastwood Trafficway, replace the existing span wire signal, and related grading paving, drainage, landscape and roadway lighting improvements. Work will also include water main replacement and sanitary sewer relocation.

**3. Administrative Items:**

- Bid Opening – 2:00 pm, April 14, 2015 City Hall, Room 102 W.
- DBE Goal 10% ~~500~~
- Contract time ~~400~~ Calendar Days
- See Notice to Contractors for further bidding requirements

**4. Construction Schedule-** Due to the heavy volume of traffic on Blue Parkway, lane closures will not be permitted between December 1 and March 1. Work shall be scheduled such that all lanes of all roadways are opened to traffic by November 30, 2016. Access to all businesses and residences shall be maintained at all times during construction.

**5.** Work on water transmission mains shall be scheduled such that they are not taken out of service during peak demand periods (between May 15<sup>th</sup> and September 15<sup>th</sup>) in accordance with Water Department requirements.

**6.** Rehabilitation of Bridge S096B11 048 will consist of construction of stem walls within the existing structure, extending the structure upstream and downstream of Blue Parkway to accommodate the widened roadway section, installing a new corrugated aluminum box culvert shell and constructing new upstream and downstream headwalls. Upon completion, the deck of the existing structure is to be demolished and a reinforced concrete pavement slab constructed.

**7.** Other drainage improvements include extending the existing 60" RCP under Eastwood Trafficway, extending the existing 8'x8' and 6'x4' RCB structures under Blue Parkway to accommodate the widened roadway section and storm water inlets and manholes associated with the new curb and gutter.

**8. Utility Status:**

- KCPL has completed pole relocations. Several poles with street lights remain in place and will be removed when lights are taken out of service.
- MGE is working on relocations and is anticipated to complete work in December.
- Google relocation work is complete but work on vault at the northeast corner of Fairway will need to be completed once Contractor has cut area down to finish grade.
- TWC relocations are complete.
- AT&T has a small amount of work to complete, but anticipates being done by mid December.





# Public Works Department

Capital Projects Division  
18<sup>th</sup> Floor, City Hall  
414 East 12<sup>th</sup> Street  
Kansas City, Missouri 64106

Office: (816) 513-2720  
Fax: (816) 513-2523

Project: Rehabilitation of Bridge SO96B11 048, Roadway Widening and Intersection Improvements at Blue Parkway and Eastwood Trafficway

City Project Number: 89005536

Federal Project Numbers: BRM-3301(470) and STP-3301(457)

Subject: Pre-Bid Meeting Notes Dated April 3,2015

1. The amount of calendar days - 500 calendar days to completion. No substantial.
2. Is there asphalt indexing? There is not asphalt indexing for this project
3. What is the bid item for the rip-rap for the RCB? Does the quantity Cover the amount required? Bid item #47 and rechecked the rip rap quantity this morning and Item 47, "Rock Blanket w/ Filter Fabric" covers this work. The quantity of 1,320 s.y.
4. In regards to the earthwork for this site. Is the all the unclassified excavation being wasted off-site and material imported for the fills (contractor furnished 7,752 CY = compacted embankment 7,752 CY)? Based on the geotech report and the limited depth of fill that is being placed, we believe that most of the excavated material will not be suitable for reuse and have therefore included a quantity for imported material. In the event that suitable material is encountered during excavation it will be used and the imported quantity reduce accordingly. The amount shown is raw number.
5. When is the potential bid date? Estimated 8-10 weeks after bid Opening( Pending bid amounts and funding procedures)