

## **ADDENDUM # 2**

TO THE DRAWINGS AND SPECIFICATIONS FOR:  
**Bryan Road Slab Replacement and Sidewalk  
STP-7302(624)**

City of O'Fallon, Missouri  
100 North Main Street  
O'Fallon, Missouri 63366

City of O'Fallon, Missouri  
100 North Main Street  
O'Fallon, MO 63366  
636-379-5491  
636-978-4144 Fax  
E-mail: jschuepfer@ofallon.mo.us

January 8, 2014

---

This Addendum forms a part of the Bidding and Contract Documents and modifies the original Bidding Documents.  
**FAILURE TO ACKNOWLEDGE RECEIPT OF ADDENDUM MAY SUBJECT BIDDER TO DISQUALIFICATION.** Any modification of the work or additional work that the bidder may be required to perform by reasons of this addendum shall be included. All work under this addendum shall be governed by the main specification for such work.

Regarding JSP#4 (24 Hour cure time and lane closure), because the second bid has a relaxed base bid high early cure time (24 hour, not 4 hour), it is understood that the lanes will not be opened in the same day, and some of the wording in this JSP does not apply. The intent for starting the lane closure to minimize traffic disruptions, based on the time of day, still applies (for example, north bound traffic is heavy in the morning and lanes shall remain open until 9:00am). It will not be required to have the southbound lanes opened by 3:00pm on the same day, however after cure is met, it will be required to have the lanes opened prior to 3:00pm on the next day (assuming 24 hour cure). Regarding the night work schedule, the lanes would no longer need to be opened by 6:00am the next morning.

See the below clarifications to the current JSP's. The wording below shall completely replace the wording on the same two paragraphs as currently found in the bid documents.

### **2. ANTICIPATED NOTICE TO PROCEED**

The anticipated notice to proceed for the project is on or around March 2, 2015. The City estimates contract approval, which will require City Council approval, on or about February 12, 2015. The City reserves the right to adjust this date as needed.

### **13. High Early (24 hour) Concrete Mix**

All mainline paving (slab repairs) shall utilize the 24 hour high early mix designs. Concrete cylinders shall be made for the concrete pour. Cylinders shall be broken at 24 hours from casting. Cylinder breaks shall achieve 3,500 psi in 24 hours.

Cylinders that do not achieve 3,500 psi in 24 hours will receive liquidated damages in the amount of \$10.00 per square yard of the quantity the cylinder(s) represents.

**END OF ADDENDUM**