



# Weis Design Group

16296 Westwoods Business Park Drive  
Ellsville, MO 63021  
phwa@phweis.com  
(636) 207-0832  
f. (636) 207-0328

## ADDENDUM #1

RE: City of Richmond Heights  
Wise Avenue Reconstruction  
STP No. 5412(602)  
WDG No. 9908-06-2

Pages 1 of 1

Date: November 21, 2014

To: All Contract Bidders of Record

**Acknowledge receipt of this Addendum by inserting its number in the Bid Proposal Form.** Failure to do so may subject bidder to disqualification. This Addendum forms a part of the Contract Documents and is attached. It modifies them as follows:

### **MODIFY SHEETS, SPECIFICATION, BID PROPOSAL OF ADDENDUM #1 AS FOLLOWS:**

#### **GENERAL CLARIFACATION:**

- The 6 parking meters on the east end of the project between Station 21+00 and Station 21+60 shall be retained and reused.

#### **BID PROPOSAL:**

- Remove Attachment "A" of the Bid Proposal Insert revised Attachment "A"

#### **REVISED PLAN SHEETS:**

- Sheet 3.2 of plan sheets (Summary Sheet)  
Remove item 46 completely (Remove and Replace Light Standard), the existing lights standard owned by Ameren U.E.
- Sheet 3.3 of the plans sheets (Traffic Control Quantity Summary):  
Remove Item number 616-11.00 and Quantity of 2, Replace with 616-10.98 Quantity of 2 (Changeable Message Board Sign, Contractor Furnished/ Retained)

**CITY OF RICHMOND HEIGHTS, MO.**  
**Wise Avenue Reconstruction**

ROADWAY ITEMS					
No.	Item Description	Quantity	Unit	Unit Price	Extended Price
1	MOBILIZATION	1	LS	\$	\$
2	SURVEYING/LAYOUT, CONSTRUCTION STAKING AND MONUMENT REPLACEMENT	1	LS	\$	\$
3	REMOVE WALL	43	LF	\$	\$
4	REMOVE AND REPLACE 4' HIGH WOOD FENCE	15	LF	\$	\$
5	REMOVE AND REPLACE PARKING METERS	6	EA	\$	\$
6	REMOVE AND REPLACE CONCRETE DRIVEWAYS AND APRONS	1,549	SY	\$	\$
7	REMOVE ASPHALT APRONS AND REPLACE WITH CONCRETE	279	SY	\$	\$
8	REMOVE AND REPLACE ASPHALT DRIVEWAYS	321	SY	\$	\$
9	ASPHALT PAVEMENT REMOVAL (ROADWAY & INCLUDES 3" OF SUBGRADE)	4,539	SY	\$	\$
10	CONCRETE PAVEMENT REMOVAL (ROADWAY & INCLUDES 3" OF SUBGRADE)	7,364	SY	\$	\$
11	CURB REMOVAL	6,064	LF	\$	\$
12	CONCRETE SIDEWALK REMOVAL	3,000	SY	\$	\$
13	ASPHALT SIDEWALK REMOVAL	17	SY	\$	\$
14	SAWCUT EXISTING PAVEMENT (FULL DEPTH)	238	LF	\$	\$
15	BUTT JOINTS	158	LF	\$	\$
16	EXCAVATION & GRADING	180	CY	\$	\$
17	EROSION CONTROL	1	LS	\$	\$
18	CHANGEABLE MESSAGE SIGN (CONTRACTOR FURNISHED / RETAINED)	2	EA	\$	\$
19	TRAFFIC CONTROL BARRICADES	9	EA	\$	\$
20	TRAFFIC CHANNELIZER (TRIM-LINE)	92	EA	\$	\$
21	TEMPORARY TRAFFIC CONTROL SIGNS	523	SF	\$	\$
22	7" P.C. CONCRETE (NON-REINFORCED)	12,658	SY	\$	\$
23	3" OF 1" MINUS AGGREGATE (COMPACTED)	2,024	TN	\$	\$
24	3" ROLLED CURBING	6,064	LF	\$	\$
25	P.C.C. SIDEWALK (4" THICK)	3,251	SY	\$	\$
26	NEW CURB RAMPS	123	SY	\$	\$
27	NEW TRUCATED DOMES	294	SF	\$	\$
28	REMOVE AND REPLACE FRONT PORCH AND WALKWAY (#7461 WISE AVENUE)	15	SY	\$	\$
29	NEW MODULAR BLOCK WALL	194	SF	\$	\$
				<b>SUB-TOTAL</b>	\$

**CITY OF RICHMOND HEIGHTS, MO.**  
**Wise Avenue Reconstruction**

ROADWAY ITEMS					
LANDSCAPING ITEMS					
30	TREE REMOVAL (1" TO 8" DIAMETER)	1	EA	\$	\$
31	BRUSH/SHRUB REMOVAL (CLEARING AND GRUBBING)	154	SF	\$	\$
32	SODDING	4,106	SY	\$	\$
<b>SUB-TOTAL</b>					<b>\$</b>
UTILITIES ITEMS					
33	ADJUST MANHOLE TOPS (ATG)	13	EA	\$	\$
34	REMOVE AND REPLACE YARD DRAINS	4	EA	\$	\$
35	ADJUST VALVE BOXES, METER BOXES, STOP BOXES, SANITARY CLEANOUTS, ETC.	95	EA	\$	\$
36	WATER SERVICE LINE ADJUSTMENT	45	EA	\$	\$
37	WATER SERVICE LINE MAIN RECONNECTION	45	EA	\$	\$
38	ADJUSTING SANITARY SEWER LATERAL	45	EA	\$	\$
39	SANITARY LATERAL RECONNECTION	45	EA	\$	\$
<b>SUB-TOTAL</b>					<b>\$</b>
SAFETY ITEMS					
40	ACRYLIC WATERBORNE PVMT. MARKING PAINT, 4" DOUBLE YELLOW CENTERLINE STRIPING	5,740	LF	\$	\$
41	ACRYLIC WATERBORNE PVMT. MARKING PAINT, 4" WHITE LANE/PARKING SPACE STRIPING	192	LF	\$	\$
42	ACRYLIC WATERBORNE PVMT. MARKING PAINT, 12" YELLOW CURB STRIPING	1,061	LF	\$	\$
43	ACRYLIC WATERBORNE PVMT. MARKING PAINT, 12" WHITE CROSSWALK STRIPING	1,158	LF	\$	\$
44	ACRYLIC WATERBORNE PVMT. MARKING PAINT, 24" WHITE STOP BAR STRIPPING	15	EA	\$	\$
45	ACRYLIC COPOLYMER FAST DRY PVMT. MARKING PAINT, LEFT/RIGHT ARROW	3	EA	\$	\$
46	ACRYLIC COPOLYMER FAST DRY PVMT. MARKING PAINT, COMB. STR-LEFT/RIGHT ARROW	3	EA	\$	\$
<b>SUB-TOTAL</b>					<b>\$</b>
<b>TOTAL PROJECT COST</b>					<b>\$</b>