

Charlie A. Dooley
County Executive

Saint Louis
COUNTY
HIGHWAYS & TRAFFIC
PUBLIC WORKS

Sheryl L. Hodges, D.E., P.E., L.P.G.
Director

October 23, 2014

ADDENDUM NO. 3

Notice to All Persons and Firms Proposing
to Submit a Bid or Furnish Materials for
Mason Road Bridge No. 211
St. Louis County Project No. AR-1133
Federal Project No. STP-5574(604)

The construction bid items identified below have been clarified as follows:

No. 1

Safety Barrier Curb (Bridges, Cast-in-Place) Item No. 703-42.15

Safety Barrier Curb (Bridges, Cast-in-Place) Item No. 703-42.15 – Linear Feet		
Lin. Ft.	Concrete (Cubic Yard) See Note 1	Steel (lb) See Note 2
99	225	1740

Notes:

1. The concrete volume is based on the safety barrier curb area of 2.27 ft²/ft of length.
2. Steel weight taken from existing bar list on Sheet 52 of 57 for Barrier (R, R1, R3, and R4 bars), to the nearest 10 pounds.

Bid price of Safety Barrier Curb includes cost of concrete, reinforcement, and curing compound including field cuts, complete in place.

No. 2

Slab on Prestressed Concrete Deck Beams Item No. 703-42.30

Slab on Prestressed Concrete Deck Beams Item No. 703-42.30 – Square Yard		
Square Yard	Concrete (Cubic Yard) See Note 1	Steel (lb) See Note 2
230	58.0	9020

Notes:

1. The concrete quantity shown above includes the deck thickness of 8" plus an assumed 1 ½" thick average haunch thickness atop the 4'-0" wide beams over a beam length of 48'-3".
2. The steel weight shown includes deck bars D100-D105 shown on the bar list on Sheet 52/57, to the nearest 10 pounds.

The amount of completed and accepted work for the reinforcing concrete slab will be paid for at the contract unit price per square yard for "Slab on Prestressed Concrete Deck Beams" which will include full compensation for furnishing and placing all forms, and any surface preparation required, furnishing and placing all concrete and reinforcing steel for the concrete slab, haunches, all labor, equipment, tools, and incidentals necessary to complete the work.

ATTENTION BIDDERS: CHECK THE SECOND STATEMENT ON ADDENDUM ACKNOWLEDGEMENT SHEET NO. 330 OF 345 OF THE BID DOCUMENTS AND COMPLETE APPROPRIATELY.



Daniel R. Naunheim, P.E.
Division Manager, Design

DRN/KJJ/dah

Attachments: Addendum Acknowledgement (**Please sign and return.**)

October 23, 2014

ADDENDUM ACKNOWLEDGEMENT

ADDENDUM NO. 3

FROM: St. Louis County Department of Highways and Traffic

RE: Mason Road Bridge No. 211
St. Louis County Project No. AR-1133
Federal Project No. STP-5574(604)

**PACKAGE INCLUDES THIS ACKNOWLEDGEMENT AND
ADDENDUM NOTICE.**

(21 pages & 22 plan sheets total)

IF YOU DID NOT RECEIVE ALL PAGES, CALL (314) 615-8582.

UPON RECEIPT OF THIS PACKAGE, **PLEASE SIGN AND
DATE** (IN THE INDICATED LOCATIONS BELOW), AND **FAX
THIS ACKNOWLEDGEMENT TO THE DEPARTMENT OF
HIGHWAYS & TRAFFIC AT (314) 615-8194** (Attn: Dan Howell,
DESIGN DIVISION) TO VERIFY RECEIPT

COMPANY _____

RECEIVED BY _____

DATE _____