

ADDENDUM NO. 2

STP-9900(596)
OSAGE BEACH PARKWAY
SIDEWALK IMPROVEMENTS

FOR

CITY OF OSAGE BEACH
CAMDEN COUNTY, MO

June 20, 2014

This addendum shall become a part of the specifications noted above. This Addendum shall be attached to the bid in accordance with Bidder Checklist, Item No. 7 and Notice to Contractors, Paragraph No. 13.

PROJECT MANUAL:

1. **ITEMIZED BID:**

- a. Replace the Itemized Bid form in the project manual with attached Itemized Bid Form.

CLARIFICATION:

1. **BID ITEMS:**

- a. Bid Item No. 7: Concrete Drive (8" Thick, Includes Curbs) shall be changed to Concrete Drive (6" Thick, Includes Curbs). Concrete Drive (6" Thick, Includes Curbs) shall include the following: Concrete Drives shall be placed on Type 5 aggregate 4 inches thick. The sub-grade below the Type 5 aggregate shall be compacted in accordance with MoDOT specifications. The Type 5 aggregate and the compacted sub-grade shall be subsidiary to Bid Item Number 7.
- b. Bid Item No. 25: Force Account - \$15,000 was added to this line item.

END OF ADDENDUM 2

L:\130317-010_Project Management\Addendums\130317-010 Addendum02.doc

ITEMIZED BASE BID: The bidder should complete the following section in accordance with Sec 102.7. The bidder proposes to furnish all labor, materials, equipment, services, etc. required for the performance and completion of the base contract work, as follows:

BASE BID

| ITEM | DESCRIPTION | UNIT | QUANTITY | UNIT PRICE | AMOUNT |
|-----------------------|---|------|----------|--------------|--------------|
| 1 | Mobilization | L.S. | 1 | \$ | \$ |
| 2 | Clearing, Grubbing & Removal | L.S. | 1 | \$ | \$ |
| 3 | Linear Grading | L.F. | 3,500 | \$ | \$ |
| 4 | 2' Conc. Curb & Gutter | L.F. | 123 | \$ | \$ |
| 5 | Concrete Sidewalk (Includes Ramps) | S.F. | 17,420 | \$ | \$ |
| 6 | Detectable Warning | S.F. | 268 | \$ | \$ |
| 7 | Concrete Drive (6" Thick, Includes Curbs) | S.Y. | 1,714 | \$ | \$ |
| 8 | 6" White Line (Crosswalk Marking) | L.F. | 871 | \$ | \$ |
| 9 | Adjust Pushbutton Detectors | EA. | 4 | \$ | \$ |
| 10 | Pedestrian Signal Head | EA. | 2 | \$ | \$ |
| 11 | Pushbutton Detector | EA. | 2 | \$ | \$ |
| 12 | 3-Inch Conduit - Trench | L.F. | 37 | \$ | \$ |
| 13 | 5c Cable Ped Head | L.F. | 218 | \$ | \$ |
| 14 | 2c Cable Push Button | L.F. | 206 | \$ | \$ |
| 15 | R10-3e (Left Arrow) Pedestrian Signal Sign | EA. | 1 | \$ | \$ |
| 16 | R10-3e (Right Arrow) Pedestrian Signal Sign | EA. | 1 | \$ | \$ |
| 17 | 8 FT Signal Post | EA. | 2 | \$ | \$ |
| 18 | Type C Base | EA. | 2 | \$ | \$ |
| 19 | Sidewalk Wall | L.F. | 352 | \$ | \$ |
| 20 | Seeding, Fertilizing and Mulching | ACRE | 1.00 | \$ | \$ |
| 21 | Temporary Traffic Control | S.F. | 82 | \$ | \$ |
| 22 | Silt Fence | L.F. | 3,751 | \$ | \$ |
| 23 | Straw Wattle | L.F. | 3,312 | \$ | \$ |
| 24 | Construction Staking | L.S. | 1 | \$ | \$ |
| 25 | Force Account | L.S. | 1 | \$ 15,000.00 | \$ 15,000.00 |
| TOTAL BASE BID | | | | | \$ |

COMPANY

BIDDER'S SIGNATURE

DATE