



ADDENDUM NUMBER 2

Project Number SBMO 11001

Project Title Cliff Drive Recreational Improvements

ISSUE DATE: June 6, 2014

Bidders are hereby notified that the Bidding and Contract Documents for the above project, for which Bids are to be received on June 11, 2014, are amended as follows:

Information to Bidders: The following is provided to Bidders for information only:

Q1.	What is the depth of the roadway at site one?
A1.	A core of the roadway was not taken so that information is not available. The portland cement concrete crosswalk detail on sheet C-202 requires a minimum removal of 16" depth.
Q2.	At site 2 will there be any ADA striping required in the parking area?
A2.	Yes. Reference detail on sheet C-102 for striping requirements.
Q3.	Is the linear foot quantity for the 6' wide concrete steps measured as each step being 6' long x 10 steps for a total of 60 linear feet?
A3.	The quantity is measured as the linear feet of each stair run. If the drawings show a dimension of a set of stairs as 6' wide and 10' long, then 10' is counted toward the linear foot total.
Q4.	If rock is encountered during excavation, is the rock removal paid separately?
A4.	No. All costs related to excavation necessary to meet grades for all new construction will be considered a subsidiary cost of that line item. If rock is encountered during excavation for steps, then the rock excavation cost is considered a subsidiary cost to the 6' wide concrete step construction line item. Reference Geotech report provided in bid documents.
Q5.	If rock is encountered for step installations, will the concrete foundation key be required to extend into the rock and how deep into the rock will that requirement be?
A5.	The concrete foundation key and anchoring into rock will be reviewed by the engineer and will require approval of the engineer. Reference details 1 and 2 of sheet S-100.
Q6.	Does the stone wall repointing quantities include both sides of the wall at sites 7,8 & 9?
A6.	No. Repointing will only be on the street side of the wall at site 9. The repointing quantity of 225 linear feet refers to the length of wall face. Repointing of the entire face of the wall from top of wall to top of footing for 225 linear feet will be required

