

ADDENDUM NO. 1

ISSUED BY: BENTON & ASSOCIATES, INC.
2414 SOUTH FRANKLIN STREET
KIRKSVILLE, MO 63501

DATE: April 10, 2014

FOR: Carroll County Bridge 19300051
B&A NO. 13e2537

The attached revisions hereby supersede any and all data with which they may conflict as indicated on the Drawings, Specifications and related documents issued in the original set. Each trade is responsible for changes in its work caused by changes in the work of other trades. This addendum is a part of and shall be attached to the original set of plans and specifications for the work.

THIS ADDENDUM SHALL BECOME A PART OF THE SPECIFICATIONS NOTED ABOVE. RECEIPT OF THIS ADDENDUM SHOULD BE ACKNOWLEDGED ON THE BID FORM.

FOR PURPOSES OF CLARIFICATION FOR TURF REINFORCEMENT MAT & AGGREGATE BASE (GRANULAR FILL) :

(Please see Page 2 of this Addendum for Turf Reinforcement Mat)

All Aggregate Base (Granular Fill) located beneath the proposed structure, as shown on plan sheets 4 & 9, shall be a minimum thickness of 6 inches.

There is NO change in the bid date or time with this addendum.

Turf Reinforcement Mat

General – Turf reinforcement mats shall be installed in accordance with the manufacturers published recommendations at the locations shown on the plans.

Material Requirements – All material provided shall be recommended for the following applications in published application guides from the manufacturers:

- 1h : 1v slopes
- Extended Term Application with longevity of greater than 5 years.
- High Performance
- Permanent
- All fasteners shall be suitable for the soil types encountered at the project site.

Installation Requirements – All materials and fasteners shall be installed in strict accordance with the recommendations of the manufacturer directions for high water velocity and loose soil conditions. All lime, fertilizer, and seed shall be in accordance with MoDOT specifications and JSP for seeding and mulching of disturbed areas and applied to a prepared seedbed before the turf reinforcement mats are installed.

Measurement – No direct measurement will be made.

Payment – Payment will be made for plan quantity at the contract unit price. Payment includes seeding, fertilizer and lime as well.