## ADDENDUM NO. 1

## Timberlake Manor Bridge

2011-PW-12 STP-5410(616)

April 10, 2014

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents issued for construction on March 13, 2014, as set forth below. All bidders shall acknowledge receipt of this addendum on the Bid Form. Failure to acknowledge receipt of this Addendum may subject Bidder to disqualification.

1. The Contract Documents and Specifications are hereby revised as indicated below:

Section, Location	Change
Itemized proposal, pg 9	Remove line item for "Removal of Temporary Power Pole".
JSP "Y", pg 63	Delete JSP Y:."Removal of Temporary Power Pole"

Attachments:

Itemized Proposal Page 9

## ITEMIZED PROPOSAL

City of Chesterfield

Timberlake Manor Parkway Bridge over Creve Coeur Creek

	Roadway Items							
Pay Item No.	Description	Unit	Quantity	Unit Cost	Amount			
201-30.00	Clearing & Grubbing	Acre	0.25					
202-20.10	Removal of Improvements	Lump Sum	1					
203-50.00	Unclassified Excavation	Cu. Yard	37					
203-55.00	Embankment-in-Place	Cu. Yard	154					
304-05.04 Type 5 Aggregate for Base (4 in. thick)		Sq. Yard	495					
308-60.05	Concrete Sidewalk, 5 in.	Sq. Yard	110					
502-11.07	Concrete Pavement (7 in non reinforced)	Sq. Yard	495					
606-30.17	Type C Crashworthy End Terminal	Each	1					
609-20.11	Integral Curb (6 in height and under) Type A	Linear Foot	264					
611-30.20	Furnishing Type 2 Rock Blanket	Cu. Yard	822					
611-30.40	Placing Type 2 Rock Blanket	Cu. Yard	822					
613-10.14	Full Depth Saw Cut	Linear Foot	57					
618-10.00	Mobilization ·	Lump Sum	1					
805-20.00	Seeding	Acre	0.07					
806-10.17	Temporary Seeding and Mulching	Acre	0.07					
806-41.20	Type 1 Erosion Control Blanket	Sq. Yard	141					
806-10.19	Silt Fence	Linear Foot	381					
	Removal of Temporary Power Pole	Lump Sum	1					

Pay Item No.	Description	Unit	Quantity	Unit Cost	Amount
616-10.05	Construction Signs	Sq. Foot	202		
616-10.21	Channelizer (Drum-Like) with Light	Each	29		
616-10.31	Type III Movable Barricade with Light	Each	1		
616-20.00	Work Zone Traffic Signals	Each	1		
617-36.00D	Temporary Traffic Barrier - Contractor Furnished and Retained	Linear Foot	413		
617-50.10A	Relocating Temporary Traffic Barrier	Linear Foot	288		
620-53.01B	Preformed Removable Marking Tape 4 in. White	Linear Foot	1465		
620-53.09	Preformed Removable Marking Tape, 24 in. White	Linear Foot	23		
620-60.00B	4 in. White Acrylic Waterborne Pavement Marking Paint	Linear Foot	595		
620-60.01B	4 in. Yellow Acrylic Waterborne Pavement Marking Paint	Linear Foot	1233		
620-70.01	Pavement Marking Removal	Linear Foot	2004		
			Cubtatal Ci	gning/Striping=	