



ADDENDUM NUMBER TWO

DATE: April 17, 2014

OWNER: City of Pacific, Missouri
300 Hoven Drive
Pacific, Missouri 63069

SUBJECT: Addendum Number Two to
Thornton Road Improvements
Federal Project No. STP-5419(604)
Cochran Project No. SC11-277

This Addendum forms a part of the Bidding and Contract Documents and modifies the original Bidding Documents. **FAILURE TO ACKNOWLEDGE RECEIPT OF ADDENDUM MAY SUBJECT BIDDER TO DISQUALIFICATION.**

ITEM:

1. Clarification: Echelon Paving will not be required. Paving to be in accordance with JSP -15, paragraph T.

ATTACHMENTS: Revised Bid Form

END ADDENDUM NO. 2

ITEMIZED BID FORM

Bid No.	Description	Unit	Quantity	Unit Cost	Extended Cost	DBE Item *
1500.1	Mobilization	LS	1			
1500.2	Channelizers (Trimline)	EA	100			
2000.1	Clearing, Grubbing and Stripping	AC	1			
2200.1	Removal of Improvements	LS	1			
2200.2	Pavement Milling	SY	8,710			
2300.1	Earthwork	STA	40			
2300.2	MoDOT Type 2 Ditch Liner with Geotextile Fabric	CY	387			
2300.3	Rock Excavation	CY	100			
2350.1	Silt Fence	LF	3,746			
2350.2	Inlet Check	EA	14			
3000.1	Storm Sewer (24" Class III RCP)	LF	656			
3000.2	Storm Sewer (8'x8' Precast Concrete Box Culvert)	LF	59			
3000.3	Flared End Section (24" Class III RCP)	EA	1			
3000.4	Storm Sewer Structure (Manhole)	EA	2			
3000.5	Storm Sewer Structure (Curb Inlet)	EA	8			
3000.6	Storm Sewer Structure (Area Inlet)	EA	2			
3000.7	Storm Sewer Structure (Grated Inlet)	EA	1			
3000.8	Storm Sewer Structure (Double Grated Inlet)	EA	1			
3000.9	Storm Sewer Structure (Grated Inlet With Side Intake)	EA	1			
3000.10	Concrete Headwall	CY	16			
3000.11	Utility Cut Pavement Repair (Concrete and Sawcuts)	LF	167			
3200.1	Type "A" Guardrail	LF	702			
3200.2	Type "A" Crashworthy End Terminal	EA	8			
3200.3	Property Fence (Type A)	LF	1,242			
3200.4	Property Fence (Type B)	LF	609			
3200.5	Double Swing Gate (40'-0" wide)(Chainlink with 3 Strand Barbed Wire)	EA	1			
3900.1	Adjust to Grade (Sanitary Manholes)	EA	6			
4000.1	Asphalt Pavement (BP-1) (Surface Course) (2")	TON	1,336			
4000.2	Asphalt Patch, 5"	SF	1,480			
4000.3	Paving Fabric	SY	11,846			
5000.1	Full Depth Pavement (Repair)	SY	79			
5000.2	Full Depth Pavement (Widening)	SY	3,090			
5000.3	Concrete Approach, 6"	SF	7,889			
5000.4	Concrete Vertical Curb	LF	1,990			
5000.5	Concrete Curb and Gutter	LF	34			
5000.6	Concrete Swale	SF	43			
5000.7	Concrete Island, 6" (Doweled)	SF	203			
Sub-total Roadway Items						

*Contractor is required to indicate with a " * " which line items will be performed by the DBE(s).

Continued on next page

ITEMIZED BID FORM CONTINUED

Bid No.	Description	Unit	Quantity	Unit Cost	Extended Cost	DBE Item *
1500.3	"Road Work Ahead" Sign (W20-1)	EA	2			
1500.4	"Shoulder Work Ahead" Sign (W21-5)	EA	2			
1500.5	"End Road Work" Sign (G20-2)	EA	2			
1500.6	Portable Traffic Signal (Contractor Retained)	EA	2			
3200.6	"Bike" Sign (W11-1)	EA	4			
3200.7	"Share the Road" Signs (W16-1)	EA	4			
6000.1	Pavement Marking - Lane Lines 4" - White & Yellow (Epoxy, No Grinding)	LF	8,796			
6000.2	Pavement Marking 12" - White (Epoxy, No Grinding)	LF	386			
6000.3	Pavement Marking 24" - White (Epoxy, No Grinding)	LF	26			
7000.1	Relocate Pedestrian Signal Assembly	EA	1			
7000.2	Countdown Pedestrian Signal Head	EA	2			
7000.3	8' Post and Base for Pedestrian Signal Head and Pushbutton	EA	1			
7000.4	Pedestrian Pushbutton	EA	2			
7000.5	3" Conduit for Pedestrian Signals	LF	179			
7000.6	Signal Cable, (7c #16)	LF	214			
7000.7	Pull Box for Pedestrian Signal, 17" x 30"	EA	1			
7000.8	Countdown Pedestrian Push Button Sign (R10-3e)	EA	2			
Sub-total Signing/Striping/Signals Items						
3200.8	Pedestrian Fence	LF	45			
5000.8	Concrete Sidewalk	SF	11,809			
5000.9	Concrete Sidewalk with Integral Curb	SF	4,578			
5000.10	Concrete Sidewalk Bridge	EA	2			
5000.11	Detectable Warning Devices	SF	81			
Sub-total Bicycle/Pedestrian Facility Items						
5000.12	Block Retaining Wall	SF	1,145			
5900.1	Street Light Assembly	EA	20			
5900.2	Underground Cable in Conduit, 1 1/2"	LF	3,687			
5900.3	Hand Hole, 13" x 24"	EA	1			
5900.4	Load Center	EA	1			
9000.1	Seed, Mulch & Fertilize	SY	4,637			
Sub-total Landscaping/Streetscaping Items						
Total Base Bid						

*Contractor is required to indicate with a " * " which line items will be performed by the DBE(s).