

**PECULIAR ENTRANCE MONUMENT SITE
CONSTRUCTION
Addendum No. 3- Federal Project No. STP-9900 (491)**

**DATE: MARCH 24, 2014
REVISED REQUEST FOR PROPOSAL (BIDS)**



CITY OF PECULIAR, MISSOURI

**250 S. MAIN STREET AVENUE
PECULIAR, MO 64078
(816) 779-2228
(816) 779-1004 FAX**

The bid date has not changed, and the bid date remains as March 25, 2014 @ 3:00 p.m., local time.

1. Specifications

a. On Bidder Checklist: Item #1, only the crossed out section below does not apply.

~~1. Submit completed Contractor Questionnaire and/or Contractor Prequalification Questionnaire with attachments not later than seven (7) days prior to the date and hour of the bid opening. See Secs 101-103 of the Standard Specifications, and Rule 7 CSR 10-15.900, "Prequalifications to Bid of Certain Contractors". Questionnaire and Contact information are provided on MoDOT's website. (if applicable—required on highway and bridge projects)~~

Sec.102.2 of the Missouri Standard Specifications for Highway Construction will be waived for this project.

b. Section 04870 – Cast Stone

- i. The wall capstone is intended to be cast stone as listed in the specification for cast stone.

c. Section 02900 – Landscaping

**PECULIAR ENTRANCE MONUMENT SITE
CONSTRUCTION
Addendum No. 3- Federal Project No. STP-9900 (491)**

- i. Section 02900-1.2.C., and Sheet No. C001. At the contractor's option, the plug and seed installation of buffalo grass may be delayed until the fall (2014) planting season, while maintaining a delayed 1 year warranty in lieu of planting the buffalo grass at the beginning of the summer season, due to a high likely failure rate.
 - ii. Section 02900-1.7.C. Watering shall continue by Contractor until a lawn is established. After the acceptable lawn is established, the City shall maintain the watering.
 - iii. Section 02900- 1.7.E. After paragraph 1.7. E. End of Section, delete page 5 of Section 02900.
2. Drawings
- a. Sheet No. C500
 - i. Retaining Wall Detail, detail 3. The original wall design calls for a 14" width wall from the top of the footing to the bottom of the brick facing layer and a 12" width wall from there up, creating a 2" brick ledge for the facing brick to rest upon. This addendum allows a design alternate to construct a constant 12" width wall from footing to top with the facing bricks resting on a mortared to the wall concrete block layer (4"x8"x16") placed from the top of footing to bottom of brick layer.

End of Addendum No.3

Carl M. Brooks, P.E.
City Engineer
City of Peculiar