MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

SUMMARY OF QUANTITIES

1 8/23/13 PAVEMENT MARKING QUANTITIES REVISED

PAVEMENT MARKING MATERIAL

Sheet No.	Location	Station	Station	ACRYLIC WATERBORNE PAINT 4" SOLID WHITE, FT.	4" INT. WHITE, FT.	4" SOLID YELLOW, FT.	4" INT. YELLOW, FT.	TYPE 2 PREFORMED MARKING TAPE (GROOVED) 24" SOLID WHITE, FT.	LEFT TURN ARROW SYMBOL, EA. 1	REMARKS
				ITEM NO. 620-60.00B		ITEM NO. 620-60.01B		ITEM NO. 620-51.20	ITEM NO. 620-51.30	
108	20TH STREET	234+99	238+69		100					EB INTERMITTENT LANE LINE
108	20TH STREET	237+81	238+43			62	20			EB LANE LINE
108	20TH STREET	238+93	239+15	22	1					EB LANE LINE
108	20TH STREET	238+93	239+30	37						EB LANE LINE
108	20TH STREET	239+44	---					128		EB CROSSWALK
108	20TH STREET	239+62	---					12		EB STOP LINE
108	20TH STREET	239+69	---					26		EB STOP LINE
108	20TH STREET	239+78	---					105		SB CROSSWALK
108	20TH STREET	240+09	---					10		NB STOP LINE
108	20TH STREET	240+20	---					20		NB STOP LINE
108	20TH STREET	240+34	---					65		WB CROSSWALK
108	20TH STREET	240+35	---					12		SB STOP LINE
108	20TH STREET	240+67	---					92		NB CROSSWALK
108	20TH STREET	240+97	---					22		WB STOP LINE
108	20TH STREET	240+97	241+97	100						WB LANE LINE
108	20TH STREET	240+97	241+97	100						WB LANE LINE
108	20TH STREET	240+97	243+45	70						EB INTERMITTENT LANE LINE
108	20TH STREET	241+05	---					11		WB STOP LINE
108	20TH STREET	241+05	243+45			488				EB/WB CENTERLINE
108	20TH STREET	241+26	241+97						2	WB SYMBOLS
108	20TH STREET	242+27	243+57		40					WB INTERMITTENT LANE LINE
108	20TH STREET	242+83	243+45	62						EB LANE LINE
108	20TH STREET	243+00	---						1	EB SYMBOL
108	20TH STREET	244+25	244+70	45						WB LANE LINE
108 - 109	20TH STREET	244+25	255+94		300					EB INTERMITTENT LANE LINE
108 - 109	20TH STREET	244+25	255+94		300					WB INTERMITTENT LANE LINE
108 - 109	20TH STREET	244+25	256+23			2398				EB/WB CENTERLINE
108	20TH STREET	244+60	---						1	WB SYMBOLS
108	20TH STREET	248+83	250+56	173						WB EDGE LINE
108	20TH STREET	249+08	250+81	173						EB EDGE LINE
109	20TH STREET	255+33	256+23	90						EB LANE LINE
109	20TH STREET	255+43	256+05						2	EB SYMBOLS
109	20TH STREET	257+07	257+79			72	20			EB LANE LINE
109	20TH STREET	257+07	257+79			72	20			WB LANE LINE
109	20TH STREET	257+33	257+83		20					EB INTERMITTENT LANE LINE
109	20TH STREET	257+38	257+48		10					WB INTERMITTENT LANE LINE
109	NEW HAMPSHIRE AVE.	2+20	4+51			464				NB/SB CENTERLINE
109	NEW HAMPSHIRE AVE.	2+99	4+51	152						NB LANE LINE
109	NEW HAMPSHIRE AVE.	3+09	4+29						3	NB SYMBOLS
109	NEW HAMPSHIRE AVE.	5+58	8+04			492				NB/SB CENTERLINE
SHEET 1 SUBTOTAL				1024	770	4048	60	503	9	
BID ITEM TOTAL				1794		4108		503	9	

1

1

SHEET 6 OF 10

STATE OF MISSOURI
DOUGLAS B. PARKE
NUMBER PE-2011011130
PROFESSIONAL ENGINEER

THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.

DATE PREPARED 8/30/2013

ROUTE	STATE
N/A	MO
DISTRICT	SHEET NO.
SW	14

COUNTY: JASPER

JOB NO. TDG-3200(718)

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

TRANSYSTEMS CORP.
2400 PERSHING ROAD
SUITE 400
KANSAS CITY, MO 64108
PHONE: (816)329-8600
FAX: (816)329-8601

MO STATE CERTIFICATE OF AUTHORITY # 273
ENGINEERING

REV.