



Architecture and Engineering

over 35 Years of Experience

3216 Emerald Lane, Suite D, Jefferson City, MO 65109
Ph: (573)634-3551 Fx: (573)634-3424 Email: SVCon@aol.com

**Clark County Commission
Over the Wyaconda/Danker Bridge
BRO-B023(24)**

Date: May 9, 2013

SPECIFICATIONS MANUAL Sealed by: FRIDTJOV N. SEVERUD, JR.,

ADDENDUM #1

This bridge was recently damaged by a flood. The General Contractor will be responsible for removing the portion of the bridge that is within the construction site. It is recommended that this bridge site be viewed prior to submitting a bid.

1. Itemized Bid page 2 of 2 has been changed. Use the Revised sheet for bidding purposes.
2. The Clark County Commission would like for this project to be open for traffic in time for harvest season.

This addendum contains 2 pages.

End of Addendum

Attachment: Itemized Bid -2 of 2 (Revised 5/9/13)

ITEMIZED BID
(Revised 5/9/13)(Addendum No.1)

BRIDGE CONSTRUCTION

ITEM NO.	ITEM (MO STD.)	UNIT DESCRIPTION	QTY.	UNIT PRICE	AMOUNT
11	216-10.10	Removal of Bridge L.S.	1		
12	606-22.00	Bridge Anchor Section Each	4		
13	606-99.02	Guardrail Terminal Section Each	4		
14	606-10.00	Guardrail (Type A) L.F.	250		
15	702-10.14	14"Dia. C.I.P. Pile L.F.	1794		
16	703-20.03	Class B Concrete (Substructure) CuYd	35.1		
17	703-42.10	Class B2 Concrete (Superstructure) CuYd	196.3		
18	716-10.00	Plain Neoprene Bearing Pads Each	18		
19	703-99.03	(C.I.P.) Concrete Bridge Rail (Class B1 Conc.) L.F.	508		
20	705-11.70	P/C, P/S Concrete I-Girders (70' span) Each	3		
21	705-11.80	P/C, P/S Concrete I-Girders (80' span) Each	6		
22	705-60.62	P/C, P/S Concrete Panel Forms Sq.Yd.	391		
23	706-10.60	Reinforcing Steel (Bridges) Pound	47,270		
SUBTOTAL FOR BRIDGE CONSTRUCTION:					
TOTAL FOR PROJECT:					