

ADDENDUM NO. 4

ISSUED BY: Great River Associates
2826 S Ingram Mill Road
Springfield, Missouri 65804
(417) 886-7171
(417) 886-7591 --- FAX

DATE: November 28, 2012

FOR: **PETTIS COUNTY BRIDGE REPLACEMENT**
BRIDGE 2090031
BRO-B080(26)
GRA NO. 12-3073

The attached revisions hereby supersede any and all data with which they may conflict as indicated on the Drawings, Specifications and related documents issued in the original set. Each trade is responsible for changes in its work caused by changes in the work of other trades. This addendum is a part of and shall be attached to the original set of plans and specifications for the work.

ITEM 1

The bill of reinforcing on Sheet S15 is changed as follows:

1. The #5 U11, #6 U12 and #5 U15 bars in Abutment #1 are to be epoxy coated.
2. Delete the #5 U21 bars in Abutment #2.
3. The #6 S3 bars in the slab are changed to 44'-9" and the quantity is changed to 36. The minimum lap splice length is 23".
4. The #5 S4 bars in the slab are changed to 24'-0" and the quantity is changed to 18. The minimum lap splice length is 20".
5. The plain steel bar weight is 12,283 pounds and the epoxy bar weight is 9,619 pounds.

ITEM 2

The Bid Form is changed as follows:

1. Bid Item 27 is changed to **REINFORCING STEEL (PLAIN) 12,283 LBS.**
2. Bid Item 28 is changed to **REINFORCING STEEL (EPOXY) 9,619 LBS.**

Bidders are to change these items on the Bid Form and initial the change.

