

Weldon Spring City Hall  
5401 Independence Road  
Weldon Spring, Missouri 63304

February 22, 2012

**Re: Independence Road Reconstruction Phase 2**

**CONTRACT ADDENDUM #1**

**TO ALL BIDDERS:**

**You are hereby notified of the following changes to the above referenced Contract Documents and Specifications for Independence Road Reconstruction Phase 2.**

- 1) Instruction to Bidders Item No. 12 (Page IB-5) – Should read *Bids will be received until 10:00 (ten o'clock) A.M., March 1, 2012 by:*
- 2) Job Special Provisions – Addition to Section 2.1

**2.1.5 Contractor Furnished Construction Staking**

The CITY will provide the site control. The CONTRACTOR shall provide all necessary construction staking. This is including, but not limited to, all required centerline, pavement and necessary staking for construction of improvements. Missouri American Water Company has indicated that they will require approximately 2 stakes per cross section along the extent of the watermain relocation. All other utility companies have indicated that they will likely be able to work off of centerline stakes. The CONTRACTOR will be responsible for re-establishment of all property corners, by a Professional Licensed Surveyor, along the project corridor.

- 3) City-Contractor Agreement Article 3. Time of Completion – Should state *The project shall be fully complete under this contract within 210 days from the date of the written "Notice to Proceed."*
- 4) The culvert pipe from EP4 to 2GI3 and from 2GI3 to CI2 are 36" RCP as indicated on the profile sheets and reflected in the quantities. The label on sheet 4 (plan & profile 2) should read 36" RCP.
- 5) The Relocated 2" Force Main depicted on Sheets 4 & 5 will not be relocated as shown. The manhole shown as TBR&R shall be adjusted to grade and the cover shall be approved by a Duckett Creek Sanitary District inspector. The depth of the existing forcemain shall be determined prior to construction of the proposed storm sewer crossings at station 6+10 and between stations 9+50 and 10+20. Vertical conflicts shall require adjustment of the forcemain or other proposed improvements as determined necessary. Any adjustments to the forcemain or the proposed improvements shall be incidental to construction.

This addendum must be acknowledged by submittal of the Contract Addendum form on page AD-1. Please feel free to contact us with questions.

Sincerely,



Michael N. Meiners, P.E  
City Engineer of Weldon Spring.