



Clay County, Missouri

Purchasing Department

16 W. Franklin, Suite 16-B ~ Liberty, MO 64068

PURCHASING DEPARTMENT

IFB 20-20

BRIDGE REPLACEMENT ON NE 188TH STREET OVER NEW HOPE CREEK BRO-B024(26) BRIDGE DEMOLITION, BRIDGE RECONSTRUCTION AND ROAD GRADING

ADDENDUM No. 3

Dear Vendor,

The original IFB remains in effect except as revised by the following changes, which shall take precedence over anything to the contrary in the specifications.

Except as amended by this Addendum, all terms and conditions of the IFB remain unchanged.

Please Note: The format for this addendum will detail questions asked, answers given and clarifications and statements made. Q = Question, A = Answer, C = Clarification and S = Statement.

Q1: Will the county be providing the Type 2 Rock Blanket and the Type 3 Rock Ditch Liner?

A1: a. Per the Spec - 609.60.5.4 If the plans do not provide for a source of material, the contractor shall provide the material. All costs for securing the source, quarrying, excavating, breaking and hauling the material to the site will be paid for at the contract unit price for Furnishing Rock Ditch Liner.

b. There will be a Furnishing Type 2 Rock Blanket quantity and a Placing Type 3 Rock Ditch Liner quantity for both projects.

- i. 188th St Project – Furnishing Type 2 Rock Blanket – 671 CU YD
- ii. 188th St Project – Placing Type 2 Rock Blanket – 671 CU YD
- iii. 188th St Project – Furnishing Type 3 Rock Ditch Liner – 144 CU YD
- iv. 188th St Project – Placing Type 3 Rock Ditch Liner – 144 CU YD

Q2: Who is providing the Geo textile fabric that is on sheet 24?

A2: Geotextile Fabric will be provided by the contractor. See the Spec on Rock Blanket and Rock Ditch liner. There will be a Permanent Erosion Control Geotextile quantity for both projects

- i. 188th St Project - Permanent Erosion Control Geotextile – 1356 SQ YD

Q3: What about road signs, there is no line item for them?

A3: The only signs on the project can be found on Sheet 7 of the 148th St and 188th St project. The quantities for those items (FLAT SHEET & WOOD POST 4X4) can be found on sheets 13 of the 148th St and 188th St projects.

Q4: What about road closed movable barricades, etc?

A4 From the plan cover sheet. The County will maintain the SIGNAGE (reflectivity, etc.). The Contractor checks the devices daily to maintain the CLOSURE OF THE ROAD. When the construction is over, the County will pick up their property.

THE ROUTE, 148TH STREET, IS CURRENTLY CLOSED BY THE COUNTY AND WILL REMAIN CLOSED DURING CONSTRUCTION. THE COUNTY SHALL MAINTAIN ROAD CLOSURE SIGNAGE. THE CONTRACTOR SHALL CHECK THESE DEVICES DAILY TO MAINTAIN CLOSURE OF THE ROAD.

And in the Special Provisions...

N. Work Zone Traffic Management Plan JSP-02-06A

I Description

- 1.1 This route is currently closed to construction. The County had erected the road closures that are in place. The Contractor shall keep the route closed from the start to the end of construction of the project improvements.

CLAY COUNTY
BRIDGE REPLACEMENT, BRO-B024(27)

JOB SPECIAL PROVISIONS
Page 20 of 21

- S1:** S1 from Addendum 2 is no longer valid. Bids will not be accepted at the Highway Department from 11:30:00 AM to 1:59:59 PM on March 26, 2020.
- S2:** S2 from Addendum 2 is no longer valid. There will not be a teleconference at 3:00 PM on March 26, 2020.
- S3:** The Due Date for all Bids has been extended until April 23, 2020 at 2:00 PM (CST)

ACKNOWLEDGEMENT

Each bidder shall acknowledge receipt of this Addendum No. 3 of IFB 20-20, Bridge Replacement on NE 188th Street Over New Hope Creek BRO-B024(26) Bridge Demolition, Bridge Reconstruction and Road Grading by their signature affixed hereto, and shall attach this Addendum to the original IFB.

CERTIFICATION BY BIDDER

SIGNATURE _____

TITLE _____

COMPANY _____

DATE _____

Cordially,

Clay County Purchasing Department