

## ADDENDUM NO. 2

TO: All Holders of Plans and Contract Documents  
for the Webb City Long-Range Sidewalk  
Enhancement Plan, Phase II  
Project, TAP-3221(703)  
Webb City, Missouri

ISSUED: November 30, 2020

Name of Bidder:

\_\_\_\_\_  
Receipt Acknowledged By

**This Addendum is hereby made a part of the Contract Documents to the same extent as if it were originally included herein. This Addendum shall be inserted in the Contract Documents and submitted with the Bid, and includes the following items:**

### PLANS:

- 1) All improvements included on Sheet 10 of the plans are included as Add Alternate #1 on the bid schedule and shall be bid as such (see below for more instruction on add alternate bid).
- 2) The City will relocate all existing fire hydrant assemblies and water meters that are in conflict with project improvements.

### CONTRACT DOCUMENTS:

- 1) The bid schedule is hereby replaced with the attached revised bid schedule. The replacement bid schedule shall be used in the bid submitted.
  - a. Traffic control Items are to be bid as lump sum to allow the contractor flexibility in choosing a MoDOT approved traffic control management plan. Traffic control may be staged with construction areas in order to reduce the number of traffic control devices in place at one time. The contractor is advised that any additional material needed to provide traffic control shall be considered part of and completely paid for in the Traffic Control lump sum item.
  - b. The quantity for Seeding & Mulch and Linear Grading – Class 1 were corrected (rounding errors).
- 2) Add Alternate: The Contractor shall submit a bid for the Add Alternate section. The City reserves the right to award, to the lowest responsible bidder, the combination of base plus add alternate sections that will allow the most work to be completed within the City's budget of \$275,200. If the City chooses to exercise this right, the award of Add Alternate sections will be selected in accordance with the following priorities:
  - i. Base + Alt. 1
  - ii. Base

The City reserves the right to award the combination of highest priority add alternate sections over the City's budget as long as the low bidder does not change and the award of the combination of highest priority alternate sections does not exceed more than ten percent of the City's budget, whichever is less.

The City's budget is the basis for award of add alternates but not the basis for award of the base section. The base section of the contract will be awarded or rejected in accordance with Sec 100.

The awarded bidder will be notified of the City's selection of the combination of add alternate sections to be awarded.


**Bid Bond Requirements:** The contractor shall be required to obtain a bid bond for 5% of the total bid amount for the base bid and all add alternates. This bid bond will be considered applicable to the proposed work for any option.

MISCELLANEOUS:

- 1) Testing will be conducted by Anderson Engineering and paid for by the LPA as outlined in their existing engineering services agreement. Acceptance testing will NOT be conducted at the contractor's expense.
- 2) All construction staking is the responsibility of the contractor.

Sincerely,

*Anderson Engineering, Inc.*



J. Andrew Eckhart, P.E.



ITEMIZED BID SCHEDULE

Sidewalk Improvements Phase II, TAP-3221(703) - Stadium Drive  
Webb City, Missouri

NAME OF BIDDER:

Bidder assures and acknowledges that each unit or lump sum bid price includes the cost of all adjacent, incidental, related, and companion items which are shown on the drawings, called for in the specifications, or otherwise necessary to provide a complete						
The OWNER reserves the right to increase, decrease, or delete from the Project quantities of work at the Unit Bid Price or Lump Sum Price in order to bring the total contract price to the budgeted project expenditures.						
The bidder should complete the following sections in accordance with Section 102.7. The bidder proposes to furnish all all labor, materials, equipment, services, etc. required for the performance of the work as follows:						
Sidewalk Improvements Phase II, TAP-3221(703)						
	Item No.	Description	Unit	Quantity	Unit Price	Amount
1	202-20.10	REMOVAL OF IMPROVEMENTS	LS	1		
2	206-30.00	CLASS 3 EXCAVATION	CY	31		
3	207-10.00	LINEAR GRADING - CLASS 1	STA	26		
4	304-05.04	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	SY	1992		
5	608-30-08	CONCRETE MEDIAN STRIP (8 IN. ISLAND)	SY	41		
6	608-10.12	TRUNCATED DOMES	SF	132		
7	608-60.04	CONCRETE SIDEWALK, 4 IN.	SY	1315		
8	608-99.05	CONCRETE DRIVEWAY ENTRANCES, 8 IN.	SY	676		
9	609-99-03	CURB AND GUTTER (2'-0")	LF	2425		
10	616-10.99	TEMPORARY TRAFFIC CONTROL	LS	1		
11	618-10.00	MOBILIZATION	LS	1		
12	620-00.36	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	EA	7		
13	620-00.42	PREFORMED THERMOPLASTIC PAVEMENT MARKING, 12 IN WHITE, YIELD LINE TRIANGLES	EA	12		
14	620-59.02A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	LF	218		
15	620-61.24A	24 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	LF	24		
16	725-03.12A	12 IN. PIPE GROUP B	LF	106		
17	731-99.02-A	CURB INLET (4 FT X 2 FT)	EA	1		
18	731-99.02-B	DROP INLET (3 FT X 3 FT, REPLACEMENT)	EA	1		
19	805-99.19	SEEDING AND MULCH	AC	0.18		
20	806-10.07A	CURB INLET CHECK	EA	2		
21	806-10.19	SILT FENCE	LF	90		
22	903-50.04A	SH-FLAT SHEET (PERMANENT SIGNING)	SF	45		
				Total Base Bid Amount		

ITEMIZED BID SCHEDULE

Sidewalk Improvements Phase II, TAP-3221(703) - Stadium Drive  
Webb City, Missouri

NAME OF BIDDER: \_\_\_\_\_

THE ITEMS LISTED HEREINAFTER ARE TO BE BID AS ALTERNATES AND ADD ALTERNATES. THESE ITEMS WILL BE CONSIDERED BY THE OWNER AND THE ENGINEER FOR THE PROJECT, SUBJECT TO AVAILABLE FUNDING. THE BID WILL BE AWARDED BASED ON THE PRIORITIZED ALTERNATES TO THE LOWEST RESPONSIVE AND RESPONSIBLE BIDDER. SEE 'ALTERNATES' JOB SPECIAL PROVISION IN CONTRACT DOCUMENTS FOR ADDITIONAL INFORMATION.

Add Alternate #1 - Madison Street					
Sidewalk Improvements Phase II, TAP-3221(703)					
Item No.	Description	Unit	Quantity	Unit Price	Amount
202-20.10-ALT	REMOVAL OF IMPROVEMENTS	LS	1		
206-30.00-ALT	CLASS 3 EXCAVATION	CY	51		
207-10.00-ALT	LINEAR GRADING - CLASS 1	STA	1		
304-05.04-ALT	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	SY	35		
605-302.0A-ALT	FRENCH UNDERDRAIN (4" PERFORATED PVC)	LF	105		
608-60.04-ALT	CONCRETE SIDEWALK, 4 IN.	SY	9		
608-99.05-ALT	CONCRETE DRIVEWAY ENTRANCES, 8 IN.	SY	27		
609-10-60-ALT	PAVED DITCH	SY	2		
609-99-03-ALT	CURB AND GUTTER (2'-0")	LF	24		
613-99.05-ALT	PAVEMENT REPAIR	SY	45		
726-99.03-ALT	6 IN. HDPE PIPE	LF	125		
731-00.48-ALT	PRECAST CONCRETE MANHOLE (48 IN. FLAT TOP)	LF	3		
Add Alternate 1 Amount					
Total Base Bid Amount +Add Alternate 1					