LEE C. FINE MEMORIAL AIRPORT CITY OF OSAGE BEACH, MISSOURI

ADDENDUM NO. 1

for

State Project No. 20-046B-1

BASE BID: RECONSTRUCTION OF THE SOUTHERN PORTION OF THE GA APRON; DEMOLITION OF TAXIWAY CHARLIE FROM RUNWAY 4-22 TO TAXIWAY A

ADDITIVE ALTERNATE NO. 1: REALIGNMENT OF TAXIWAY BRAVO FROM TAXIWAY A
TO THE GA APRON

ADDITIVE ALTERNATE NO. 2: RECONSTRUCTION OF THE NORTHERN PORTION OF THE GA APRON

FEBRUARY 11, 2021

Prepared By:



Crawford, Murphy & Tilly Consulting Engineers St. Louis, Missouri

200486-01-00

ADDENDUM NO. 1

BASE BID: RECONSTRUCTION OF THE SOUTHERN PORTION OF THE GA APRON; DEMOLITION OF TAXIWAY CHARLIE FROM RUNWAY 4-22 TO TAXIWAY A

ADDITIVE ALTERNATE NO. 1: REALIGNMENT OF TAXIWAY BRAVO FROM TAXIWAY A TO THE GA APRON

ADDITIVE ALTERNATE NO. 2: RECONSTRUCTION OF THE NORTHERN PORTION OF THE GA APRON

This addendum is herewith a part of the Contract Documents of the above issued project, and is issued to amend and supplement the January 22, 2021 construction plan drawings, proposal, contract documents, and specifications.

The **CONTRACT DOCUMENTS** are revised as follows:

PART I - GENERAL PROVISIONS

REVISE: Section 80-08 Failure to Complete on Time, Schedule of Liquidated Damages Table, last row, to read:

Holiday Impacts	\$1,500 per holiday or holiday buffer	Per the Holiday Schedule, G-5002
	calendar day when a minimum of	
	half of the full, aircraft traffic-rated	
	(per P-501) apron, or aircraft traffic-	
	rated access to the open apron half	
	is not available	

APPENDICES

CONSTRUCTION SAFETY AND PHASING PLAN (CSPP)

REVISE: Section 2. Phasing, C. Work Area Restrictions, General (All Work Areas), paragraph 6 to read: "Because of the critical limitations placed on the Airport when portions of the parking are not available, specifically during the busiest Lake holiday/event periods (Memorial Day, Independence Day, Labor Day, Lake of the Ozarks (Boat) Shootout), a non-penal amount of \$1,500 per day will be assessed for each holiday or holiday buffer calendar day that a minimum of a half of the parking apron and the full geometry of its associated access taxiway pavement (new pavement to be rated for aircraft traffic loading per P-501) is not available for use.

PROPOSAL/FORMS

PROPOSAL FORM

REVISE: Acknowledgements by Bidder, h., last sentence, to read:

"In addition, for each day that a minimum of half of the parking apron and associated access taxiway pavement at aircraft-rated traffic strength (per P-501) is not available during a holiday and/or holiday buffer timeframe, the CONTRACTOR shall pay to the OWNER the non-penal amount of \$1,500 per calendar day where half parking capacity or access to the open apron half is not available."

FORM OF CONTRACT AGREEMENT

REVISE: Article 6 – Liquidated Damages, first paragraph, last sentence, to read:

"In addition, for each day that a minimum of half of the parking apron and associated access taxiway pavement at aircraft-rated traffic strength (per P-501) is not available during a holiday and/or holiday buffer timeframe, the CONTRACTOR shall pay to the OWNER the non-penal amount of \$1,500 per calendar day where half parking capacity or access to the open apron half is not available."

REVISE: Article 6 – Liquidated Damages, Table, last row, to read:

Holiday Impacts	\$1,500 per holiday or holiday buffer calendar	All scenarios	Per the Holiday Schedule,
	day when a minimum of half of the full,		G-5002
	aircraft traffic-rated (per P-501) apron, or		
	aircraft traffic-rated access to the open apron		
	half is not available		

The **CONSTRUCTION PLAN SHEETS** are revised as follows:

SHEET 7 of 71 - CSPP Notes Sheet 2 of 2

DELETE: This sheet. ADD: Attached sheet.

CLARIFICATION: For the four holidays/events, a full apron is no longer required. An aircraft-rated half-apron (either new PCC or existing), as defined by the Phase 1/Phase 2 limit, along with an associated aircraft-rated access connector (again, either new PCC or existing), will be required during those events.

SHEET 8 of 71 – Construction Activity Details Sheet 1

DELETE: This sheet. ADD: Attached sheet.

CLARIFICATION: 2021 Allowable Construction Timeframes has been modified to reflect the new, minimum halfapron requirements for the holidays and buffers. Heavy hauling during these buffers will not be allowed, as airport activity will be at a high, and the remaining apron will be in use by aircraft.

SHEET 33 of 71 - Jointing Plan - Base Bid

DELETE: This sheet. ADD: Attached sheet.

SHEET 34 of 71 - Jointing Plan - Base Bid, Alt. 1

DELETE: This sheet. ADD: Attached sheet.

SHEET 35 of 71 - Jointing Plan - Base Bid, Alts 1 & 2

DELETE: This sheet. ADD: Attached sheet.

CLARIFICATION: Revised sheet reflects 25' paving lanes, and a reduction of transverse panel joint reinforcement and longitudinal joint reinforcement on interior panels. Outer panels will still be doweled or basketed, pending construction method. Note that if paved with 12.5' lanes, dummy joints would be replaced with doweled construction joints for load transfer. Legend revised to include dummy sawed joints, and other jointing types renamed for consistency.

SHEET 45 of 71 - General Details Sheet 1 of 8

DELETE: This sheet. ADD: Attached sheet.

CLARIFICATION: Dummy joint detail added, other jointing types renamed for consistency.

LEE C. FINE MEMORIAL AIRPORT ADDENDUM NO. 1 RECONSTRUCTION OF GENERAL AVIATION APRON STATE PROJ. NO. 20-046B-1

REVISED CONSTRUCTION PLAN SHEETS

CONSTRUCTION ACTIVITY PLAN GENERAL NOTES: AREAS AND OPERATIONS AFFECTED BY CONSTRUCTION OPERATIONS: ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE PHASING PLAN. 2. WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT, ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING AIRCRAFT AT ALL TIMES PROTECTION OF NAVIGATION AIDS (NAVAIDS): 1. THE CONTRACTOR SHALL REMAIN CLEAR OF THE LOCALIZER, VASI SYSTEMS, WIND CONE, BEACON AND OTHER NAVAIDS FACILITIES AT ALL TIMES. 2. THE CONTRACTOR SHALL PROTECT NAVAIDS AND CABLING WITHIN THE PROJECT LIMITS, CONTRACTOR ACCESS: CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN AND CONSTRUCTION ACTIVITY PLAN SHEETS. THE CONTRACTOR SHALL DESIGNATE AT LEAST ONE PERSON TO MONITOR THE AIRPORT UNICOM FREQUENCY OF 122.80. THE PERSON DESIGNATED SHALL HAVE THE ABILITY TO EASILY COMMUNICATE WITH OTHER CONTRACTOR PERSONNEL WORKING ON THE JOBSITE. THE CONTRACTOR SHALL PROVIDE HIS/HER OWN AIRPORT RADIO(S) THE STORAGE AND STAGING AREA WILL BE AS SHOWN ON THE SITE PLAN. THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT WHEN THE CONTRACTOR IS NOT WORKING, EQUIPMENT SHALL BE STORED AT THE STAGING AREA OR WITHIN THE WORK AREA LIMITS (SEE NOTE 6).

THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS

SHOWN, PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED

BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE, SEE SECTION A-A ON THE SITE

AIRCRAFT TRAFFIC SHALL BE UNDER CONTROL BY A FLAGMAN OR ESCORT WHO IS MONITORING THE

THE CONTRACTOR SHALL THOROUGHLY CLEAN ALL CONSTRUCTION AREAS AND HAUL ROUTES WHICH

WILL BE OPENED TO AIR TRAFFIC TO THE SATISFACTION OF THE ENGINEER. A POWER BROOM AND

ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE CONTRACTOR FOR HAUL ROADS OR

WERE PRIOR TO BEGINNING CONSTRUCTION, NO ADDITIONAL COMPENSATION WILL BE MADE TO THE

10. ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY

11. THE CONTRACTOR SHALL NOTIFY THE LOCAL FIRE DEPARTMENT IF CONSTRUCTION ACTIVITY WILL

12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE RESTORATION, SEEDING AND MULCHING OF THE

THE CONTRACTOR SHALL NOTIFY THE ENGINEER OR AIRPORT MANAGER IF ANY WILDLIFE IS SEEN

1. THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD

MATERIAL SAFETY DATA SHEETS (SDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE

2. THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES PRIOR TO DRIVING ON AIRFIELD

THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF

THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR

REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS TO THE AIRPORT.

CONTRACTOR'S STORAGE AREAS AND HAUL ROADS.

FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT:

HAZARDOUS MATER**I**AL (HAZMAT) MANAGEMENT:

STORAGE AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY

AIRPORT UNICOM FREQUENCY. THE CONTRACTOR SHALL PROVIDE HIS/HER OWN FLAGMEN.

OPERATOR SHALL BE ON SITE AT ALL TIMES WHEN ACTIVE PAVEMENTS ARE UTILIZED FOR

ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS, TAXIWAYS AND APRONS OPEN TO

PLAN SHEET

CONSTRUCTION TRAFFIC.

THE CONTRACTOR.

WILDLIFE MANAGEMENT:

ENTERING THE AIRPORT.

PROVIDED CONTAINERS.

CONTRACTOR FOR THIS WORK.

INSPECTION REQUIREMENTS:

OWNER CITY OF OSAGE BEACH

FIRE DEPARTMENT

EMERGENCY

AIRPORT
TY DINSDALE - AIRPORT MANAGER

CRAWFORD MURPHY & TILLY INC.

OSAGE BEACH FIRE DEPT. #4

WATER
CITY OF OSAGE BEACH WATER DEPT.

RON RICHARDS - FOREMAN

BRIAN HUTSELL, P.E. - PROJECT MANAGER

FAA AIRWAYS FACILITIES
CASEY SCHALLER - COLUMBIA SSC MANAGER

NOTIFICATION OF CONSTRUCTION ACTIVITIES:

6. CONTACTS FOR THIS PROJECT ARE AS LISTED BELOW:

MIKE WELTY - ASSISTANT CITY ADMINISTRATOR

COORDINATION WITH THE AIRPORT TENANTS BY THE CITY.

5 IN THE EVENT OF AN EMERGENCY THE CONTRACTOR SHALL CALL 911

1. THE CONTRACTOR SHALL INSPECT THE JOBISTE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2G MAY BE USED TO AID IN THE INSPECTIONS.

THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER.

2. THE CONTRACTOR SHALL GIVE A MINIMUM OF 72 HOURS NOTICE TO THE CITY PRIOR TO CLOSING ANY

TAXIWAY PAVEMENTS SO THAT PROPER NOTAMS MAY BE ISSUED BY THE CITY AND TO ALLOW FOR

3, THE CONTRACTOR SHALL GIVE A MINIMUM OF 10 DAYS NOTICE TO THE FAA AIRWAYS FACILITIES AND THE

4. FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR

GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.

SHALL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT

CITY PRIOR TO CLOSURE OF THE RUNWAY SO THAT THE FAA MAY DEACTIVATE THE FAA OWNED NAVAIDS.

2. THE CONTRACTOR SHALL ATTEND A FINAL INSPECTION OF EACH PHASE WORK AREA PRIOR TO OPENING THE AREA TO AIRPORT OPERATIONS.

UNDERGROUND UTILITIES:

- 1. IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROUND UTILITIES AT CRITICAL POINTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION,
- 2. BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL 1-800-DIG-RITE TO ARRANGE FOR UTILITY LOCATES.
- LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED, ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO PREVIOUS EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF REPAIRS.
- 4. ALL EXISTING TAXIWAY AND RUNWAY LIGHTING CIRCUITS, FAA CABLES AND OTHER AIRPORT ELECTRICAL CABLES SHALL REMAIN IN SERVICE UNTIL REPLACED AS ACCEPTABLE TO THE RESIDENT ENGINEER. ALL TEMPORARY CABLING AND SPLICING NECESSARY TO KEEP THE CIRCUITS IN OPERATION SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

PENATLIES:

- NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT
- 2. FOR EACH AND EVERY CALENDAR DAY THE PROJECT OR PROJECT PHASE REMAINS INCOMPLETE BEYOND THE CONTRACT TIME ALLOWED FOR PERFORMANCE OF THAT WORK ITEM, THE CONTRACTOR SHALL PAY THE NON-PENAL AMOUNT OF \$800,00 PER CALENDAR DAY AS A LIQUIDATED DAMAGE TO THE OWNER. FURTHERMORE, THE CONTRACTOR SHALL PAY THE NON-PENAL AMOUNT OF \$800.00 PER CALENDAR DAY PLUS \$250.00 FOR EVERY HOUR AS A LIQUIDATED DAMAGE TO THE OWNER FOR EACH AND EVERY HOUR RUNWAY 4-22 IS CLOSED BEYOND THE MAXIMUM ALLOWED 7 DAY CLOSURE PERIOD.

SPECIAL CONDITIONS:

- 1. A MINIMUM OF HALF THE APRON, AS DEFINED BY THE PHASE 1/2 LIMIT LINE, AND ASSOCIATED TRAFFIC-RATED TAXIWAY ACCESS SHALL BE OPEN DURING MEMORIAL DAY WEEKEND, 4TH OF JULY, THE LAKE OF THE OZARKS SHOOTOUT, AND LABOR DAY WEEKEND. FOR ALL INTENTS AND PURPOSES, ALL OF THESE EVENTS SHALL BE CONSIDERED "HOLIDAYS".
- 2. THE OPEN HALF OF THE APRON AND CONNECTING TAXIWAY ACCESS SHALL EITHER BE EXISTING PCC, OR NEW PCC HAVING GAINED ADEQUATE STRENGTH, PER P-501, FOR OPENING TO AIRCRAFT TRAFFIC.
- 3. IF A HOLIDAY/EVENT LANDS DURING THE WEEK, ONLY HALF OF THE APRON MAY BE CLOSED FOR THE ENTIRE WEEK OF THE HOLIDAY/EVENT.
- 4. IF THE HOLIDAY/EVENT LANDS ON A WEEKEND, ONLY HALF OF THE APBON MAY BE CLOSED FROM 2 BUSINESS DAYS BEFORE UNTIL 2 DAYS AFTER THE HOLIDAY/EVENT. SEE ALLOWABLE CONSTRUCTION TIME FRAMES TABLE ON DRAWING G-5002
- 5 LIQUIDATED DAMAGES WILL BE ASSESSED IF MORE THAN HALF OF THE APRON REMAINS CLOSED, OR TAXIWAY ACCESS TO THE OPEN HALF OF THE RUNWAY IS NOT AVAILABLE, BEYOND THE ALLOTTED TIME FRAMES, IMPACTING HOLIDAY PARKING CAPACITY, AS SHOWN ON G-5002.

RUNWAY & TAXIWAY VISUAL AIDS:

(573) 302-2000

(573) 216-4743

(314) 571-9077

(573) 875-5310

(573) 348-8992 (NON-EMERGENCY)

(573) 302-2020

911

- THE AIRPORT WILL BE CLOSED DURING A PORTION OF THIS PROJECT. THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOW THE REQUIREMENTS OF FAA AC 150/5370-2G.
- 2. BARRICADES SHALL BE USED AS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN SHEET OR AS DIRECTED BY ENGINEER.

MARKINGS & SIGNS FOR ACCESS ROUTES:

1. BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED ON THIS SHEET AND THE CONSTRUCTION ACTIVITY DETAILS AND CRITICAL POINTS TABLE ON DRAWING

HAZARD MARKING & LIGHTING:

- 1. THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT,
- 2. ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN ACCORDANCE WITH FAA ADVISORY CIRCUI AR 150/5370-2G AND 150/5210-5D AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY, THE MAXIMUM EQUIPMENT HEIGHT IS 25'.
- 3. BARRICADES SHALL BE PLACED AT THE LOCATIONS AND SPACINGS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN SHEET OR AS DIRECTED BY THE ENGINEER
- 4. THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS.

PROTECTION:

- NO WORK SHALL BE PERFORMED/REQUIRED INSIDE OF ACTIVE RUNWAY 4-22 SAFETY AREA WHICH EXTENDS 250' FROM THE RUNWAY CENTERLINE UNLESS THE RUNWAY IS CLOSED AND CLOSURE MARKERS ARE IN PLACE.
- 2. NO WORK SHALL BE PERFORMED/REQUIRED INSIDE OF AN ACTIVE TAXIWAY OBJECT FREE AREA WHICH EXTENDS 65.5' FROM THE TAXIWAY CENTERLINE UNLESS THE TAXIWAY IS CLOSED AND BARRICADES ARE

OTHER LIMITATIONS ON CONSTRUCTION:

- 1. IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE CITY, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT.
- 2. BROKEN CONCRETE, BROKEN ASPHALT, UNUSED PAINT, UNUSED SEALER AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS OTHERWISE SPECIFIED.
- 3. RUNWAY 4/22 MAY ONLY BE CLOSED FROM MONDAY AT 12:00 PM TO FRIDAY AT 12:00 PM.
- 4. IF A HOLIDAY/EVENT LANDS DURING THE WEEK, THE RUNWAY MAY NOT BE CLOSED THAT HOLIDAY/EVENT
- 5. IF THE HOLIDAY/EVENT LANDS ON A WEEKEND, THE RUNWAY MAY NOT BE CLOSED 2 BUSINESS DAYS BEFORE AND 2 BUSINESS DAYS AFTER THE HOLIDAY/EVENT. SEE ALLOWABLE CONSTRUCTION TIME FRAMES TABLE ON DRAWING G-5002.

)WG			
∇	ADDENDUM NO. 1	2/11/21	ВНН
VISION	DESCRIPTION	DATE	APPROVE

Ш					0		빏	
_					9-50			
Project Date: 1/21/21	Plot Scale:			et 22"x34"	CONSTRUCTION ACTIVITY NOTES 3-5000.		01	
Approved by: BHH	Chk by: TWM, ASF	11-Feb-21 19:48	Brian Hutsell	At Full Size Sheet 22"x34"	ONSTRUCTIO	lo: 20-046B-1	20-0486-01	
Designed by: DFH	Dwn by: DFH	Plot Date: 1	Plot By: B	Page Size: A	File Name: C	Airfield Project No.:	CMT Project No.:	

ROAD IY, MO


1111 LEE C. FINE ပ Щ

. U 7

CSPP NOTES SHEET 2 OF 2



20-046B-1 awing: _G-5001 VOL. 1 of 1



The Professional Engineer's seal affixed to this sheet applies only to the material and items shown on this sheet. All drawings, instruments or other documents not exhibiting this seal shall not be considered prepared by this engineer, and this engineer exprestly disclaims any and all responsibility for such plan, drawings or documents not exhibiting this seal. ROAD

C. FINE


Ŝ


20-046B-1


rawing: <u>G</u>-5002


VOL. 1 of 1

Ö









ACKNOWLEDGEMENT

Each bidder shall acknowledge receipt of this Addendum No. 1 of

BASE BID: RECONSTRUCTION OF THE SOUTHERN PORTION OF THE GA APRON; DEMOLITION OF TAXIWAY CHARLIE FROM RUNWAY 4-22 TO TAXIWAY A

ADDITIVE ALTERNATE NO. 1: REALIGNMENT OF TAXIWAY BRAVO FROM TAXIWAY A TO THE GA APRON

ADDITIVE ALTERNATE NO. 2: RECONSTRUCTION OF THE NORTHERN PORTION OF THE GA APRON

by his/her signature affixed hereto, and shall attach this Addendum to the original bid.

CERTIFICATION BY BIDDER
SIGNATURE
TITLE
COMPANY
DATE

FAX/EMAIL TRANSMITTAL

To: Crawford, Murphy & Tilly, Inc **Attention:** Brian Hutsell

Re: Addendum #1

Fax 314.436.0723

From:
(name)

(company)

Date:

To verify that all contractors are in receipt of this addendum, Contractors are asked to sign and date this acknowledgement sheet. The Contractor should fax or E-mail to Crawford, Murphy, & Tilly, Inc. at the number/address listed below by **February 12, 2021.**

Crawford, Murphy, & Tilly, Inc. One Memorial Drive, Suite 500 Saint Louis, Missouri 63102

Fax: (314) 436-0723 Phone: (314) 436-5500

Email: bhutsell@cmtengr.com and vursin@cmtengr.com

BY: CRAWFORD, MURPHY, & TILLY, INC.