

**LEE C. FINE MEMORIAL AIRPORT  
CITY OF OSAGE BEACH, MISSOURI**

**ADDENDUM NO. 2**

for

**State Project No. 20-046B-1**

**BASE BID: RECONSTRUCTION OF THE SOUTHERN PORTION OF THE GA APRON;  
DEMOLITION OF TAXIWAY CHARLIE FROM RUNWAY 4-22 TO TAXIWAY A**

**ADDITIVE ALTERNATE NO. 1: REALIGNMENT OF TAXIWAY BRAVO FROM TAXIWAY A  
TO THE GA APRON**

**ADDITIVE ALTERNATE NO. 2: RECONSTRUCTION OF THE NORTHERN PORTION OF  
THE GA APRON**

**FEBRUARY 12, 2021**

**Prepared By:**



**Crawford, Murphy & Tilly  
Consulting Engineers  
St. Louis, Missouri**

**200486-01-00**

**ADDENDUM NO. 2**

**BASE BID: RECONSTRUCTION OF THE SOUTHERN PORTION OF THE GA APRON; DEMOLITION OF TAXIWAY CHARLIE FROM RUNWAY 4-22 TO TAXIWAY A**

**ADDITIVE ALTERNATE NO. 1: REALIGNMENT OF TAXIWAY BRAVO FROM TAXIWAY A TO THE GA APRON**

**ADDITIVE ALTERNATE NO. 2: RECONSTRUCTION OF THE NORTHERN PORTION OF THE GA APRON**

This addendum is herewith a part of the Contract Documents of the above issued project, and is issued to amend and supplement the January 22, 2021 construction plan drawings, proposal, contract documents, and specifications, and the February 11, 2021 Addendum No. 1.

The **CONTRACT DOCUMENTS** are revised as follows:

**PART III SITEWORK**

ITEM P-157 Lime Kiln Dust Treated Subgrade

REVISE: 157-6.6 Compaction, second sentence to read, "The field density shall be at least 90% of the maximum density as specified in paragraph 157-6.10."

REVISE: 157-6.10 Acceptance Sampling and Testing, a. Density, second paragraph, first sentence to read, "Each area shall be accepted for density when the field density is at least 90% of the maximum density of laboratory specimens compacted and tested per ASTM D1557."

The **CONSTRUCTION PLAN SHEETS** are revised as follows:

SHEETS 27, 28, and 29 of 71 – Grading and Drainage Plan – Base Bid; Base Bid, Alt. 1; Base Bid Alts 1 & 2

REVISE: New Storm Sewer Inlet callouts to include, "3'x3' I.D. MoDOT S-1"

SHEET 45 of 71 – General Details Sheet 1 of 8

REVISE: Dimensions and Spacing of Steel Dowels Table, to read: "Length – 18 Inches"

REVISE: Details 4, 6, 7, 8 and 10 dowel callouts to read, "18" x 1" Dia. Steel Dowel Rod"

SHEET 46 of 71 – General Details Sheet 2 of 8

REVISE: Dimensions and Spacing of Steel Dowels Table, to read: "Length – 18 Inches"

CLARIFICATION: Dowels for the project shall be 1" in diameter, 18" long and 12" on center.

## **ACKNOWLEDGEMENT**

Each bidder shall acknowledge receipt of this **Addendum No. 2** of

***BASE BID: RECONSTRUCTION OF THE SOUTHERN PORTION OF THE GA APRON; DEMOLITION OF TAXIWAY CHARLIE FROM RUNWAY 4-22 TO TAXIWAY A***

***ADDITIVE ALTERNATE NO. 1: REALIGNMENT OF TAXIWAY BRAVO FROM TAXIWAY A TO THE GA APRON***

***ADDITIVE ALTERNATE NO. 2: RECONSTRUCTION OF THE NORTHERN PORTION OF THE GA APRON***

by his/her signature affixed hereto, and shall attach this Addendum to the original bid.

CERTIFICATION BY BIDDER

SIGNATURE \_\_\_\_\_

TITLE \_\_\_\_\_

COMPANY \_\_\_\_\_

DATE \_\_\_\_\_

# FAX/EMAIL TRANSMITTAL

To: Crawford, Murphy & Tilly, Inc

**Attention: Brian Hutsell**

Re: Addendum #2

Fax 314.436.0723

From:

(name)

---

(company)

---

Date:

---

To verify that all contractors are in receipt of this addendum, Contractors are asked to sign and date this acknowledgement sheet. The Contractor should fax or E-mail to Crawford, Murphy, & Tilly, Inc. at the number/address listed below by **February 15, 2021**.

Crawford, Murphy, & Tilly, Inc.  
One Memorial Drive, Suite 500  
Saint Louis, Missouri 63102

Fax: (314) 436-0723

Phone: (314) 436-5500

Email : [bhutsell@cmtengr.com](mailto:bhutsell@cmtengr.com) **and** [vursin@cmtengr.com](mailto:vursin@cmtengr.com)

BY: CRAWFORD, MURPHY, & TILLY, INC.