

PRELIMINARY - NOT FOR CONSTRUCTION
Bid Report

Date: 02/12/2021
 Time: 02:43:39 PM

bidTABS.NET

Project: ROUTE 100 REHABILITATION	Job Number: J6S1718C_DRAFT	Bid Date: 05/21/2021	State: MO
Location: FROM KENMORE DRIVE TO KIRKWOOD ROAD			

Project Settings

Primary County: ST. LOUIS	Urban / Rural: URBAN ROUTE
Addl Counties:	Project Type: ASPH. & BITUM. RESURF(NOT LEVEL COURSE)
District: St. Louis	Work Type: REHABILITATOIN
Latitude: 90° 21' 32"	Traffic: Heavy Traffic (over 1700 DAT)
Longitude: 38° 36' 26"	Estimator: kostermiller@twm-inc.com
Log Mile: Beg:	Constr Eng: 0.00%
	Priced Date: 2/12/2021
Station: Beg: 236+63.86	Create Date: 2/12/2021
	Fed Project No: J6S1718C
Project Length: 0.8400 miles	Mobe Percent: 0.00%
Route: 100	Survey Percent: 0.00%

Project Sections

1 Roadway	\$0.00	NaN
20 Lighting	\$0.00	NaN
60 Utility	\$0.00	NaN
100 Non-Contractual Items	\$0.00	NaN
Total	\$0.00	0.0%

STIP Information

Construction Cost	\$0.00	NaN
PE (0.00% of construction cost)	\$0.00	NaN
CE (0.00% of construction cost)	\$0.00	NaN
R/W	\$0.00	NaN
R/W Incidentals	\$0.00	NaN
Utilities	\$0.00	NaN
Incentive	\$0.00	NaN
Total	\$0.00	0.0%

Major Categories

BRIDGE	\$0.00	NaN
GRADE/DRAIN	\$0.00	NaN
MISC.	\$0.00	NaN
PAVEMENT/BASE	\$0.00	NaN
Total	\$0.00	0.0%

Bid Report

Project: ROUTE 100 REHABILITATION	Job Number: J6S1718C_DRAFT	Bid Date: 05/21/2021	State: MO
Location: FROM KENMORE DRIVE TO KIRKWOOD ROAD			

Section: Roadway

Sort	Pay Item	Description	Quantity	Unit	Unit Price	Extension
10	2022010	REMOVAL OF IMPROVEMENTS	1.000	L.S.	0.00	\$0.00
20	2071000	LINEAR GRADING CLASS 1	4.600	STA.	0.00	\$0.00
30	3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	1,251.000	S.Y.	0.00	\$0.00
40	4011209	"BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)"	37.900	TON	0.00	\$0.00
50	4013000	BITUMINOUS PAVEMENT MIXTURE PG64-22 (BASE)	92.700	TON	0.00	\$0.00
60	4030109	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP125CLP MIX)	64.300	TON	0.00	\$0.00
70	4030208	ASPHALTIC CONCRETE MIXTURE PG 70-22 (SP190C MIX)	37.500	TON	0.00	\$0.00
80	4071005	TACK COAT	175.000	GAL	0.00	\$0.00
90	5021107	CONCRETE PAVEMENT (7 IN. NON-REINF)	360.000	S.Y.	0.00	\$0.00
100	6071102	MODIFIED CONCRETE GUTTER TYPE B	212.000	L.F.	0.00	\$0.00
110	6079903	MISC. {48" DECORATIVE PEDESTRIAN FENCE (STRUCTURES)}	503.000	L.F.	0.00	\$0.00
120	6079903 {1}	MISC. {CHAIN-LINK FENCE (48 IN.)}	1,159.000	L.F.	0.00	\$0.00
130	6084023	SIDEWALK HAND-RAILING WITHOUT BALUSTERS	403.000	L.F.	0.00	\$0.00
140	6085007	"PAVED APPROACH, 7 IN."	179.300	S.Y.	0.00	\$0.00
150	6086004	"CONCRETE SIDEWALK, 4 IN."	259.200	S.Y.	0.00	\$0.00
160	6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	120.000	L.F.	0.00	\$0.00
170	6091052	CURB AND GUTTER TYPE B	157.000	L.F.	0.00	\$0.00
180	6099903	MISC. {MODIFIED CURB}	59.000	L.F.	0.00	\$0.00
190	6169901	MISC. {TEMPORARY TRAFFIC CONTROL}	1.000	L.S.	0.00	\$0.00
200	6181000	MOBILIZATION	1.000	L.S.	0.00	\$0.00
210	6209902	MISC. {HELMETED BICYCLE RIDER AND ARROW SYMBOL}	7.000	EACH	0.00	\$0.00
220	6209902 {1}	MISC. {SHARROW SYMBOL}	2.000	EACH	0.00	\$0.00
230	6221003	COLDMILLING BITUMINOUS PAVEMENT FOR REMOVAL OF SURFACING (GREATER THAN 3 IN. THICK)	304.000	S.Y.	0.00	\$0.00
240	6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	1.000	L.S.	0.00	\$0.00
250	7201000	MECHANICALLY STABILIZED EARTH WALL SYSTEMS	2,118.000	S.F.	0.00	\$0.00
260	7209904	MISC. {SMALL BLOCK WALL}	1,606.000	S.F.	0.00	\$0.00
270	7209904 {1}	MISC. {PRECAST MODULAR BLOCK WALL}	4,600.000	S.F.	0.00	\$0.00
280	8089901	MISC. {LANDSCAPING}	1.000	L.S.	0.00	\$0.00
290	8089901 {1}	MISC. {VERTICAL GATEWAY MONUMENT}	1.000	L.S.	0.00	\$0.00
Category: Roadway						\$0.00

Section: Lighting

Sort	Pay Item	Description	Quantity	Unit	Unit Price	Extension
------	----------	-------------	----------	------	------------	-----------

PRELIMINARY - NOT FOR CONSTRUCTION
Bid Report

Date: 02/12/2021
 Time: 02:43:39 PM

bidTABS.NET

Project: ROUTE 100 REHABILITATION	Job Number: J6S1718C_DRAFT	Bid Date: 05/21/2021	State: MO
Location: FROM KENMORE DRIVE TO KIRKWOOD ROAD			

300	9012230	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	3.000	EACH	0.00	\$0.00
310	9013004	"CONDUIT, 4 IN. RIGID, IN TRENCH"	30.000	L.F.	0.00	\$0.00
320	9014004	"CONDUIT, 4 IN. RIGID, PUSHED"	880.000	L.F.	0.00	\$0.00
330	9015010	TRENCHING TYPE I	8,164.000	L.F.	0.00	\$0.00
340	9016110	"PULL BOX, PREFORMED CLASS 1"	17.000	EACH	0.00	\$0.00
350	9017407	"CABLE-CONDUIT, 1 IN., 2 CONDUCTORS AND 1 BARE NEUTRAL, 8 AWG"	11,110.000	L.F.	0.00	\$0.00
360	9019902	MISC. {ORNAMENTAL LIGHT POLE AND LUMINAIRE - KIRKWOOD STREETSCAPING}	94.000	EACH	0.00	\$0.00
Category: Lighting						\$0.00

Section: Utility

Sort	Pay Item	Description	Quantity	Unit	Unit Price	Extension
370	6039932	GAS {ADJUSTING GAS VALVE}	1.000	EACH	0.00	\$0.00
Category: Utility						\$0.00

Section: Non-Contractual Items

Sort	Pay Item	Description	Quantity	Unit	Unit Price	Extension
380	1099902	MISC. {ELECTRICAL SERVICE FEE}	3.000	EACH	0.00	\$0.00
Category: Non-Contractual Items						\$0.00

Total: \$0.00

REPORT PARAMETERS	
Project	J6S1718C_DRAFT - ROUTE 100 REHABILITATION
Comparison	Bid Price