

## **ADDENDUM # 2**

Monroe County Bridge Replacement

BRO-B069(46)

Bridge #0760014 1

9/22/2021

Please replace the bid form in your bid packet with the attached Bidding Form. Note the addition of item **216-99.01-Removal of Existing Abutments.**

**Please acknowledge receipt of Addendum #2 in your bid.**

## BIDDING FORM

(work to be completed by contractor only)

MONROE COUNTY BRIDGE REPLACEMENT  
FEDERAL PROJECT BRO-B069(46)  
BRIDGE NO. 0760014 1 OVER LONG BRANCH CREEK  
85' SINGLE SPAN STEEL I-GIRDER BRIDGE  
COUNTY ROAD 819

### ROADWAY

| ITEM NO.   | ITEM  | UNITS | QTY   | UNIT PRICE          | AMOUNT |
|------------|---|-------|-------|---------------------|--------|
| 201-99.01  | CLEARING AND GRUBBING                         | L.S.  | 1     |                     |        |
| 203-55.00  | EMBANKMENT IN PLACE                           | C.Y.  | 3,450 |                     |        |
| 216-99.01  | REMOVAL OF EXISTING ABUTMENTS                 | L.S.. | 1     |                     |        |
| 304-05.04  | TYPE 5 AGGREGATE FOR BASE<br>(4" THICK)       | S.Y.  | 1,345 |                     |        |
| 611-30.20  | FURNISHING TYPE 2 ROCK BLANKET                | C.Y.  | 415   |                     |        |
| 611-30.40  | PLACING TYPE 2 ROCK BLANKET                   | C.Y.  | 415   |                     |        |
| 616-10.05  | CONSTRUCTION SIGNS                            | S.F.  | 45    |                     |        |
| 616-10.30  | TYPE III TEMPORARY BARRICADES                 | EACH  | 2     |                     |        |
| 618-10.00  | MOBILIZATION                                  | L.S.  | 1     |                     |        |
| 624-1.04A  | SEPARATION GEOTEXTILE<br>CONTRACTOR FURNISHED | S.Y.  | 415   |                     |        |
| 627-40.00  | SURVEYING AND STAKING                         | L.S.  | 1     |                     |        |
| 805-20.00A | SEEDING - COOL SEASON<br>MIXTURES             | ACRE  | 1.25  |                     |        |
| 806-10.19  | SILT FENCE                                    | L.F.  | 870   |                     |        |
|            |   |       |       | SUBTOTAL (ROADWAY): |        |

**BRIDGE**

| ITEM NO.  | ITEM  | UNITS | QTY    | UNIT PRICE         | AMOUNT |
|-----------|---|-------|--------|--------------------|--------|
| 203-50.00 | CLASS 1 EXCAVATION                            | C.Y.  | 125    |                    |        |
| 606-10.10 | BRIDGE RAIL (THRIE BEAM)                      | L.F.  | 187.5  |                    |        |
| 606-99.02 | BRIDGE RAIL FLARED END SHOE                   | EACH  | 4      |                    |        |
| 702-10.10 | STRUCTURAL STEEL PILES (10 INCH)              | L.F.  | 176    |                    |        |
| 703-42.01 | CLASS B-1 CONCRETE (4000 psi)                 | C.Y.  | 20     |                    |        |
| 703-42.14 | CLASS B-2 CONCRETE (4000 psi)                 | C.Y.  | 65     |                    |        |
| 705-99.04 | PRE-STRESSED DECK PANEL                       | S.F.  | 1,681  |                    |        |
| 706-10.60 | REINFORCING STEEL (Gr. 60)                    | LB.   | 15,677 |                    |        |
| 712-10.10 | W36x182 STEEL GIRDERS -<br>GRADE 50W (83'-8") | EACH  | 4      |                    |        |
| 716-10.00 | PLAIN NEOPRENE BEARING PADS                   | EACH  | 8      |                    |        |
|           |   |       |        | SUBTOTAL (BRIDGE): |        |
|           |   |       |        | TOTAL:             |        |

---

(PLEASE PRINT OR TYPE BID AMOUNT)

Contractor: \_\_\_\_\_

Representative: \_\_\_\_\_

\_\_\_\_\_  
(please print or type name and title along with signature of the individual that completed this bid)

Phone: \_\_\_\_\_

Address: \_\_\_\_\_

Fax: \_\_\_\_\_