Standard Drawing Guidance (do not show on plans):

- 1) Remove if not required.
- 2) Use the following values for clearance to top longitudinal bars: $3\frac{1}{8}$ " for #5 bars

Effective: Jan. 2022

Supersedes: July 2021


SLABO7_38ft_symm

- 3" for #6 bars
- $2\frac{7}{8}$ " for #7 bars
- $2\frac{3}{4}$ " for #8 bars Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed) (this will be the only asterisk note for CIP decks):
 - *** 3 1/8" (#5) 3" (#6) 2 7/8" (#7) 2 3/4" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- (3) The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown. and will become visible when the larger bars are deleted. (No need to resize)
- 4) The subheadings and negative moment bars are arouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- (5) Place appropriate slab pouring sequence cell and modify as required.
- 6 Use alternate detail for CIP decks:


For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".




SLAB CONSTRUCTION JOINT

7 Remove for CIP deck

Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.





Alternate detail for Type H barrier

DATE PREPARED 11/10/2021

IOB NO

PROJECT NO.

SLAB07

MO

SHEET NO

*

105 WEST CAPIT FERSON CITY, MO 651 MODOT (1-888-275-663

