



Discovering what's possible with calcium

ADVERTISEMENT FOR BIDS

Mississippi Lime will receive Bids for **Bismarck Track Improvements** until **March 7th** at **10:00 a.m.** local prevailing time, at Mississippi Lime Ste Genevieve 16147 US -61 Ste Genevieve, MO Attention: John Moore. at which time and place all bids will be publicly opened and read aloud.

Bids are advertised as follows:

Project Details:

The below pricing is a budgetary estimates for the scope of work as follows:

1. Total 20 track miles with various work locations. All locations for the work to be completed will be marked by owner and contractor of award.
2. Supply and install 650 ties.
3. Supply and install 950 tons of railroad ballast and 30 tons of rip rap.
4. Surface, line, and regulate 5,500TF.
5. Ditching 2,200 linear feet to correct drainage.
6. Clean up all old ties from work and previous work and haul to plant.
7. Brush cut entire length of track 25ft from center of track out both sides.

NOTE(All Materials to be supplied by contractor)

M.P. Locations

- 90.0 - 100 ea. Cross ties, 100 tons of ballast, 500 L.F. of ditching, surface , line and regulate 600 T.F.
- 91.0 - 100 ea. Cross ties, 100 ton of ballast, 500 L.F. of ditching, surface, line and regulate 600 T.F.
- 93.78 East - 300 L.F. of ditching, 40 ea. Cross ties
- 93.78 West – 15 tons of rip, 20 ea. Cross ties, 150 L.F. of ditching
- 94.51 East – 15 ton of rip, 150 L.F. of ditching
- 97.10 - 24 T.F. church crossing replace field and gauge timbers
- 98.50 West – 50 ea. Cross ties, 200 ton of ballast, surface, line and regulate 1,500 T.F.
- 99.10 - 600 L.F. of ditching, 50 ea. Cross ties
- 100.50 - 50 ea. Cross ties, 100 ton of ballast, surface, line and regulate 500 T.F.
- 102.0 East - 30 ea. Cross ties, 80 ton ballast, surface, line and regulate 350 T.F.
- 102.0 West – 50 ea. Cross ties, 100 ton of ballast, surface, line and regulate 500 T.F.
- 102.5 - 50 ea. Cross ties, 50 ton of ballast, surface, line and regulate 250 T.F.
- 104.0 - 50 ea. Cross ties, 100 ton ballast, surface, line and regulate 500 T.F.
- 104.5 - 30 ea. Cross ties, 60 ton of ballast, surface, line and regulate 350 T.F.
- 105.37 - 30 ea. Cross ties, 60 ton of ballast, surface, line and regulate 350 T.F.

Arrangements to survey the track via high rail capable truck can be made by contacting John Moore at 573-366-8922. Bidder to provide high rail truck at bidder expense.

A certified check or bank draft, payable to the order of **Mississippi Lime Company**, negotiable U.S. Government bonds (at par value) or a satisfactory Bid Bond executed by the Bidder and an acceptable surety in an amount equal to five percent (5%) of the total Bid shall be submitted with each Bid.

Attention is called to the fact that no less than the minimum salaries and wages as set forth in the Contract Documents must be paid on this project, and that the Contractor must ensure that employees and applicants for employment are not discriminated against because of their race, color, religion, sex or national origin.

Mississippi Lime Company **reserves** the right to reject any or all Bids or to waive any informality in the bidding.

Bids may be held by Mississippi Lime Company for a period not to exceed 45 days from the date of the opening of Bids for the purpose of reviewing the Bids and investigating the qualifications of Bidders, prior to awarding of the Contract.