From: Debra M. Beckwith

To: BR

**Subject:** Bridge Advertisement (DSI 22-043) Prestressed Girder Steps

**Date:** Monday, February 27, 2023 8:57:05 AM

The EPG & Bridge Standard Drawings have been updated as described below:

## **Implementation Statement:** Effective immediately for details not started.

(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)

<b>Revision Date</b>	Items Revised	Description of Change
<u>Feb. 2023</u>	EPG:	To avoid higher fabrication costs associated with
	<u>751.22; 751.10;</u>	excessively stepped girders the following revisions
	751.40; 751.50	were made along with clarifying and simplifying
	Bridge Standard	haunch reinforcement and haunch limits.
	Drawings:	EPG 751.10.1.14: Simplified guidance for haunch
	<u>PSP</u> 01-05	reinforcement.
	(Prestressed Panels)	EPG 751.22.3.4.1: Revised minimum projection of
	MicroStation Cells:	shear reinforcement into the slab from 2" to 2½"
	NA	(provides ½" variance in the field).
	Std. Specifications:	EPG 751.22.3.6: Clarified haunching limits. Revised
	NA	haunch values for when steps are required to match
	Standard Plans:	the maximum haunch limits. Added a check to see if
	NA	steps are feasible with the maximum change in joint
	Bridge Special	filler thickness between adjacent eight-foot
	Provisions:	prestressed panels. Added maximum allowable total
	NA	increase to the top flange depth.
		Bridge Standard Drawings PSP01-05, EPG
		751.10.2.1, 751.40 & 751.50: Increased the
		maximum change in joint filler thickness between
		adjacent eight-foot prestressed panels along length
		of the beam from ¼" to ½".

to view more details about this (or any) revision,

use the <u>Revision Index Database</u>, located under Completed Revisions on Development's Sharepoint page.

## Instructions:

Under Tables (left-hand side) double-click on RevisionRecords.

Click on the link under the Effective Date to access documentation for the completed revision.

## Debra M. (Debbie) Beckwith

Structural Specialist – Development Section

## **Missouri Department of Transportation**

Central Office – Bridge Division 105 W. Capitol Ave., P.O. Box 270, Jefferson City, MO 65102 573-522-8718 www.modot.org