

**AGENDA**  
**Clark County, U.S. 61**  
**Call 240119-B01 Job No. J2P3062**  
**Virtual Pre-bid Meeting**  
**January 5, 2024**

**I. INTRODUCTIONS**

- A. Please add your name, organization, and title to the chat
- B. The meeting is being recorded

**II. PROJECT OVERVIEW**

- A. Scope of Project: This segment of U.S. 61 floods frequently due to its location near the Des Moines and Mississippi Rivers. Based on a consultant hydraulic study it was determined that raising the U.S. 61 profile grade by approximately 2.5' would greatly reduce the number and duration of closures due to flooding. The closure of this segment of U.S. 61 requires a 41-mile detour.
- B. Contract Time
  - i. Notice to Proceed February 22, 2024 (earlier than standard NTP)
  - ii. Completion Date November 1, 2024
  - iii. Calendar Days N/A
- C. Contract will be administered by Hannibal Project Office, Marty Lincoln R.E.

**III. RIGHT OF WAY STATUS**

- A. Right of way is clear. Temporary construction easements were acquired from two parcels to tie in entrances.

**IV. CONSTRUCTION STAGING**

- A. Tree Clearing: there are several large trees noted in the plans for removal. Per the Tree Clearing Restrictions special provision these trees need to be removed by March 31, 2024.
- B. A 14-day closure period has been provided to install crossroad culverts at three locations. Closure restrictions are included in paragraph 4.2 of the Work Zone Traffic Management special provision. To maintain property access the contractor will not be allowed to work on all three culvert locations concurrently. Liquidated damages and savings will be assessed per the special provision.
- C. Bituminous base was chosen for the fill material to allow U.S. 61 to remain open to traffic during construction. Pavement edge treatment (both centerline and edgeline) and temporary striping shall be installed at the end of each workday to maintain traffic during non-working hours.

**V. UTILITY RELOCATION STATUS**

- A. Utilities are clear
- B. Ameren, Brightspeed, and Clark County Public Water are located within the project limits. No relocations are required, but contractor shall contact utility representatives prior to work as noted in the special provisions.

## **VI. JOB SPECIAL PROVISIONS**

- B. Contract Liquidated Damages: \$1500/day administrative damages
- C. Work Zone Traffic Management: Section 4.2 U.S. 61 closure
- J. Tree Clearing Restrictions: Clearing complete by March 31
- K. Liquidated Damages/Savings Specified: 14-day closure, \$8000 per day damages/incentive. Maximum incentive 4 days (\$32,000)
- L. Wetland in Project Area: Contractor shall mark locations in field

## **VII. CONTRACTOR QUESTIONS**