



### LETTER OF TRANSMITTAL

- DATE: December 4, 2024
- TO: All Prospective Bidders
- **FROM:** Andy Macias, P.E.
- RE: St. Joseph Regional Port Authority Sheet Pile Wall St. Joseph, Missouri MoDOT Project # ARPA23PORTSGRANT141 Addendum No. 2
- **CONTENT:** The following is Addendum No. 2 for the above reference project. **Please complete the confirmation portion from this addendum and fax it back to our office at (816) 364-6086 or scan and email to akatakis@snyder-associates.com** to ensure that you have received the addendum.

CONFIRMATION OF RECEIPT ADDENDUM NO. 2					
This is to confirm that we did receive Addendum No. 2 for the above					
referenced project on this	_day of	_, 2024.			
Company:					
Ву:					



### Addendum No. 2

### St. Joseph Regional Port Authority Sheet Pile Wall St. Joseph, Missouri

All Prospective Bidders:

The contract documents are hereby amended in the following particulars only. All other terms and conditions remain unchanged.

### A. SPECIFICATIONS

1. Replace original Bid Sheets 10 and 11 with revised Bid Sheets 10A and 11A. Alternate wall pricing/S.F. has been added. The owner will evaluate the base bid wall and alternate wall pricing and will choose wall system which achieves the long-term goals of the project.

### **B. PLANS**

- **1.** Remove all references to fenders on Plan Sheets C3.0, C3.1, C3.2, C3.3, and C3.4. No Fenders will be required.
- 2. Sheet pile lift holes may be left in place.
- **3.** Alternate sheet pile wall details are attached. Alternate sheet pile wall with tiebacks will be based on attached details. S.F. pricing to include piling, installation, tiebacks, waler, and other miscellaneous parts as shown in the attached details.
- **4.** Plan Sheet C1.1 Alternate wall pricing/S.F. has been added.

The above interpretations and alterations are hereby made a part of the contract documents and supersede all other addenda or interpretations.

Issued this Forth (4<sup>th</sup>) day of December 2024.

SNYDER & ASSO CIATES

Andy Macias, P.E.

## MoDOT Project #ARPA23PORTSGRANT141

Alterna	ate No. 3					
1	Sheet Pile Wall	SF	7,000	\$	\$	
2	Excavation & Haul Off					
	(River Side)	CY	836	\$	\$	
3	Excavation & Hall Off					
	(Land Side)	CY	686	\$	\$	
4	Type 2 Rock Blanket	SY	783	\$	\$	
5	Geotextile Fabric	SY	783	\$	\$	
6	Erosion Control	LS	1	\$	\$	
Alterna	ate No. 3 in words and figure	es:				
					(\$	)
Alterna	ate No. 4				('	/
1	Sheet Pile Wall	SF	6,790	\$	\$	
2	Excavation & Haul Off					
	(River Side)	CY	1,537	\$	\$	
3	Excavation & Hall Off					
	(Land Side)	CY	17	\$		
4	Type 2 Rock Blanket	SY	-97	\$	\$	
5	Geotextile Fabric	SY	-97	\$	\$	
6	Erosion Control	LS	1	\$	\$	
Alterna	ate No. 4 in words and figure	es:				
					(\$	)
Shoot D	Pile & Associated Work:					
Sheet r	10 Horizontal feet of					
1	sheet pile and associated					
	work	EA			\$	
	work	<b>L</b> / <b>I</b>			Ψ	
SHEET	Г PILE & ASSOCIATED W	ORK	IN WORI	OS AND FIGURES:		
					(\$	)
Alterne	ate Wall & Associated Work	•				
1	Alternate Wall (Includes	•				
1	sheet pile, tiebacks, waler					
	& miscellaneous parts	SF		\$		
	<b>r</b>					

### MoDOT Project #ARPA23PORTSGRANT141

TOTAL BID (BASE BID) in words and figures:		
	(\$	)
TOTAL BID (BASE BID + ALT NO. 1) in words and figures:		
	(\$	)
TOTAL BID (BASE BID + ALT NO. 1 + ALT NO. 2) in words and	figures:	
	(\$	)
TOTAL BID (BASE BID + ALT NO. 1 + ALT NO. 3) in words and	figures:	
	(\$	)
TOTAL BID (BASE BID + ALT NO. 1 + ALT NO. 3 + ALT NO. 4)	) in words and figures	S:
	(\$	)

Alternates will be selected in the numerical order listed. Each alternate may be divided into smaller sections of wall as follows:

Based on the owner's budget any alternate may be subdivided in increments of 10 horizontal feet. The bid alternate for each 10 horizontal feet of sheet pile wall shall include the following: Sheet pile wall, furnished and installed as shown on the plans, excavation, rock blanket and geotextile fabric. The unit cost for "10' additional sheet pile wall" shall include those items listed and any subsidiary work to complete each 10' section of sheet pile wall. This will be considered a deduct for any alternate.

COMPANY:	
SIGNED BY:	

TITLE:

COMPLETE WORK IN ACCORDANCE WITH APWA, CITY OF ST. JOSEPH AND OWNERS SPECIFICATIONS.	DRAINA( FROM PI
	B. THE COI
PROPOSED CONTOURS AND SPOT ELEVATION REPRESENT FINISH GRADE. FINISH GRADE CONSISTS OF TOP OF PAVEMENT,	PROPER
SIDEWALK, OR TOP OF EARTH, DEPENDING ON SITE LOCATION. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE AWAY FROM ALL STRUCTURES UPON THE COMPLETION OF GRADING.	C. PRIOR T OF THE
SITE TOPOGRAPHY TAKEN FROM SURVEY COMPLETED BY SNYDER & ASSOCIATES AND MIDLAND SURVEYING. CONTRACTOR TO VERIFY EXISTING CONDITIONS OF THE SITE THAT MAY NOT BE REPRESENTATIVE OF CONSTRUCTION PLANS.	D. THE COI
EXISTING UTILITIES SHOWN ARE APPROXIMATE LOCATIONS. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE LOCATIONS OF ALL EXISTING UTILITIES PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES, STRUCTURE, FENCES, AND/OR INCIDENTALS NOT DESIGNED FOR REMOVAL SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.	EROSION CON 1. THE STORN DRAWINGS
ANY ADDITIONAL EXCAVATION REQUIRED FOR RE-SHAPING OF ADJACENT AREAS TO PROVIDE FOR DRAINAGE IS CONSIDERED INCIDENTAL.	2. ALL BMP'S RESPONSIE
DO NOT RESTRICT DRAINAGE CHANNELS. PROTECT EXISTING DRAINAGE STRUCTURES UNLESS SPECIFICALLY NOTED OTHERWISE. REPAIR ANY DAMAGE TO PUBLIC OR PRIVATE PROPERTY CAUSED BY CONTRACTOR'S ACTION OR INACTION IN THE HANDLING OF STORM WATER FLOWS DURING CONSTRUCTION.	3. THE SITE N PROJECT S
PROVIDE EROSION CONTROL MEASURES NECESSARY TO PROTECT AGAINST SILTATION, EROSION, AND DUST POLLUTION ON THE PROJECT. COMPLY WITH THE SOIL EROSION CONTROL REQUIREMENTS OF THE MISSOURI DEPARTMENT OF NATURAL RESOURCES AND LOCAL ORDINANCES.	4. THE CONTE NOT LIMITE A. INSTALL
NOTIFY UTILITY COMPANIES PRIOR TO BEGINNING CONSTRUCTION. COORDINATE AND COOPERATE WITH UTILITY COMPANIES TO ALLOW RELOCATIONS DURING THE CONSTRUCTION PERIOD. VERIFY THE ACTUAL LOCATION OF ALL UTILITIES BY EXCAVATING IN ADVANCE OF WORK AT CRITICAL LOCATIONS. PROTECT UTILITIES AND SERVICES DURING CONSTRUCTION.	BERMS, GRADIN B. PRESER DISTURE
PROVIDE TEMPORARY SUPPORT FOR EXISTING UTILITY LINES THAT ARE ENCOUNTERED DURING CONSTRUCTION UNTIL BACKFILLING IS COMPLETED.	C. MAINTAI REPAIRI
IN THE EVENT OF A DISCREPANCY BETWEEN THE QUANTITY ESTIMATES AND THE DETAILED PLANS, THE DETAILED PLANS SHALL GOVERN.	CONTRO
ALL FIELD TILES ENCOUNTERED DURING CONSTRUCTION SHALL BE RECONNECTED AND NOTED ACCORDINGLY ON THE AS-BUILT DOCUMENTS.	EVERY S SWPPP
ADDITIONAL NOTES	E. PREVEN PROPER ANY ACC
A MISSOURI STATE OPERATING PERMIT FOR STORM WATER DISCHARGE IS REQUIRED IF CONSTRUCTION ACTIVITY DISTURBS ONE ACRE OR MORE IN ACCORDANCE WITH THE MISSOURI DEPARTMENT OF NATURAL RESOURCES' REGULATION (10 CSR 20-6.200). COMPLIANCE WITH THE STORMWATER POLLUTION PREVENTION PLAN IS REQUIRED IN THIS INSTANCE. A CONSTRUCTION PERMIT FOR LAND DISTURBANCE WILL BE SECURED FROM THE MISSOURI DEPARTMENT OF NATURAL RESOURCES AND PROVIDED TO THE CONTRACTOR.	F. INSTALL OR RIPR ENSURE SEWERS
SLOPES ARE TO BE LEFT IN A ROUGHENED CONDITION DURING GRADING.	G. COORDI CONTAII
EROSION CONTROL MEASURES SHALL BE CONSTRUCTED PRIOR TO BEGINNING GRADING OPERATIONS WHERE POSSIBLE. ALL REMAINING EROSION CONTROL MEASURES SHALL BE CONSTRUCTED IMMEDIATELY FOLLOWING GRADING OPERATIONS.	MATERI/ CONTRO
CONTRACTOR SHALL INSPECT EROSION CONTROL MEASURES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. ANY REQUIRED REPAIRS SHOULD BE MADE IMMEDIATELY.	K. REMOVE DISCON
ADDITIONAL EROSION CONTROL MEASURES MAY BE NEEDED IF UNFORESEEN EROSION PROBLEMS ARISE OR IF THE SUBMITTED PLAN DOES NOT FUNCTION AS INTENDED.	UTILITY N
A. EROSION PROTECTION	THE EXISTING
1. CODE COMPLIANCE: THE CONTRACTOR SHALL COMPLY WITH SOIL EROSION CONTROL REQUIREMENTS OF THE MISSOURI	CONTRACTOR EXISTING PIPE
CODE, THE MISSOURI DEPARTMENT OF NATURAL RESOURCES NPDES PERMIT, AND LOCAL ORDINANCE. THE CONTRACTOR SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT	-
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE</li> </ul>	THE UTILITIES MAKES NO GU EITHER IN SEF FEATURES SH
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY,</li> </ul>	UTILITY M THE UTILITIES MAKES NO GU EITHER IN SEF
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS</li> </ul>	UTILITY V THE UTILITIES MAKES NO GU EITHER IN SEF FEATURES SH THE CONTRAC OTHER LINES PRIOR TO THE
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS AND THESE STANDARDS.</li> <li>B.</li> </ul>	UTILITY V THE UTILITIES MAKES NO GU EITHER IN SEF FEATURES SH THE CONTRAC OTHER LINES PRIOR TO THE SURVEY I
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS AND THESE STANDARDS.</li> <li>B.</li> <li>STORM WATER DISCHARGE PERMIT:</li> <li>1. THIS PROJECT REQUIRES A LAND DISTURBANCE PERMIT FROM THE CITY OF ST. JOSEPH. THE OWNER SHALL OBTAIN THE PERMIT. THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL BE RESPONSIBLE FOR COMPLIANCE AND FULFILLING ALL REQUIREMENTS OF THE PERMIT INCLUDING THE STORM WATER POLLUTION PREVENTION PLAN.</li> <li>2. ALL DOCUMENTS RELATED TO THE STORM WATER DISCHARGE PERMIT SHALL BE KEPT ON SITE AT ALL TIMES AND MUST BE PRESENTED TO THE JURISDICTION UPON REQUEST WHICH INCLUDE THE NOTICE OF INTENT, PROOF OF PUBLICATION, POLLUTION PREVENTION PLAN, PROJECT INSPECTION DIARY, AND OTHER ITEMS. FAILURE TO COMPLY WITH THE DISCHARGE</li> </ul>	UTILITY M THE UTILITIES MAKES NO GU EITHER IN SEF FEATURES SH THE CONTRAC OTHER LINES PRIOR TO THE SURVEY I
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS AND THESE STANDARDS.</li> <li>B.</li> <li>STORM WATER DISCHARGE PERMIT:</li> <li>1. THIS PROJECT REQUIRES A LAND DISTURBANCE PERMIT FROM THE CITY OF ST. JOSEPH. THE OWNER SHALL OBTAIN THE PERMIT. THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL BE RESPONSIBLE FOR COMPLIANCE AND FULFILLING ALL REQUIREMENTS OF THE PERMIT INCLUDING THE STORM WATER POLLUTION PREVENTION PLAN.</li> <li>2. ALL DOCUMENTS RELATED TO THE STORM WATER DISCHARGE PERMIT SHALL BE KEPT ON SITE AT ALL TIMES AND MUST BE PRESENTED TO THE JURISDICTION UPON REQUEST WHICH INCLUDE THE NOTICE OF INTENT, PROOF OF PUBLICATION, POLLUTION PREVENTION PLAN, PROJECT INSPECTION DIARY, AND OTHER ITEMS. FAILURE TO COMPLY WITH THE DISCHARGE REQUIREMENTS IS IN VIOLATION OF THE CLEAN WATER ACT AND THE CODE OF MISSOURI.</li> <li>3. UPON FINAL STABILIZATION OF THE DISTURBED AREA, A "NOTICE OF DISCONTINUATION" MUST BE FILED BY THE OWNER WITH THE JUSRISDICTION. ALL PLANS, INSPECTION REPORTS, AND OTHER DOCUMENTS MUST BE RETAINED FOR A PERIOD OF</li> </ul>	UTILITY V THE UTILITIES MAKES NO GL EITHER IN SEF FEATURES SH THE CONTRAC OTHER LINES PRIOR TO THE SURVEY I 1. BUILDING PROPOSE 2. FOR CLAF DIGITAL C 3. FOR THE A STRAIG
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS AND THESE STANDARDS.</li> <li>B. STORM WATER DISCHARGE PERMIT:</li> <li>1. THIS PROJECT REQUIRES A LAND DISTURBANCE PERMIT FROM THE CITY OF ST. JOSEPH. THE OWNER SHALL OBTAIN THE PERMIT. THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL BE RESPONSIBLE FOR COMPLIANCE AND FULFILLING ALL REQUIREMENTS OF THE PERMIT INCLUDING THE STORM WATER POLLUTION PREVENTION PLAN.</li> <li>2. ALL DOCUMENTS RELATED TO THE STORM WATER DISCHARGE PERMIT SHALL BE KEPT ON SITE AT ALL TIMES AND MUST BE PRESENTED TO THE JURISDICTION UPON REQUEST WHICH INCLUDE THE NOTICE OF INTENT, PROOF OF PUBLICATION, POLLUTION PREVENTION PLAN, PROJECT INSPECTION DIARY, AND OTHER TEMS. FAILURE TO COMPLY WITH THE DISCHARGE REQUIREMENTS IS IN VIOLATION OF THE CLEAN WATER ACT AND THE CODE OF MISSOURI.</li> <li>3. UPON FINAL STABILIZATION OF THE DISTURBED AREA, A "NOTICE OF DISCONTINUATION" MUST BE FILED BY THE OWNER WITH THE JUSRISDICTION. ALL PLANS, INSPECTION REPORTS, AND OTHER DOCUMENTS MUST BE FILED BY THE OWNER WITH THE JUSRISDICTION. ALL PLANS, INSPECTION REPORTS, AND OTHER DOCUMENTS MUST BE RETAINED FOR A PERIOD OF THREE YEARS AFTER PROJECT COMPLETION. THE CONTRACTOR SHALL RETAIN RECORD COPY AND PROVIDE ORIGINA</li></ul>	UTILITY V THE UTILITIES MAKES NO GU EITHER IN SEF FEATURES SF THE CONTRAC OTHER LINES PRIOR TO THE SURVEY I 1. BUILDING BUILDING PROPOSE 2. FOR CLAF DIGITAL C 3. FOR THE A STRAIG 4. UTILITY S AND/OR S
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS AND THESE STANDARDS.</li> <li>B.</li> <li>STORM WATER DISCHARGE PERMIT:</li> <li>1. THIS PROJECT REQUIRES A LAND DISTURBANCE PERMIT FROM THE CITY OF ST. JOSEPH. THE OWNER SHALL OBTAIN THE PERMIT. THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL BE RESPONSIBLE FOR COMPLIANCE AND FULFILLING ALL REQUIREMENTS OF THE PERMIT INCLUDING THE STORM WATER POLLUTION PREVENTION PLAN.</li> <li>2. ALL DOCUMENTS RELATED TO THE STORM WATER DISCHARGE PERMIT SHALL BE KEPT ON SITE AT ALL TIMES AND MUST BE PRESENTED TO THE JURISDICTION UPON REQUEST WHICH INCLUDE THE NOT LEC OF INTENT, PROOF OF PUBLICATION, POLLUTION PREVENTION PLAN, PROJECT INSPECTION DIARY, AND OTHER ITEMS. FAILURE TO COMPLY WITH THE DISCHARGE REQUIREMENTS IS IN VIOLATION OF THE DISTURBED AREA, A "NOTICE OF DISCONTINUATION" MUST BE FILMED FOR A PERIOD OF THREE YEARS AFTER PROJECT COMPLETION. THE CONTRACTOR SHALL BETAIN DECORD COPY AND PROVIDE ORIGINAL DOCUMENTS TO THE OWNER UPON ISSUANCE OF THE NOTICE OF DISCONTINUATION.</li> <li>POLLUTION PREVENTION PLAN:</li> <li>1. SITE DESCRIPTION: THIS PROJECT IS FOR THE CONSTRUCTION OF ROUGH GRADING FOR COMMERCIAL DEVELOPMENT. THE</li> </ul>	UTILITY V THE UTILITIES MAKES NO GL EITHER IN SEF FEATURES SH THE CONTRAC OTHER LINES PRIOR TO THE SURVEY I 1. BUILDING PROPOSE 2. FOR CLAF DIGITAL C 3. FOR THE A STRAIG 4. UTILITY S AND/OR S SERVICES 5. BOUNDAF CREATION
<ul> <li>SHALİ TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOEVER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER. FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS AND THESE STANDARDS.</li> <li>B. STORM WATER DISCHARGE PERMIT:</li> <li>1. THIS PROJECT REQUIRES A LAND DISTURBANCE PERMIT FROM THE CITY OF ST. JOSEPH. THE OWNER SHALL OBTAIN THE PERMIT. THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL BE RESPONSIBLE FOR COMPLIANCE AND FULFILLING ALL REQUIREMENTS OF THE PERMIT INCLUDING THE STORM WATER POLLUTION PREVENTION PLAN.</li> <li>2. ALL DOCUMENTS RELATED TO THE STORM WATER DISCHARGE PERMIT SHALL BE KEPT ON SITE AT ALL TIMES AND MUST BE PRESENTED TO THE JURISDICTION UPON REQUEST WHICH INCLUDE THE NOTICE OF INTEXT, PROOF OP PUBLICATION, POLLUTION PREVENTION PLAN, PROJECT INSPECTION DIARY, AND OTHER NELS FAILURE TO COMPLY WITH THE DISCHARGE REQUIREMENTS IS IN VIOLATION OF THE CLEAN WATER ACT AND THE CODE OF MISSIOURI.</li> <li>3. UPON FINAL STABILIZATION OF THE CLEAN WATER ACT AND THE CODE OF INTEXT, PROOF OP PUBLICATION, POLLUTION PREVENTION PLAN, INSPECTION REPORTS, AND OTHER TOCHNINUATION' MUST BE FILED BY THE OWNER WITH THE JUSRISDICTION. ALL PLANS, INSPECTION REPORTS, AND OTHER CODE OF DISCONTINUATION MUST BE FILED BY THE OWNER WITH THE JUSRISDICTION PLAN:</li> <li>3. UPON FINAL STABILIZATION OF THE DISTURBED AREA, A "NOTICE OF D</li></ul>	UTILITY M THE UTILITIES MAKES NO GU EITHER IN SEP FEATURES SH THE CONTRAC OTHER LINES PRIOR TO THE SURVEY I 1. BUILDING BUILDING PROPOSE 2. FOR CLAF DIGITAL C 3. FOR THE A STRAIG 4. UTILITY S AND/OR S SERVICES 5. BOUNDAF
<ul> <li>SHALL TAKE ALL NECESSARY MEASUREMENTS TO PROTECT AGAINST EROSION AND DUST POLLUTION ON THIS PROJECT SITE AND ALL OFF-SITE BORROW OR DEPOSIT AREAS DURING PERFORMANCE OR AS A RESULT OF PERFORMANCE.</li> <li>2. DAMAGE CLAIMS: THE CONTRACTOR WILL HOLD THE OWNER, ARCHITECT AND ENGINEER HARMLESS FROM ANY AND ALL CLAIMS OF ANY TYPE WHATSOCYER RESULTING FROM DAMAGES TO ADJOINING PUBLIC OR PRIVATE PROPERTY, INCLUDING REASONABLE ATTORNEY FEES INCURRED TO OWNER, FURTHER, IF THE CONTRACTOR FAILS TO TAKE NECESSARY STEPS TO PROMPTLY REMOVE EARTH SEDIMENTATION OR DEBRIS WHICH COMES ONTO ADJOINING PUBLIC OR PRIVATE PROPERTY, THE OWNER MAY, BUT NEED NOT, REMOVE SUCH ITEMS AND DEDUCT THE COST THEREOF FROM AMOUNTS DUE TO THE CONTRACTOR.</li> <li>3. ALL AREAS DISTURBED BY CONSTRUCTION ON THIS PROJECT WILL BE SUBJECT TO CURRENT REGULATORY REQUIREMENTS AND THESE STANDARDS.</li> <li>B.</li> <li>STORM WATER DISCHARGE PERMIT:</li> <li>1. THIS PROJECT REQUIRES A LAND DISTURBANCE PERMIT FROM THE CITY OF ST. JOSEPH. THE OWNER SHALL OBTAIN THE PERMIT. THE GENERAL CONTRACTOR AND ALL SUBCONTRACTORS SHALL BE RESPONSIBLE FOR COMPLIANCE AND FULFILLING ALL REQUIREMENTS OF THE PERMIT INCLUDING THE STORM WATER POLLUTION PREVENTION PLAN.</li> <li>2. ALL DOCUMENTS RELATED TO THE STORM WATER DISCHARGE PERMIT SHALL BE KEPT ON SITE AT ALL TIMES AND MUST BE PRESENTED TO THE JURISDICTION UPON REQUEST WHICH INCLUDE THE NOTICE OF INTENT, PROOF OF PUBLICATION, POLLUTION PREVENTION PLAN, PROJECT INSPECTION DLARY, AND OTHER ITEMS. FAILURE TO COMPLY WITH THE DISCHARGE REQUIREMENTS IS IN VIOLATION OF THE CLEAN WATER ACT AND THE CODE OF MISSOURI.</li> <li>3. UPON FINAL STABILIZATION OF THE DISTURBED AREA, A "NOTICE OF DISCONTINUATION" MUST BE FILED BY THE OWNER WITH THE JUSNISDICTION. PLAN, INSPECTION REPORTS, AND OTHER TOCUMENTS MUST BE RETAINED FOR A PERIOD OF THREE YEARS AFTER PROJECT IS FOR THE CONSTRUCTION OF ROUGH GRADING FOR COMMERCIAL DEVELOPMENT. THE ENTIRE PROJECT SHE AND WILL BE ONTED OF THE NOTICE OF DISCONTINUATION.</li> <li>POLLUTION PREVE</li></ul>	UTILITY M THE UTILITIES MAKES NO GU EITHER IN SEP FEATURES SH THE CONTRAC OTHER LINES PRIOR TO THE SURVEY I 1. BUILDING BUILDING PROPOSE 2. FOR CLAF DIGITAL C 3. FOR THE A STRAIG 4. UTILITY S AND/OR S SERVICES 5. BOUNDAF

CONTRACTOR SHALL PROTECT ADJOINING PROPERTY INCLUDING PUBLIC UTILITIES, SANITARY AND STORM NAGE SYSTEMS, AND STREETS FROM ANY DAMAGE RESULTING FROM MOVEMENT OF EARTH OR OTHER DEBRIS I PROJECT SITE. REPAIR ANY DAMAGE IMMEDIATELY AT NO ADDITIONAL COST.

CONTRACTOR SHALL PREVENT ACCUMULATION OF EARTH, SILTATION, OR DEBRIS ON ADJOINING PUBLIC OR PRIVATE ERTY FROM PROJECT SITE. REMOVE ANY ACCUMULATION OF EARTH OR DEBRIS IMMEDIATELY AND TAKE REMEDIAL ONS FOR PREVENTION.

R TO SITE CLEARING AND GRADING OPERATIONS, CONTRACTOR SHALL INSTALL SILT FENCE ALONG THE PERIMETER IE PROJECT DOWNSTREAM OF DISTURBING ACTIVITIES AS REQUIRED AND AS SHOWN ON THE PLANS.

CONTRACTOR SHALL PRESERVE EXISTING VEGETATION IN AREAS NOT NEEDED FOR CONSTRUCTION.

ONTROL & POLLUTION PREVENTION PLAN - GENERAL NOTES

RM WATER POLLUTION PREVENTION PLAN (SWPPP) IS A SEPARATE DOCUMENT IN ADDITION TO THESE PLAN

'S AND EROSION CONTROL MEASURES REQUIRED AS A RESULT OF CONSTRUCTION ACTIVITIES ARE THE SIBILITY OF THE CONTRACTOR TO IDENTIFY, NOTE AND IMPLEMENT.

E MAP SHOULD BE EXPEDITIOUSLY REVISED TO REFLECT CONSTRUCTION PROGRESS AND CHANGES AT THE T SITE.

ITRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH ALL REQUIREMENTS OF THE GENERAL PERMIT, INCLUDING, BUT ITED TO, THE FOLLOWING BMP'S UNLESS INFEASIBLE OR NOT APPLICABLE:

LL PERIMETER AND FINAL SEDIMENT CONTROL MEASURES SUCH AS SILT BARRIERS, DITCH CHECKS, DIVERSION IS, OR SEDIMENTATION BASINS DOWNSTREAM OF SOIL DISTURBING ACTIVITIES PRIOR TO SITE CLEARING AND ING OPERATIONS.

ERVE EXISTING VEGETATION IN AREAS NOT NEEDED FOR CONSTRUCTION AND LIMIT TO A MINIMUM THE TOTAL AREA IRBED BY CONSTRUCTION OPERATIONS AT ANY TIME.

FAIN ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES IN WORKING ORDER, INCLUDING CLEANING, IRING, REPLACEMENT, AND SEDIMENT REMOVAL THROUGHOUT THE PERMIT PERIOD. CLEAN OR REPLACE SILT ROL DEVICES WHEN THE MEASURES HAVE LOST 50% OF THEIR ORIGINAL CAPACITY.

ECT THE PROJECT AREA AND CONTROL DEVICES (BY QUALIFIED PERSONNEL ASSIGNED BY THE CONTRACTOR) Y SEVEN CALENDAR DAYS. RECORD THE FINDING OF THESE INSPECTIONS AND ANY RESULTING ACTIONS IN THE PP WITH A COPY SUBMITTED WEEKLY TO THE OWNER OR ENGINEER DURING CONSTRUCTION.

ENT ACCUMULATION OF EARTH AND DEBRIS FROM CONSTRUCTION ACTIVITIES ON ADJOINING PUBLIC OR PRIVATE ERTIES, INCLUDING STREETS, DRIVEWAYS, SIDEWALKS, DRAINAGEWAYS, OR UNDERGROUND SEWERS. REMOVE ACCUMULATION OF EARTH OR DEBRIS IMMEDIATELY AND TAKE REMEDIAL ACTIONS FOR FUTURE PREVENTION.

LL NECESSARY CONTROL MEASURES SUCH AS SILT BARRIERS, EROSION CONTROL MATS, MULCH, DITCH CHECKS PRAP AS SOON AS AREAS REACH THEIR FINAL GRADES AND AS CONSTRUCTION OPERATIONS PROGRESS TO RE CONTINUOUS RUNOFF CONTROL. PROVIDE INLET AND OUTLET CONTROL MEASURES AS SOON AS STORM RS ARE INSTALLED.

RDINATE LOCATIONS OF STAGING AREAS WITH THE OWNER. UNLESS NOTED OTHERWISE, STAGING AREAS SHOULD AIN THE FOLLOWING: JOB TRAILERS, FUELING / VEHICLE MAINTENANCE AREA, TEMPORARY SANITARY FACILITIES, RIALS STORAGE, AND CONCRETE WASHOUT FACILITY. BARRIERS AND DIRECT TO A SEDIMENT BASIN OR OTHER ROL DEVICE WHERE POSSIBLE. CONCRETE WASHOUT MUST BE CONTAINED ONSITE.

VE ALL TEMPORARY EROSION CONTROL MEASURES AND SITE WASTE PRIOR TO FILING OF THE "NOTICE OF ONTINUATION".

## NOTES

NG UTILITIES SHOWN ON THESE PLANS ARE IN THEIR APPROXIMATE LOCATION ONLY. AND ARE BASED ON AVAILABLE ON FOR THIS SITE. CONTRACTOR TO VERIFY THE EXACT LOCATION OF ALL UTILITIES BY CALLING A UTILITY LOCATOR. OR MAY ALSO NEED TO POTHOLE OR USE OTHER METHODS AS NECESSARY TO LOCATE UTILITIES AND TO DETERMINE IPE SIZES. CONTRACTOR TO FOLLOW ALL LAWS AND REGULATIONS WHEN INSTALLING UNDERGROUND UTILITIES.

## WARNING

ES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND/OR RECORDS OBTAINED. THE SURVEYOR GUARANTEE THAT THE UTILITIES OR SUBSURFACE FEATURES SHOWN COMPRISE ALL SUCH ITEMS IN THE AREA. SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UTILITIES OR SUBSURFACE SHOWN ARE IN THE EXACT LOCATION INDICATED EXCEPT WHERE NOTED AS QUALITY LEVEL A.

ACTOR IS REQUIRED TO TAKE DUE PRECAUTIONARY MEASURES TO PROTECT THE UTILITY LINES SHOWN, [AND ALL ES NOT OF RECORD OR NOT SHOWN ON THESE DRAWINGS] BY VERIFICATION OF THEIR LOCATION IN THE FIELD HE INITIATION OF THE ACTUAL PORTION OF THEIR WORK.

# **NOTES**

NG LINES AND CORNERS ARE FOR USE IN PREPARING CIVIL SITE PLAN DOCUMENTS. BUILDING CORNERS AND NG LINES SHOULD BE SPECIFICALLY VERIFIED, AS NECESSARY, PRIOR TO DESIGN FOR CONSTRUCTION OF ANY SED EXPANSION OR CONNECTION OF BUILDING COMPONENTS.

ARITY PURPOSES, SURVEY SPOT ELEVATIONS ARE NOT SHOWN ON THIS SURVEY, BUT ARE CONTAINED WITHIN THE L CADD FILES.

IE PURPOSE OF THIS SURVEY, STORM SEWER, SANITARY SEWER AND WATER MAIN LINES ARE ASSUMED TO FOLLOW AIGHT LINE FROM STRUCTURE TO STRUCTURE.

SERVICE LINES TO BUILDINGS ARE APPROXIMATE ONLY. AN INTERNAL BUILDING INVESTIGATION, EXCAVATION R SUBSURFACE LOCATING/DESIGNATING WOULD NEED TO BE PERFORMED TO DETERMINE THE LOCATION OF ES ENTERING THE BUILDING.

ARY LINES SHOWN ON THE EXISTING SITE SURVEY ARE TO FACILITATE DESIGN OR CONCEPT NEEDS AND ENABLE ION OF SAID CONSTRUCTION DOCUMENTS. THESE LINES DO NOT CONSTITUTE A CERTIFIED BOUNDARY SURVEY AND G MONUMENTS WILL NOT BE SET.

	ESTIMATED QUANTITIES -	(BASE BID	)
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	MOBILIZATION	LS	1
2	SHEET PILE WALL	SF	14,000
3	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,728
4	EXCAVATION & HAUL OFF (LAND SIDE)	CY	703
5	TYPE 2 ROCK BLANKET	SY	631
6	GEOTEXTILE FABRIC	SY	631
7	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES	6 - (ALT-1)	
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	SHEET PILE WALL	SF	4,970
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	565
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	74
4	TYPE 2 ROCK BLANKET	SY	205
5	GEOTEXTILE FABRIC	SY	205
6	EROSION CONTROL	LS	1
ITEM NO. 1 2	EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET	UNIT CY SY	QTY. 1,024 866
3	GEOTEXTILE FABRIC	SY	866
4	EROSION CONTROL	LS	1
ITEM NO.	DESCRIPTION SHEET PILE WALL	UNIT	QTY. 7,000
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	836
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	686
4	TYPE 2 ROCK BLANKET	SY	783
5	GEOTEXTILE FABRIC	SY	783
	EROSION CONTROL	LS	1
6		II	
6	ESTIMATED QUANTITIES	S - (ALT-4)	
	ESTIMATED QUANTITIES	5 - (ALT-4)	QTY.
	1		QTY. 6,790
ITEM NO.	DESCRIPTION	UNIT	
ITEM NO. 1	DESCRIPTION SHEET PILE WALL	UNIT SF	6,790
ITEM NO. 1 2	DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE)	UNIT SF CY	6,790 1,537
ITEM NO. 1 2 3	DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE)	UNIT SF CY CY	6,790 1,537 17

	ESTIMATED QUANTITIES -	- (BASE BID	))
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	MOBILIZATION	LS	1
2	SHEET PILE WALL	SF	14,000
3	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,728
4	EXCAVATION & HAUL OFF (LAND SIDE)	CY	703
5	TYPE 2 ROCK BLANKET	SY	631
6	GEOTEXTILE FABRIC	SY	631
7	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES		
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	SHEET PILE WALL	SF	4,970
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	565
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	74
4	TYPE 2 ROCK BLANKET	SY	205
5	GEOTEXTILE FABRIC	SY	205
6	EROSION CONTROL	LS	1
ITEM NO.	ESTIMATED QUANTITIES	S - (ALT-2)	QTY.
1	EXCAVATION & HAUL OFF (LAND SIDE)	CY	1,024
2	TYPE 2 ROCK BLANKET	SY	866
3	GEOTEXTILE FABRIC	SY	866
4	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES	ς _ (ΔΙ Τ_3)	
		UNIT	QTY.
11EM NO.	SHEET PILE WALL	SF	7,000
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	836
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	686
4	TYPE 2 ROCK BLANKET	SY	783
5	GEOTEXTILE FABRIC	SY	783
6	EROSION CONTROL	LS	1
			· ·
	ESTIMATED QUANTITIES	S - (ALT-4)	
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	SHEET PILE WALL	SF	6,790
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,537
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	17
	•		
4	TYPE 2 ROCK BLANKET	SY	-97
	TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC	SY SY	-97 -97

	ESTIMATED QUANTITIES -	- (BASE BID	)
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	MOBILIZATION	LS	1
2	SHEET PILE WALL	SF	14,000
3	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,728
4	EXCAVATION & HAUL OFF (LAND SIDE)	CY	703
5	TYPE 2 ROCK BLANKET	SY	631
6	GEOTEXTILE FABRIC	SY	631
7	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES	S - (ALT-1)	
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	SHEET PILE WALL	SF	4,970
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	565
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	74
4	TYPE 2 ROCK BLANKET	SY	205
5	GEOTEXTILE FABRIC	SY	205
6	EROSION CONTROL	LS	1
ITEM NO.	ESTIMATED QUANTITIES	S - (ALT-2)	QTY.
1	EXCAVATION & HAUL OFF (LAND SIDE)	CY	1,024
2	TYPE 2 ROCK BLANKET	SY	866
3	GEOTEXTILE FABRIC	SY	866
4	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES		
ITEM NO.		UNIT	QTY.
1	SHEET PILE WALL	SF	7,000
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	836
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	686
4	TYPE 2 ROCK BLANKET	SY	783
5	GEOTEXTILE FABRIC	SY	783
6	EROSION CONTROL	LS	1
0			
	ESTIMATED QUANTITIES	S - (ALT-4)	
	DESCRIPTION	UNIT	QTY.
ITEM NO.		SF	6,790
ITEM NO. 1	SHEET PILE WALL		
	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,537
1		CY CY	1,537 17
1 2	EXCAVATION & HAUL OFF (RIVER SIDE)		
1 2 3	EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE)	CY	17

	<b>ESTIMATED QUANTITIES -</b>	(BASE BID	))
ITEM NO.	DESCRIPTION		QTY.
1	MOBILIZATION	LS	1
2	SHEET PILE WALL	SF	14,000
3	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,728
4	EXCAVATION & HAUL OFF (LAND SIDE)	CY	703
5	TYPE 2 ROCK BLANKET	SY	631
6	GEOTEXTILE FABRIC	SY	631
7	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES	6 - (ALT-1)	
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	SHEET PILE WALL	SF	4,970
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	565
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	74
4	TYPE 2 ROCK BLANKET	SY	205
5	GEOTEXTILE FABRIC	SY	205
6	EROSION CONTROL	LS	1
ITEM NO.	ESTIMATED QUANTITIES	5 - (ALT-2)	QTY.
1	EXCAVATION & HAUL OFF (LAND SIDE)	CY	1,024
2	TYPE 2 ROCK BLANKET	SY	866
3	GEOTEXTILE FABRIC	SY	866
4	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES		
	1		
ITEM NO. 1	DESCRIPTION SHEET PILE WALL	UNIT	QTY. 7,000
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	836
2	EXCAVATION & HAUL OFF (LAND SIDE)	CY	686
3 4	TYPE 2 ROCK BLANKET	SY	783
 5	GEOTEXTILE FABRIC	SY	783
5 6	EROSION CONTROL	LS	1
0		L0	
	ESTIMATED QUANTITIES	6 - (ALT-4)	
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	SHEET PILE WALL	SF	6,790
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,537
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	17
4	TYPE 2 ROCK BLANKET	SY	-97
		SY	-97
5	GEOTEXTILE FABRIC	51	-97

	ESTIMATED QUANTITIES -	(BASE BID	))
ITEM NO.	DESCRIPTION	UNIT	QTY.
1	MOBILIZATION	LS	1
2	SHEET PILE WALL	SF	14,000
3	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	1,728
4	EXCAVATION & HAUL OFF (LAND SIDE)	CY	703
5	TYPE 2 ROCK BLANKET	SY	631
6	GEOTEXTILE FABRIC	SY	631
7	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES	S - (ALT-1)	
ITEM NO.	1		QTY.
1	SHEET PILE WALL	SF	4,970
2	EXCAVATION & HAUL OFF (RIVER SIDE)	CY	565
3	EXCAVATION & HAUL OFF (LAND SIDE)	CY	74
4	TYPE 2 ROCK BLANKET	SY	205
5	GEOTEXTILE FABRIC	SY	205
6	EROSION CONTROL	LS	1
	ESTIMATED QUANTITIES	S - (ALT-2)	
ITEM NO.			QTY.
1	EXCAVATION & HAUL OFF (LAND SIDE)	CY	1,024
2	TYPE 2 ROCK BLANKET	SY	866
3	GEOTEXTILE FABRIC	SY	866
	EROSION CONTROL	51	000
4		LS	1
4			1
	ESTIMATED QUANTITIES		
	ESTIMATED QUANTITIES	6 - (ALT-3)	QTY.
ITEM NO.	ESTIMATED QUANTITIES	6 - (ALT-3)	QTY.
ITEM NO. 1	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL	5 - (ALT-3)	QTY. 7,000
ITEM NO. 1 2	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE)	S - (ALT-3) UNIT SF CY	QTY. 7,000 836
ITEM NO. 1 2 3	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE)	S - (ALT-3) UNIT SF CY CY	QTY. 7,000 836 686
ITEM NO. 1 2 3 4	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET	S - (ALT-3) UNIT SF CY CY CY SY	QTY. 7,000 836 686 783
ITEM NO. 1 2 3 4 5	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC EROSION CONTROL	S - (ALT-3) UNIT SF CY CY CY SY SY LS	QTY. 7,000 836 686 783 783
ITEM NO. 1 2 3 4 5 6	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC EROSION CONTROL ESTIMATED QUANTITIES	S - (ALT-3) UNIT SF CY CY CY SY SY LS S - (ALT-4)	QTY. 7,000 836 686 783 783 1
ITEM NO. 1 2 3 4 5 6 1 1 EM NO.	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC EROSION CONTROL ESTIMATED QUANTITIES DESCRIPTION	S - (ALT-3) UNIT SF CY CY CY SY SY LS S - (ALT-4) UNIT	QTY. 7,000 836 686 783 783 1 1 QTY.
ITEM NO. 1 2 3 4 5 6 ITEM NO. 1	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC EROSION CONTROL ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL	S - (ALT-3) UNIT SF CY CY CY SY SY LS S - (ALT-4) UNIT SF	QTY. 7,000 836 686 783 783 1 1 QTY. 6,790
ITEM NO. 1 2 3 4 5 6 ITEM NO. 1 2	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC EROSION CONTROL  ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE)	S - (ALT-3) UNIT SF CY CY CY SY SY LS S- (ALT-4) UNIT SF CY	QTY. 7,000 836 686 783 783 1 1 QTY. 6,790 1,537
ITEM NO. 1 2 3 4 5 6 ITEM NO. 1 2 3	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC EROSION CONTROL  ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE)	S - (ALT-3) UNIT SF CY CY CY SY LS S- (ALT-4) UNIT SF CY CY	QTY. 7,000 836 686 783 783 1 1 QTY. 6,790 1,537 17
ITEM NO. 1 2 3 4 5 6 1 ITEM NO. 1 2	ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE) EXCAVATION & HAUL OFF (LAND SIDE) TYPE 2 ROCK BLANKET GEOTEXTILE FABRIC EROSION CONTROL  ESTIMATED QUANTITIES DESCRIPTION SHEET PILE WALL EXCAVATION & HAUL OFF (RIVER SIDE)	S - (ALT-3) UNIT SF CY CY CY SY SY LS S- (ALT-4) UNIT SF CY	QTY. 7,000 836 686 783 783 1 1 QTY. 6,790 1,537

### NOTES:

1) IF ALTERNATE-3 IS CHOSEN, ALTERNATE-2 QUANTITIES AND ASSOCIATED COSTS WILL BE NOT BE INCLUDED. 2) IF ALTERNATE-4 IS CHOSEN, THE EXCAVATION AND ROCK BLANKET WORK BEYOND ALTERNATE-3 SHEET PILE WALL WILL BE DELETED FROM THE RESPECTIVE ALTERNATE-4 QUANTITIES.


ALTERNATE WALL COST INCLUDING TIEBACKS AND WATER COST / SQ FT:

# LEGEND: EXISTING FEATURES

FOUND MONUMENT CONTROL POINT	● ⊙CP
LAND CONTOUR ELEVATION	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
OVERHEAD ELECTRIC UNDERGROUND GAS STORM SEWER LINE UNDERGROUND TELECOM METAL FENCE UTILITY POLE SANITARY MANHOLE WATER VALVE ELECTRICAL BOX ELECTRICAL HANDHOLE FIBER OPTIC MANHOLE	— OE
CONCRETE	▽ ◁  ▽

4


CONC



TYPICAL HELICAL PILE DETAIL (N.T.S.)

- 7. SEE SHEET C5.3 FOR TIEBACK ANCHOR DETAILS.
- 6. A FACTOR OF SAFETY OF 2.0 SHALL BE APPLIED TO THESE LOADS.
- 5. SUPPORT LINE 2 TO BE DESIGNED FOR 12.2 KIP/FT.
- 4. SUPPORT LINE 1 TO BE DESIGNED FOR 4.7 KIP/FT.
- 3. TIEBACK LENGTH L, AND ROTATION O TO BE DETERMINED BY MICRO PILE DESIGNER. TIEBACKS BE DESIGNED BASED ON THE LOADS PROVIDED.
- BE DESIGNED BY A MISSOURI REGISTERED ENGINEER BASED ON THE LOADS PROVIDED.
- 1. MINIMUM SHEET SECTION MODULUS = 24 CUBIC INCHES PER FT (PZC 13).

NOTES:



# HELICAL PILE GENERAL NOTES

GENERAL:

- 1. THE CONTRACTOR SHALL VERIFY ALL EXISTING DIMENSIONS PRIOR TO COMMENCING FABRICATION OR CONSTRUCTION.
- 2. ALL OF THE WORK TO BE DONE UNDER THIS CONTRACT SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE DRAWINGS, THE GENERAL REQUIREMENTS OF DIVISION ONE, THE GENERAL CONDITIONS, THE SPECIFICATIONS, AND ANY ADDENDA THERETO.
- 3. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ACQUAINT THEMSELVES AND ALL SUPERVISORY PERSONNEL WITH THE ABOVE-NAMED DRAWINGS AND DOCUMENTS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSPECTING THE SITE OF THE PROPOSED WORK TO SATISFY
- THEMSELVES AS TO THE EXISTING CONDITIONS RELATIVE TO THE CONTRACT. 5. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING ALL TEMPORARY SHORING/BRACING, AS REQUIRED BY ALL
- FEDERAL, STATE AND LOCAL AGENCIES HAVING JURISDICTION, UNTIL ALL PERMANENT FRAMING IS INSTALLED. 6. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING
- IMMEDIATELY NOTIFIED. THE CONTRACTOR SHALL BE FULLY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT BE OCCASIONED BY THEIR FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES. 7. ALL CONSTRUCTION SHALL CONFORM TO INTERNATIONAL BUILDING CODE 2018 UNLESS NOTED OTHERWISE.

# DESIGN LOADS:

LIVE LOAD STAIRS: 40 PSF

- LIVE LOAD PLATFORM: 60 PSF SNOW:
- DRIFT PER IBC 2018
- Pg = 20 PSF
- ls = 0.80 Ce = 0.90

Ct = 1.20

- WIND: BASIC WIND SPEED (3-SECOND GUST) = 105 MPH lw = 1.00
- OCCUPANCY CATEGORY I EXPOSURE C

# SEISMIC:

- SITE CLASS D le = 1.00 OCCUPANCY CATEGORY I Ss = 0.329 SMs = 0.506 SDs = 0.337 S1 = 0.151 SM1 = 0.348 SD1 = 0.232 SEISMIC DESIGN CATEGORY D
- 8. IF CONFLICTS ARE FOUND BETWEEN DETAILS OR DIMENSIONS SHOWN ON STRUCTURAL PLANS AND THOSE SHOWN ON OTHER DISCIPLINES' PLANS, NOTIFY ENGINEER IMMEDIATELY FOR CLARIFICATION PRIOR TO PERFORMING WORK.
- 9. IN ANY CASE OF CONFLICT BETWEEN THE NOTES, DETAILS AND SPECIFICATIONS, THE MOST STRINGENT REQUIREMENTS SHALL GOVERN. CONTRACTOR SHALL MAKE NO DEVIATION FROM DESIGN DRAWINGS WITHOUT WRITTEN APPROVAL OF THE ENGINEER.
- 10.DO NOT UNDERMINE EXISTING CRANE PAD FOUNDATIONS.

# PILES:

- 1. MINIMUM OF TEN TEST PILES REQUIRED TO VERIFY SUFFICIENT LOAD CAPACITY. TEST PILES MAY BE
- INCORPORATED INTO WORK IF THE CAPACITY MEETS SPECIFICATIONS. 2. PILES SHALL BE DESIGNED BY A MISSOURI REGISTERED ENGINEER BASED ON THE LOADS PROVIDED ABOVE.
- 3. ALL PILE INSTALLATION SHALL BE DONE IN THE PRESENCE OF THE OWNER'S GEOTECHNICAL REPRESENTATIVE ON SITE.
- 4. A COMPLETE, ACCURATE LOG OF PILING INSTALLED SHALL BE MAINTAINED AND FURNISHED TO THE CONTRACTOR, OWNER AND ENGINEER. THE LOG SHALL INDICATE THE FOLLOWING:
- A. PILE LOCATION B. DIAMETER
- C. LENGTH
- D. ELEVATION OF TIP AND TOP OF PILE
- E. QUANTITY OF GROUT (IF USED) IN EACH PILE F. DATE OF INSTALLATION
- G. TYPE OF PILE
- H. INSTALLATION DATA VERIFYING LOAD CAPACITY

# SPECIAL INSPECTION:


PILES


- 1. SPECIAL INSPECTION IN ACCORDANCE WITH SECTION 1704 OF THE 2018 INTERNATIONAL BUILDING CODE, AND
- ICBO MODEL PROGRAM FOR SPECIAL INSPECTION.
- 2. THE OWNER WILL EMPLOY AN APPROVED AGENCY TO PERFORM THE SPECIAL INSPECTION SERVICES.
- 3. SPECIAL INSPECTION WILL BE PERFORMED IN ACCORDANCE WITH AND IN ADDITION TO THE INSPECTION AND TESTING REQUIRED BY THE DRAWINGS AND SPECIFICATIONS. 4. THE FOLLOWING ITEMS ARE INCLUDED IN THE SPECIAL INSPECTION:
- SOILS:

2. TIEBACK LENGTH AND SIZE SHOWN FOR SCHEMATIC PURPOSES ONLY. MICRO PILE TIE BACK TO




WORK. SHOULD ANY UTILITIES BE FOUND, THEY SHALL BE PROTECTED IN PLACE AND THE ENGINEER SHALL BE






# HELICAL PILES NEAR EXISTING CRANE PADS DETAIL

(N.T.S.)






Waler tie back anchor connection detail to be used if anchor spacing is between 10ft and 2ft.


> Waler tieback anchor connection detail

SECTION A-A

TIEBACK ANCHOR DETAILS

(N.T.S.)





TIEBACK LAYOUT