



MISSOURI STATE HIGHWAY DEPARTMENT


60'-80'-60' Cont. I-Beam Spans

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	MO.		19	23	





GENERAL NOTES:

Design Specifications: A.A.S.H.O. 1957
 Loading: H15-44 (One-Lane)
 Structural Steel Stress 18,000 %
 Reinforcing Steel Stress 20,000 %
 Class B1 Concrete Stress 1600 %
 Class B Concrete Stress 1200 %
 Superstructure concrete shall be Class B1 (Air-Entrained)
 Substructure concrete shall be Class B (Air-Entrained)
 Rivets 3/4"; holes 1/2", except where otherwise noted.
 Field connections shall be riveted except as noted in handrail details or if the Contractor desires to eliminate all field riveting on this project, he may use high strength steel bolts with hardened washers for the expansion device and the beam splices and machine bolts for other field connections. Heads and nuts of machine bolts shall be American Standard Regular.
 Paint: Shop, none; Field, contact surfaces of bolted field connections, except where high strength bolts are used, one coat of red lead and surfaces inaccessible after erection three coats of red lead. No other paint to be applied by Contractor except as noted for steel piles. Red lead required shall be furnished by Contractor. Payment for cleaning and painting such surfaces will be included in unit price bid for Fabricated Structural Carbon Steel.
 See Section 52.7 of Standard Specifications for required painting of steel piles.
 Qualification of welding operators will be required.
 Where joint filler is specified on the plans, it shall conform with the requirements for Premoulded Material for Filler as given in Section 157.2.5 of Standard Specifications.



ESTIMATED QUANTITIES			
Item	Substr.	Superstr.	Total
Class 1 Excavation for Structures Cu.Yd.	90		90
Class 2 Excavation for Structures Cu.Yd.	95		95
Steel Piles in Place Lin.Ft.	320		320
Steel Pile Cut-offs Lin.Ft.	30		30
Class B Concrete Cu.Yd.	75.5		75.5
Class B1 Concrete Cu.Yd.		101.4	101.4
Reinforcing Steel Lbs.	8550	24620	33170
Fabricated Structural Carbon Steel Lbs.		120640	120640

Note: Excavation for bridge made above Elev. 807.0 will be paid for as Class 1 Excavation for Structures.
 Excavation for bridge made below Elev. 807.0 will be paid for as Class 2 Excavation for Structures.
 Final pay weight for Fabricated Structural Carbon Steel will be based on using field rivets except for bolted connections specified for handrail.



B.M. Elev. 823.83, X-Nails in West Roof of 30" E.I. 160' R.L. Sta. 287+24 (U.S.G.S. Datum)

BRIDGE OVER LOCUST CREEK

STATE ROAD FROM MILAN NORTHWESTERLY TO BAIRDSTOWN
 ABOUT 4.0 MILES N.W. OF MILAN
 PROJECT NO. S-2154(1) (SOO) STA. 285+96.1

SULLIVAN COUNTY

SUBMITTED BY: *Leo J. Beckert* DATE: 1-13-61
 APPROVED BY: *Ref. M. Sutton* DATE: 1-13-61

Drawn Mar. 1960 by G.F.J.
 Checked Dec. 1960 by H.F.C.

Note: This drawing is not to scale. Follow dimensions.


Sheet No. 1 of 7

SEE FINAL PLANS BROWN-LINES


STD. 54.00
 N-973

MISSOURI STATE HIGHWAY DEPARTMENT

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	MO		19	24	




SECTION AT E.



ELEVATION

DETAILS OF END BENT NO. 1



DETAILS OF STEEL PILE SPlice

Note: Top of backwall and expansion device for end bent No. 1 to conform to crown of roadway slab.
Backwall above construction joint shall not be poured until the structural steel of the expansion device is in place and has been poured in adjacent span.
Fill at end bent No. 1 shall not be carried above bottom of beam and wings until superstructure span (1-2) is in place.

COMPLETE BILL OF REINFORCING STEEL

No.	Size	Length	Mark	Location	Bending Sketches & Cutting Diagrams	
End Bents No. 1 & 2						
16	#6	26'-9"	H1	Beam		
4	#6	24'-9"	H2	"		
4	#6	6'-0"	H3	Wing		
12	#6	9'-0"	H4	"		
4	#6	7'-6"	H5	"		
2	#6	25'-0"	H6	Bk.wll. Bt. #1		
2	#4	25'-9"	H7	"		
2	#6	24'-6"	H8	Bk.wll. Bt. #1		
4	#6	13'-0"	T1	Wing Bt. #1		
8	#6	11'-0"	T2	Wing		
4	#6	11'-9"	T3	Wing Bt. #1		
48	#4	11'-6"	U1	Beam		
20	#4	3'-6"	U2	"		
4	#4	25'-9"	H7	Bk.wll. Bt. #1		
42	#5	5'-0"	V1	Bk.wll. Bt. #1		
14	#4	9'-3"	V2	Wing		
4	#4	6'-0"	V3	Bk.wll. Bt. #1		
40	#5	4'-9"	V5	Bk.wll. Bt. #1		
2	#4	6'-0"	V3	Bk.wll. Bt. #1		
10	#2	19'-9"	W1	A.B. Wells		
Int. Bents No. 2 & 3						
32	#7	9'-0"	D1	Footing		
10	#6	8'-0"	F1	Col. Haunch		
10	#6	8'-3"	F2	"		
12	#10	21'-6"	G1	Beam		
4	#6	21'-6"	G2	"		
12	#9	24'-3"	G3	"		
66	#5	9'-0"	U3	"		
40	#3	9'-9"	P1	Col. Bt. #2		
16	#7	26'-0"	P2	Col. Bt. #2		
16	#7	28'-3"	P3	Col. Bt. #3		
12	#4	3'-3"	U4	Beam		
10	#2	19'-9"	W1	A.B. Wells		
50	#3	9'-9"	P1	Col. Bt. #3		
Superstructure						
674	#5	22'-0"	S1	Slab		
18	#4	22'-6"	S2	"		
200	#4	30'-0"	S3	"		
50	#4	16'-0"	S4	"		
1	#5	22'-9"	S5	"		
12	#6	31'-3"	C1	Curb		
3/0	#5	3'-3"	C2	"		
12	#6	41'-0"	C3	"		
12	#6	32'-0"	C4	"		
FINISHED						

FINISHED

BRIDGE OVER LOCUST CREEK
STATE ROAD FROM MILAN NORTHWESTERLY TO BAIRDSTOWN
ABOUT 4.0 MILES N.W. OF MILAN
PROJECT NO. S-2154(1) (S.O.O.) STA. 285+96.1
SULLIVAN COUNTY

04

N-973




ELEVATION




DETAILS OF END BENT NO. 4

ELEVATION



ELEVATION









FINISHED

FINISHED

I-Bm. conc. cap Type End Bl. on Piles with conc. Int. Bent
4-1-59

Note: This drawing is not to scale. Follow dimensions.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	MO.		19	26	



FINISHED DETAIL OF EXPANSION DEVICE

STATE ROAD FROM MIL. N NORTHWESTERLY TO BAIRDSTOWN
ABOUT 4.0 MILES N.W. OF MILAN
PROJECT NO. S-2154(1) (SOO) STA. 285+961

COUNTY








FINISHED

N-973

MISSOURI STATE HIGHWAY DEPARTMENT

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	MO.		19	27	






HALF SECTION NEAR CENTER OF SPAN

HALF SECTION AT INT. BENTS

SPANS (1-2) & (3-4) SPAN (2-3)

Note: The slab shall be poured in sections of the lengths shown above and in the sequence indicated by the numbers 1, 2, 3, 4, 5, 6, 7 or as an alternate by the numbers 1, 2, 3, 4. The separate pours shall progress in the direction indicated by the arrows. Longitudinal construction joints will not be permitted. See Section 53.4.12 Standard Specifications.



BRIDGE OVER LOCUST CREEK
STATE ROAD FROM MILAN NORTHWESTERLY TO BAIRDSTOWN
ABOUT 4.0 MILES N.W. OF MILAN
PROJECT NO. S-2154(1) (500) STA. 285+96.1
SULLIVAN COUNTY

Drawn Feb. 1960 by G.F.J. & E.J.W.
Checked Dec. 1960 by H.F.C.

Note: This drawing is not to scale. Follow dimensions.


Sheet No. 5 of 7

NO CONSTRUCTION CHANGES

N-973

MISSOURI STATE HIGHWAY DEPARTMENT

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	MO.		19	28	



8-Expansion Bearings required for Bent No. 1 & Bent No. 4.
4-Expansion Bearings required for Bent No. 2.

4-Fixed Bearings required for Bent No. 3.

GENERAL NOTES:

Material for Type "D" Bearings shall be A.S.T.M. A-373 Steel or A-7 meeting the carbon and manganese requirements of A-373, except as noted.
Material for Type "C" Bearings shall be Gray Iron Alloy or Cast Steel but payment will be made as Gray Iron Alloy.
Material for Pins shall be A.I. S.I. C-1018.
Anchor Bolts for Type "D" Bearings shall be 1/2" Swedged Bolts and shall extend 12" into concrete, with hexagon nuts and plain washers for Fixed Bearing.
Anchor Bolts for Type "C" Bearing shall be 1" Swedged Bolts, no heads or nuts and shall extend 10" into concrete. Top of Anchor Bolts shall be approximately 2" above top of Casting or Fill Plate.
Anchor Bolts and Studs for Type "C" Castings will be paid for as Fabricated Structural Steel.
Lead Plates under bearings shall be approximately 1/8" thickness and weigh 8#/sq. Foot. Cost of lead plates shall be included in price bid for other items.
Edge (A) to be rounded. (1/8" to 1/4" Radius.)

FINISHED

BRIDGE OVER LOCUST CREEK
STATE ROAD FROM MILAN NORTHWESTERLY TO BAIRDSTOWN
ABOUT 4.0 MILES N.W. OF MILAN
PROJECT NO. S-2154(1) (SOOISTA. 285+96.1)
SULLIVAN COUNTY

FINISHED

FINISHED

Assembled Mar. 1960 by G.F.J. & B.W.D.
Checked Dec. 1960 by H.F.C.

Note: This drawing is not to scale. Follow dimensions

Sheet No. 6 of 7




NO CONSTRUCTION CHANGES

N-973

49

MISSOURI STATE HIGHWAY DEPARTMENT

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
5	MO		19	29	





Note: Use bevel as shown for exposed faces of all filled joints except at top surface of roadway slab. Use edging tool with 1/4" radius at top surface of roadway slab each side of joint and fill flush with joint seal as shown.

DETAILS OF BEVEL FOR FILLED JOINTS

GENERAL NOTES:

Top of curbs and end posts to be built parallel to grade. Vertical faces of end posts to be vertical. All exposed edges of end posts to be beveled 1/2". 6" WF posts to be set normal to grade. 12" L rails shall be fabricated to conform to horizontal and vertical alignment of curb.



BRIDGE OVER LOCUST CREEK
 STATE ROAD FROM MILAN NORTHWESTERLY TO BAIRDSTOWN
 ABOUT 4.0 MILES N.W. OF MILAN
 PROJECT NO. S-2154(1) (SOO) STA. 285+96.1
 SULLIVAN COUNTY

Assembled Feb. 1960 by G.F.J. & B.W.D.
 Checked Dec. 1960 by M.F.C.

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 7 of 7

NO CONSTRUCTION CHANGES

N-973

FINAL PLANS




ELEVATION



Note: This drawing is not to scale. Follow dimensions.



SECTION AT E



FINISHED

FINISHED

Sheet No. 3A of 2

I-Bm. conc. cap Type End Bl. on Piles with conc Int. Bent
4-1-59

N-973

Assembled Jan. 1960 by G.F.J. & E.J.W.F.B.W.D.
Checked Dec. 1960 by H.F.G.

Bridge Number:

ND973

Route/County:

00/Sullivan

Asbestos-Containing Material Present?

Yes: ☐

No: ☒

If yes, see report for location(s).

Structural Steel Present?

Yes: ☒

No: ☐

If No, then skip the following.

Lead-Based Paint (LBP) Present?

Yes: ☒

No: ☐

Trusses LBP?

Yes: ☐ No: ☐

Girder LBP?

Yes: ☒ No: ☐

Railing LBP?

Yes: ☒ No: ☐

Pile LBP?


Yes: ☐ No: ☐



MEMORANDUM

Missouri Department of Transportation Construction and Materials Central Laboratory

TO: TMS

FROM: Frank Reichart 
Environmental Chemist

DATE: February 25, 2016

SUBJECT: Materials
Asbestos Inspection & Heavy Metal Paint Survey
Route OO
Bridge N-0973
Sullivan County

We are providing you with the results of the inspection on the above referenced bridge. The inspection report contains an asbestos and a heavy metals survey. The asbestos inspection included identifying suspect asbestos-containing material and NVLAP accredited testing to confirm the presence of asbestos.

Form T746 – This will show if samples were taken, where from, and, if the sample was found to contain asbestos, our estimated quantity of material present. Under the column “Friability Category”, this is the meaning for the following:

N-ACM – No asbestos detected.

I NF – Asbestos is present. Material shall be handled carefully by a licensed abatement worker and kept wet if removing as part of a maintenance activity.

II NF – Asbestos is present. If removal is required for the maintenance activity, use an abatement contractor.

In accordance with Missouri Department of Natural Resources’ Technical Bulletin “Managing Construction and Demolition Waste” dated January 31, 2003, a heavy metal paint survey has been performed on the above referenced bridge. This survey includes locating concrete which has been painted with something other than traffic paint or graffiti, and testing the painted surface(s) to determine if hazardous heavy metals are present. If the bridge is being removed completely, or the maintenance repairs include removing the painted concrete, then, non-hazardous painted concrete may be used as clean fill materials, if properly handled. You must contact the Central Office Design Division for proper handling of the reported painted surfaces.

Although our survey included observing and sampling all accessible areas, it is possible that potentially hidden asbestos-containing materials may exist within the structure. Should you have any questions regarding these reports, please contact me at (573) 526-4359.

db/fr/dr

[http://sharepoint/systemdelivery/cm/chemicallab/environmental/shared
documents/asbestos/districts/northwest\(nw\)/mt/n0973/dr1602253.docx](http://sharepoint/systemdelivery/cm/chemicallab/environmental/shared/documents/asbestos/districts/northwest(nw)/mt/n0973/dr1602253.docx)

Attachments

**MISSOURI DEPARTMENT OF TRANSPORTATION
CONSTRUCTION AND MATERIALS
Asbestos Survey Report
All Suspect ACM**

ROUTE:	00
MODOT JOB NO.:	N/A
DISTRICT:	NW
COUNTY:	Sullivan
DATE OF SURVEY:	February 25, 2016
PARCEL NO.:	Bridge N-0973

SURVEYED BY:	Frank Reichart and Diane Roegge
CERTIFICATION #:	7118110315MOIR11239, F.R.
CERTIFICATION #:	7118110315MOIR7165, D.R.
SITE ADDRESS:	Over Locust Creek
TYPE(S) OF STRUCTURE(S):	Bridge

[illegible]

N-ACM = Non-Asbestos Containing Material I NF = Category I Nonfriable II NF = Category II Nonfriable F = Friable
NAFD = No Asbestos Fiber Detected * = Tested By Point Count Procedure

MISSOURI DEPARTMENT OF TRANSPORTATION
CONSTRUCTION AND MATERIALS

Asbestos Survey Report

Nonfriable Asbestos-Containing Materials

(Abatement not required if not made friable during demolition.)

ROUTE:

00

MODOT JOB NO.:

N/A

DISTRICT:

NW

COUNTY:

Sullivan

DATE OF TESTS:

March 14, 2016

PARCEL NO.:

Bridge N-0973

TESTED BY:

Diane Roegge

CERTIFICATION #:

7118110315MOIR7165, D.R.

SITE ADDRESS:

Over Locust Creek

TYPE(S) OF STRUCTURE(S):

Bridge

[illegible]

MISSOURI DEPARTMENT OF TRANSPORTATION
CONSTRUCTION AND MATERIALS

Asbestos Survey Report

All materials requiring removal or special handling.

平

ROUTE:	OO	TESTED BY:	Diane Roegge
MODOT JOB NO.:	N/A	CERTIFICATION #:	7118110315MOIR7165, D.R.
DISTRICT:	NW	SITE ADDRESS:	Over Locust Creek
COUNTY:	Sullivan	TYPE(S) OF STRUCTURE(S):	Bridge
DATE OF TESTS:	March 14, 2016		
PARCEL NO.:	Bridge N-0973		

[illegible]

MISSOURI DEPARTMENT OF TRANSPORTATION
CONSTRUCTION AND MATERIALS
Metals Survey Report of Painted Concrete, Block, Brick Surfaces for Clean Fill Purposes

ROUTE:	00
MODOT JOB NO.:	N/A
DISTRICT:	NW
COUNTY:	Sullivan
SURVEYED BY:	Frank Reichart
DATE OF SURVEY:	February 25, 2016

TESTED BY:	N/A
DATE OF TESTS:	N/A
PARCEL NO.:	Bridge N-0973
SITE ADDRESS:	Over Locust Creek
TYPE(S) OF STRUCTURE(S):	Bridge

[illegible]


All results are by XRF unless otherwise indicated: a = USEPA SW-846 Method 3050 b = USEPA SW-846 Method 7471



MEMORANDUM

Missouri Department of Transportation
Construction and Materials
Central Laboratory

TO: TMS

FROM: Frank Reichart 
Environmental Chemist, Lead License #110506-300003364

DATE: October 29, 2018

SUBJECT: Materials
Job No. N/A
OO/Sullivan County
Bridge# N0973

On October 29, 2018, a paint screening for regulated heavy metals was performed on the subject bridge. The following results were obtained:

	18MFJR742
Arsenic (As)	51,123 ppm**
Chromium (Cr)	4,734 ppm
Lead (Pb)	437,767 ppm (43.8%)
Cadmium (Cd)	587 ppm
Selenium (Se)	207 ppm
Barium (Ba)	LOD*
Mercury (Hg)	LOD
Silver (Ag)	LOD

*LOD = below the detection limit of the instrument

**ppm = parts per million

TMS paint data indicated a System A paint was under the System S paint, applied in 2006. The results verify the information found in TMS.

The existing paint system is lead-based paint (LBP). Therefore any painting project will be subject to DHSS notification and regulation.

Should any further screenings be required, please contact Todd Bennett, Chemical Laboratory Director, at (573) 751-1045.

Should you have any questions regarding the screenings, feel free to call me at (573) 526-4359.

fr/dr

[http://sharepoint/systemdelivery/cm/chemicallab/environmental/shared
documents/asbestos/districts/northwest \(nw\)/mt/n0973/lbp xrf n0973.docx](http://sharepoint/systemdelivery/cm/chemicallab/environmental/shared/documents/asbestos/districts/northwest(nw)/mt/n0973/lbp_xrf_n0973.docx)

Expiration Date

12/2/2016

Certificate Number: 7118110315MOIR11239

Training Date:

11/3/2015

Missouri State Certificate for Asbestos Related Occupations

issued by Department of Natural Resources

P.O. Box 176

Jefferson City, MO 65102

Phone (573) 751-4817


Francis J. Reichart

has successfully completed the requirements for certification as a INSPECTOR. This Missouri State Certification is subject to review and the director may deny, suspend or revoke the certification per RSMo chapter 643.230.

12/3/2015

Date

Director of Air Pollution Control Program



Expiration Date

12/2/2016

Certificate Number: 7118110315MOIR7165

Training Date:

11/3/2015

Missouri State Certificate for Asbestos Related Occupations

issued by Department of Natural Resources
P.O. Box 176
Jefferson City, MO 65102
Phone (573) 751-4817


Diane R. Roegge


has successfully completed the requirements for certification as a INSPECTOR. This Missouri State Certification is subject to review and the director may deny, suspend or revoke the certification per RSMo chapter 643.230.


12/3/2015


Date


Diane R. Roegge
Director of Air Pollution Control Program





		<div>Missouri Department of Transportation</div> <div>State Bridge Inspection Report</div>				<div>December 03, 2024</div> <div>7:35:31AM</div>			
COUNTY: SULLIVAN		DISTRICT: NW		CLASS: STATBR		FED-ID: 7393		BRIDGE: N0973	
GENERAL STRUCTURE INFORMATION							***BRIDGE INSPECTION INFORMATION***		
<div>ROUTE: RTOOS</div> <div>FEATURE: LOCUST CR</div> <div>STATUS: A-OPEN</div> <div>LOG MILE: 2.550</div> <div>DETOUR: 19.00 MILES</div> <div>NHS: NO</div> <div>BUILT: 1961</div> <div>REHAB:</div> <div>LOCATION: S 17 T 63 R 20 W</div> <div>LATITUDE: 40 15 30.50 (DMS)</div> <div>LONGITUDE: 93 9 59.04 (DMS)</div>		<div># SPANS: 3</div> <div>LANES ON: 2</div> <div>LANES UNDER: 0</div> <div>COMPASS DIRECTION: SOUTH to NORTH</div> <div>DIRECTION OF TRAFFIC: 2-WAY TRAF</div> <div>FUNCTIONAL CLASS: RL-MAJOR COLLECTOR</div> <div>NBI OWNER: MODOT</div> <div>NBI MAINTAINED: MODOT</div> <div>MAINTENANCE DISTRICT: NW</div> <div>MAINTENANCE COUNTY: SULLIVAN</div> <div>SUB AREA: 7A38</div>		<div>PLACE CODE: 58880 POLK</div> <div>LENGTH: 204 FT 0 IN</div> <div>MAXIMUM SPAN: 80 FT 0 IN</div> <div>APPROACH ROADWAY: 20 FT 0 IN</div> <div>CURB TO CURB: 20 FT 0 IN</div> <div>OUT TO OUT: 22 FT 4 IN</div> <div>AADT: 572</div> <div>AADT YEAR: 2023</div> <div>AADT TRUCK: 12.4%</div> <div>FUTURE AADT: 715</div> <div>FUTURE AADT YEAR: 2043</div>		<div>DATE: 08/15/2023</div> <div>RESPONSIBILITY: DISTRICT</div> <div>FREQUENCY: 24</div> <div>CALCULATED INTERVAL**: 24</div> <div>TEAM LEADER: BRYCE ACTON</div> <div>ELEMENT: NO</div> <div>INSPECTOR 2:</div> <div>INSPECTOR 4:</div> <div>INSPECTOR 3:</div> <div>** When calculated interval exceeds the frequency, a justification comment per BIRM is required.</div>			
						GENERAL INSPECTION COMMENTS			
FRACTURE CRITICAL INSPECTION INFORMATION					***INDEPTH INSPECTION INFORMATION***				
<div>DATE:</div> <div>FREQUENCY:</div> <div>TEAM LEADER:</div> <div>INSPECTOR 2:</div> <div>** When calculated interval exceeds the frequency, a justification comment per BIRM is required.</div>					<div>RESPONSIBILITY:</div> <div>CALCULATED INTERVAL**:</div> <div>INSPECTOR 3:</div> <div>INSPECTOR 4:</div> <div>CATEGORY:</div> <div>NBI:</div> <div>METHOD:</div> <div>** When calculated interval exceeds the frequency, a justification comment per BIRM is required.</div>				
FRACTURE CRITICAL INSPECTION COMMENTS					INDEPTH INSPECTION COMMENTS				
SPECIAL INSPECTION INFORMATION					***UNDERWATER INSPECTION INFORMATION***				
<div>DATE: 08/06/2021</div> <div>FREQUENCY: 72</div> <div>TEAM LEADER: SCOTT STEPHENS</div> <div>INSPECTOR 2:</div> <div>** When calculated interval exceeds the frequency, a justification comment per BIRM is required.</div>					<div>RESPONSIBILITY: DISTRICT</div> <div>CALCULATED INTERVAL**: 12</div> <div>INSPECTOR 3:</div> <div>INSPECTOR 4:</div> <div>CATEGORY: CHANNEL CROSS SEC</div> <div>NBI: NO</div> <div>METHOD: WT TAPE</div> <div>** When calculated interval exceeds the frequency, a justification comment per BIRM is required.</div>				
SPECIAL INSPECTION COMMENTS					UNDERWATER INSPECTION COMMENTS				
OTHER SPECIAL INSPECTIONS					OTHER UNDERWATER INSPECTIONS				
<div>DATE</div> <div>FREQUENCY</div> <div>CATEGORY</div> <div>NBI</div> <div>CALCULATED INTERVAL</div> <div>RESPONSIBILITY</div> <div>METHOD</div>					<div>DATE</div> <div>FREQUENCY</div> <div>CATEGORY</div> <div>NBI</div> <div>CALCULATED INTERVAL</div> <div>RESPONSIBILITY</div> <div>METHOD</div>				
Design_No = n0973									
<div>Page 1</div> <div>This report contains information that is protected from disclosure by federal law, 23 USC Section 409 and the Missouri Open Records Law (Sunshine Act), Section 610.021 RSMo. Please review MoDOT's policy and procedure manual on the Sunshine Act before releasing any of the information contained herein.</div>									


		Missouri Department of Transportation			December 03, 2024	
		State Bridge Inspection Report			7:35:31AM	
COUNTY: SULLIVAN		DISTRICT: NW		CLASS: STATBR	FED-ID: 7393	BRIDGE: N0973
STRUCTURE POSTING						
APPROVED CATEGORY: S-1		NO POSTING REQUIRED				
Ton 1:		Ton 2:		Ton 3:		
COMMENTS:						
FIELD CATEGORY: S-1		NO POSTING REQUIRED				
Ton 1:		Ton 2:		Ton 3:		PROBLEM:
COMMENTS:		PROBLEM DIRECTION:				
GENERAL COMMENTS/MAJOR RATED ITEMS						
GENERAL COMMENTS: (BOWDEJ1, 02/03/2010)--(61'-80'-61') CONT NON-COMP WF GDR SPANS						
[ITEM 58] DECK: 3-SERIOUS CONDITION		COMMENTS: (STEPHS2, 12/30/2015)--DECK SATURATION				
RATING : 09/09/2021						
[ITEM 59] SUPER: 6-SATISFACTORY CONDITION		COMMENTS: (STEPHS2, 12/30/2015)--BEAM RUSTING				
RATING : 12/30/2015						
[ITEM 60] SUB: 7-GOOD CONDITION		COMMENTS: (ACTONB1, 08/24/2023)--SCALING @ COLUMNS				
RATING : 05/18/2001						
[ITEM 61] BANK/CHANNEL: 5-MAJOR DAMAGE		COMMENTS: (BOWDEJ1, 10/27/2004)--SLOPE EROSION				
RATING : 12/30/2015		(ACTONB1, 08/24/2023)--CONSIDERABLE BANK EROSION				
[ITEM 113] SCOUR: 8-STABLE FOR CALCULATED		COMMENTS: (ACTONB1, 08/24/2023)--MINOR SCOUR @ BENT 3 COLUMNS				
RATING : 05/18/2001						
EVALUATION TYPE :						
[ITEM 71] WATERWAY ADEQUACY: DECK ABOVE FLOOD ELEV		COMMENTS:				
RATING : 05/18/2001						
[ITEM 72] APPRRDWY ALIGNMENT: 6-SATISFACTORY		COMMENTS:				
RATING : 05/18/2001						
RAILING AND APPROACH PAVEMENT COMPONENTS AND RATINGS						
[ITEM 36A] BRIDGE RAILING RATING: DOESNT MEET CURRNT STND-0		RATING : 02/22/2004		COMMENTS:		
<u>MATERIAL</u>	<u>CONSTRUCTION</u>	<u>DIRECTION</u>	<u>COMMENTS</u>			
REINFORCED CONCRETE	CURB	BOTH				
STEEL	CHANNEL-12"	BOTH				
[ITEM 36B] TRANSITION RAILING RATING: NOT PROVIDED-0		RATING : 05/18/2001		COMMENTS:		
[ITEM 36C] APPROACH RAILING RATING: NOT PROVIDED-0		RATING : 05/18/2001		COMMENTS:		
[ITEM 36D] RAIL END TREATMENT RATING: NOT PROVIDED-0		RATING : 05/18/2001		COMMENTS:		
Design_No = n0973						
Page 2						
This report contains information that is protected from disclosure by federal law, 23 USC Section 409 and the Missouri Open Records Law (Sunshine Act), Section 610.021 RSMo. Please review MoDOT's policy and procedure manual on the Sunshine Act before releasing any of the information contained herein.						







		<div>Missouri Department of Transportation</div> <div>State Bridge Inspection Report</div>				<div>December 03, 2024</div> <div>7:35:31AM</div>							
COUNTY: SULLIVAN		DISTRICT: NW		CLASS: STATBR		FED-ID: 7393		BRIDGE: N0973					
<div><div><div><div><div>CLEARANCES UNDER BRIDGE</div><div>RECORD #</div><div>ROUTE</div><div>VERTICAL CLEARANCE TYPE**</div></div><div><div># LANES</div><div>VALUE</div></div><div><div>DIRECTION OF TRAFFIC</div><div>DIRECTION</div></div><div><div>DATE</div></div><div><div>COMMENT</div></div></div><div><div>**NOTE: Vertical clearances for permitting purposes are taken as 2 inches less than the actual field measured clearance.</div></div><div><div>RIGHT LATERAL CLEARANCE</div><div>LEFT LATERAL CLEARANCE</div></div><div><div>UR-ID</div></div></div></div>													
STRUCTURE PAINT INFORMATION													
CONDITION: FAIR		RUST AMOUNT : 6=1.0% OF SURFACE RUSTED			STEEL TONS : 60								
<div><div>ORIGINAL PAINT</div><div>PAINT TYPE : A SYSTEM</div><div>NAME : RED LEAD</div><div>PAINT COLOR : ALUMINUM</div><div>PAINT YEAR : 1963</div><div>MILS : 4</div></div>		<div><div>CONTRACT REPAINT</div><div>PAINT TYPE :</div><div>NAME :</div><div>PAINT COLOR :</div><div>PAINT YEAR :</div><div>MILS :</div></div>			<div><div>DEPARTMENT REPAINT</div><div>PAINT TYPE : S SYSTEM</div><div>NAME : CAL SULPH/LEAD PAINT</div><div>PAINT COLOR : GRAY</div><div>PAINT YEAR : 2006</div><div>MILS : 15</div></div>		<div><div>MANUFACTURE :ARMOR SHIELD</div><div>SURFACE PREP :HAND CLEANED</div></div>						
REQUESTED WORK ITEMS													
GENERAL WORK COMMENTS:													
RESPONSIBILITY		LOCATION		ITEM		CATEGORY		PRIORITY		DATE		WORK ITEM COMMENT	
UTILITY ATTACHMENTS													
UTILITY		OWNER		METHOD		MEASUREMENT TYPE		VALUE		NUMBER		UTILITY ATTACHMENT COMMENT	
PROGRAM NOTES INFORMATION													
YEAR		PROJECT #		MONTH LET		YEAR LET		ITEMS		COMMENT			
Design_No = n0973													
<div>Page 6</div> <div>This report contains information that is protected from disclosure by federal law, 23 USC Section 409 and the Missouri Open Records Law (Sunshine Act), Section 610.021 RSMo. Please review MoDOT's policy and procedure manual on the Sunshine Act before releasing any of the information contained herein.</div>													

<div><div>Missouri Department of Transportation</div><div>State Bridge Inspection Report</div></div>			December 03, 2024 7:35:31AM																																																	
COUNTY: SULLIVAN			DISTRICT: NW		CLASS: STATBR		FED-ID: 7393		BRIDGE: N0973																																											
COMPUTER GENERATED RATINGS AND DEFICIENCY ITEMS						***ADVANCED SIGN INFORMATION***																																														
<div>NOTE: The items listed in this section are updated whenever computer edits are ran on a structure after the inspection updates have been entered in to TMS.</div> <table><thead><tr><th>Rated Item</th><th>Rating</th><th>Rating Date</th></tr></thead><tbody><tr><td>[Item 67] Structure Evaluation Rating:</td><td>4-MEETS MINIMUM TOLERABLE</td><td>3/20/2002</td></tr><tr><td>[Item 68] Deck Geometry Rating:</td><td>3-BASICALLY INTOL CORRECT</td><td>3/20/2002</td></tr><tr><td>[Item 69] Underclearance:</td><td>N-NOT APPLICABLE</td><td>5/18/2001</td></tr><tr><td>Sufficiency Rating:</td><td>47.1%</td><td>3/7/2024</td></tr><tr><td>Deficiency:</td><td>STRUCTURAL</td><td>1/4/2016</td></tr><tr><td>Funding Eligibility:</td><td>FULL</td><td>----</td></tr><tr><td>Estimated New Structure Length:</td><td>240 FT.</td><td>----</td></tr><tr><td>Estimated Structure Cost:</td><td>\$1,391,760</td><td>----</td></tr><tr><td>Estimated Total Project Cost:</td><td>\$2,087,640</td><td>----</td></tr><tr><td>Year of Cost Estimate:</td><td>2024</td><td>----</td></tr></tbody></table> <div>NOTE: The above structure length and cost estimates are computer generated using algorithms in the TMS system. These algorithms are generalized to use NBI items to come up with a new structure length and width to calculate a new area which is taken times a representative cost per square foot. The actual structure size and cost may vary significantly from these numbers once site specific engineering is done.</div>						Rated Item	Rating	Rating Date	[Item 67] Structure Evaluation Rating:	4-MEETS MINIMUM TOLERABLE	3/20/2002	[Item 68] Deck Geometry Rating:	3-BASICALLY INTOL CORRECT	3/20/2002	[Item 69] Underclearance:	N-NOT APPLICABLE	5/18/2001	Sufficiency Rating:	47.1%	3/7/2024	Deficiency:	STRUCTURAL	1/4/2016	Funding Eligibility:	FULL	----	Estimated New Structure Length:	240 FT.	----	Estimated Structure Cost:	\$1,391,760	----	Estimated Total Project Cost:	\$2,087,640	----	Year of Cost Estimate:	2024	----	<table><thead><tr><th>SIGN #</th><th>SIGN TYPE</th><th>PROBLEM</th><th>PROBLEM DIRECTION</th></tr></thead><tbody><tr><td>1</td><td>C - IDHW</td><td></td><td></td></tr></tbody></table>						SIGN #	SIGN TYPE	PROBLEM	PROBLEM DIRECTION	1	C - IDHW		
Rated Item	Rating	Rating Date																																																		
[Item 67] Structure Evaluation Rating:	4-MEETS MINIMUM TOLERABLE	3/20/2002																																																		
[Item 68] Deck Geometry Rating:	3-BASICALLY INTOL CORRECT	3/20/2002																																																		
[Item 69] Underclearance:	N-NOT APPLICABLE	5/18/2001																																																		
Sufficiency Rating:	47.1%	3/7/2024																																																		
Deficiency:	STRUCTURAL	1/4/2016																																																		
Funding Eligibility:	FULL	----																																																		
Estimated New Structure Length:	240 FT.	----																																																		
Estimated Structure Cost:	\$1,391,760	----																																																		
Estimated Total Project Cost:	\$2,087,640	----																																																		
Year of Cost Estimate:	2024	----																																																		
SIGN #	SIGN TYPE	PROBLEM	PROBLEM DIRECTION																																																	
1	C - IDHW																																																			
						OUTFALL INSPECTION INFORMATION																																														
						<table><tr><td># OUTFALLS:</td><td>INSPECTOR:</td></tr><tr><td>STATUS:</td><td>DATE:</td></tr><tr><td>NOTES:</td><td></td></tr></table>						# OUTFALLS:	INSPECTOR:	STATUS:	DATE:	NOTES:																																				
# OUTFALLS:	INSPECTOR:																																																			
STATUS:	DATE:																																																			
NOTES:																																																				



Missouri Department of Transportation
Bridge Inventory and Inspection System
Structural Inventory & Appraisal Sheet

December 3, 2024
7:30:18am

COUNTY : SULLIVAN BRIDGE : N0973 REVIEW STATUS : APPROVED NBI STATUS : T
RECORD TYPE : ROUTE CARRIED 'ON' STRUCT RUN DATE : 11/27/2024 SUBMITTAL YEAR : 2024

GENERAL STRUCTURE INFORMATION			ROUTE DESIGNATION INFORMATION		
1	State	MISSOURI	5A	Record Type	ROUTE CARRIED 'ON' STRUCT
2	District	NW	5B	Route Signing Prefix	MO
3	County	SULLIVAN	5C	Designated Level of Service	MAINLINE
8	Federal ID No.	7393	5D	Route Number	00000
27	Year Built	1961	5E	Directional Suffix	NOT APPLICABLE
106	Year Reconstructed	0	7	Facility Carried	RT OO S
42A	Type of Service On	HIGHWAY	12	Base Hwy. Network	NO
21	Structure Maintenance	STATE HIGHWAY AGENCY	13A	LRS Inventory Route No.	
22	Structure Owner	STATE HIGHWAY AGENCY	13B	Subroute No.	
33	Br. Median Code	NO MEDIAN	20	Toll Status	ON FREE ROAD
37	Historical Significance	NOT ELIGIBLE FOR NR OF HP	26	Functional Classification	07-RURAL MAJOR COLLECTOR
101	Parallel Struc Desg	NONE EXISTS	28A	Lanes on Structure	02
103	Temporary Structure	NOT TEMPORARY	100	STRAHNET Designation	RTE NOT A DEFENSE HWY
112	NBIS Bridge Length	YES	104	National Highway System	NOT ON NHS
			105	Federal Lands Highway	NOT APPLICABLE
			110	Designated Nat. Network	NO
STRUCTURE LOCATION INFORMATION			STRUCTURE TRAFFIC INFORMATION		
4	Place	POLK	29	AADT	572
	Code	58880	30	AADT Year	2023
9	Location	S 17 T 63 N R 20 W	102	Direction of Traffic	2-WAY TRAFFIC
11	Milepoint	2.57 miles	109	AADT Truck Percent	12%
16	Latitude	40 D 15 M 31 S	114	Future AADT	715
17	Longitude	93 D 9 M 59 S	115	Future AADT Year	2043
UNDERRECORD INFORMATION			STRUCTURE GEOMETRIC INFORMATION		
6	Features Intersected	LOCUST CR	10	Inventory Rte. Vert. Clear	99 Ft. 99 In.
42B	Type of Service Under	WATERWAY	19	By pass Detour Length	19.38 miles
28B	Lanes Under Structure	00	32	Approach Roadway Width	20 Ft. 0 In.
54A	Vert. Clearance Ref.	N/A	34	Skew	15.00 Degrees
54B	Vert. Clearance	0 Ft. 0 In.	35	Struct. Flared	NO
55A	Rt. Lat Clear Ref.	N/A	47	Total Horiz. Clear	20 Ft. 0 In.
55B	Rt. Lat Clearance	0 Ft. 0 In.	48	Maximum Span Length	80 Ft. 1 In.
56	Left Lat Clearance	0 Ft. 0 In.	49	Structure Length	204 Ft. 1 In.
38	Navigation Control	PERMIT NOT REQ	50A	Left Curb/Sidewalk Width	0 Ft. 0 In.
39	Nav Vertical Clear	0 Ft. 0 In.	50B	Right Curb/Sidewalk Width	0 Ft. 0 In.
40	Nav Horizontal Clear	0 Ft. 0 In.	51	Curb to Curb Br. Width	20 Ft. 0 In.
111	Nav. Pier Protection		52	Deck Width (Out-Out)	22 Ft. 4 In.
116	Nav. Cl. Vert. Clear		53	Vert. Clearance Over Deck	99 Ft. 99 In.

Design_No = n0973 and Inventory_Appraisal_Submittal_Year = 2024



Missouri Department of Transportation
Bridge Inventory and Inspection System
Structural Inventory & Appraisal Sheet

December 3, 2024
7:30:18am

COUNTY : SULLIVAN BRIDGE : N0973 REVIEW STATUS : APPROVED NBI STATUS : T
RECORD TYPE : ROUTE CARRIED 'ON' STRUCT RUN DATE : 11/27/2024 SUBMITTAL YEAR : 2024

LOAD RATING AND POSTING INFORMATION			MATERIAL/CONSTRUCTION INFORMATION		
31	Design Load	H 15	43A	Main Struc. Mat type	STEEL CONTINUOUS
41	Structure Status	OPEN NO RESTRICTIONS	43B	Main struc Constr. Type	STRINGER/MULTIBEAM - GRD
63	Oper. Rating Meth.	ALLOWABLE STRESS	45	# of Main Spans	3
64	Operating Rating	29 Tons.	44A	Appr Struc. Mat type	000
65	Inventory Rating Meth	ALLOWABLE STRESS	44B	Appr Struc. Cnstr. type	000
66	Inventory Rating	16 Tons.	46	# of Approach Span	0
70	Bridge Posting Code	=>LEGAL LOADS	107	Deck Mat/Constr.	1 CONCRETE CIP
PROPOSED IMPROVEMENT INFORMATION			108A	Wear Surf Mat/Constr.	6 BITUMINOUS
Sufficiency Rating 47.1 Percent			108B	Membrane Mat/Constr.	0 NONE
Deficiency Rating STRUCTURAL			108C	Deck Protect Mat/Constr.	0 NONE
Funding Eligibility FULL			CONDITION RATING INFORMATION		
75A	Proposed Work	REPLACEMENT SUBSTND LOAD	58	Deck Cond. Rating	3
75B	Work Done By	Contract	59	Superstructure Cond. Rating	6
76	New Struc Length	239 Ft. 6 In.	60	Substructure Cond. Rating	7
94	Struc Improve Cost	\$ 1,392,000	61	Channel /Channel Protection Cond. Rating	5
95	Roadway Improve Cost	\$ 139,000	62	Culvert Cond. Rating	N
96	Total Project Cost	\$ 2,088,000	INSPECTION INFORMATION		
97	Year of Cost Estimates	2024	90	Gen. Insp Date	8 / 23
APPRAISAL RATING INFORMATION			91	Gen. Insp. Frequency	24 Months
36A	Br. Rail App. Rating	DOES NOT MEET ACCEPT STND	92A	Frac. Critical Inspection	N Months
36B	Transition Rail App. Rating	DOES NOT MEET ACCEPT STND	93A	Frac. Critical Insp. Date	
36C	Approach Rail App. Rating	DOES NOT MEET ACCEPT STND	92B	Underwater Inspection	N Months
36D	Rail End Treat. App. Rating	DOES NOT MEET ACCEPT STND	93B	Underwater Insp. Date	
67	Struc Eval App. Rating	4	92C	Special Inspection	N Months
68	Deck Geometry App. Rating	3	93C	Special Inspection Date	
69	Underclearance App. Rating	N	BORDER BRIDGE INFORMATION		
71	Waterway Adeq. App. Rating	8	98	Neighboring State Code	
72	Approach Road App. Rating	6	98B	Neighboring State % Respon	
113	Scour Assess App. Rating	8	99	Neighboring State Struc. No.	
APPROVED POSTING INFORMATION			FIELD POSTING INFORMATION		
Approved Posting Category S-1			Field Posting Category S-1		
Ton1 Ton2 Ton3			Ton1 Ton2 Ton3		
Tonnage Values for Posting Sign			Tonnage Values for Posting Sign		
General Text for Posting Sign			General Text for Posting Sign		
NO POSTING REQUIRED			NO POSTING REQUIRED		

Design_No = n0973 and Inventory_Appraisal_Submittal_Year = 2024

STRUCTURAL REHABILITATION CHECKLIST

Bridge No.: **N0973**

Job No.: **NW0014**

Route: **OO**

Over: **Locust Creek**

County: **Sullivan**

Date of Field Check: **10/25/2022**

*** Please include photographs for all items that apply. ***

1

OVERLAY

* Type of existing overlay: ☐ None ☒ Asphalt ☐ Low Slump ☐ Silica Fume ☐ Latex ☐ Epoxy ☐ Other: _____

* Existing overlay thickness: **?** "

* Year overlay was applied: _____ ☒ Unknown

* % of overlay repaired or patched: _____ %

* Replace overlay: ☐ Yes ☐ No

* Notes: _____

Picture **DSCN2364, DSCN2367**
#

2A

DECK REPAIRS (Deck repair quantities are required even if a Deck Test request has been ordered for this structure.)

* Half-sole repairs: _____ sq. ft.
(round up to the nearest 50 sq. ft.)

* Full depth repairs: _____ sq. ft.
(round up to the nearest 50 sq. ft.)

* Existing deck repair (patching): _____ sq. ft.
(round up to the nearest 25 sq. ft.)

* Slab edge repairs: _____ lin. ft.
(covers the outer 4" of the slab edge)

* Superstructure repair (Unformed): _____ sq. ft.
(covers the remaining slab cantilever beyond the outer 4")

* Clean & epoxy coat slab edge: _____ lin. ft.
(in lieu of edge repairs)

* Cantilever replacement: _____ lin. ft.

* Total surface hydro demolition of bridge deck: ☐ Yes ☐ No
(half-sole, full depth and exist. deck repair quantities still required)

* Full deck replacement (redeck) ☒ Yes ☐ No ☐ Optional

* Deck repairs with voided tube replacement: ☐ Yes ☐ No
(minimum of 10% of half-sole repair quantity)
_____ sq. ft.

* Superstructure replacement: ☐ Yes ☒ No ☐ Optional

* Full bridge replacement: ☐ Yes ☒ No ☐ Optional
(Deck repair quantities required for cost comparison of alternatives)

* How were the quantities obtained ☐ Visual ☐ Bridge Inspection Report ☐ Sounded ☐ Other _____

* Notes: **Scope is to redeck the bridge.**

Picture **DSCN2367**
#

DECK REPAIRS CONT.*** ISSUES / PROBLEMS WITH PRECAST PRESTRESSED DECK PANELS**

Spans	Location in Span						Deterioration		Describe
	At Panel Jt.	Btwn (mid) Panel Jt.	End	Mid	End		Type	Amount	
_____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	_____	sq. ft	_____
_____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	_____	sq. ft	_____
_____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	_____	sq. ft	_____
_____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	_____	sq. ft	_____
_____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	_____	sq. ft	_____
_____	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	_____	sq. ft	_____

* Notes: **Scope is to redeck the bridge.**

(Deterioration may include water saturation, efflorescence, rust staining, cracking, spalling, exposed steel, disintegration of panel edges at joints, etc. Typically observed at or near panel joints. The location and "Type" of deterioration should be recorded.)

Picture
#

APPROACH SLABS

- * Is there a bridge approach slab in place? ☐ Yes ☒ No * Type: ☐ Concrete ☐ Asphalt ☐ Other _____
- * Is there rdwy. approach pavement in place? ☒ Yes ☐ No * Type: ☐ Concrete ☒ Asphalt ☐ Other _____
- * Is the approach slab sinking at the end bent? ☒ N/A ☐ Yes ☐ No _____
- * Are repairs needed to the bridge approach slab driving surface? ☐ Yes ☐ No _____
(Typically a roadway item but will be reported to District on the Bridge Memorandum.)
- * Full replacement of bridge approach slab? ☐ Yes ☐ No _____
- * Notes: _____

Picture **DSCN2364, DSCN2386**
#

4

SLAB DRAINS

* Is the drainage system working adequately? ☒ Yes ☐ No

* Recommendations: _____

* Notes: _____

Picture **DSCN2367**

#

5

CURBS & RAILS

* Existing curb (left side): ☒ Safety Barrier Curb ☒ Curb/parapet ☐ Blockouts ☐ Thrie Beam ☐ Baluster ☒ Steel Channel

☐ Other _____ ☐ Handrail ☐ Fence _____

* Does curb need repair ☐ Yes ☐ No * Curb repair _____ lin. ft.

* Remove hand rail ☐ Yes ☐ No * Add curb blockout ☐ Yes ☐ No

* Existing curb (right side): ☐ Safety Barrier Curb ☒ Curb/parapet ☐ Blockouts ☐ Thrie Beam ☐ Baluster ☒ Steel Channel

☐ Other _____ ☐ Handrail ☐ Fence _____

* Does curb need repair ☐ Yes ☐ No * Curb repair _____ lin. ft.

* Remove hand rail ☐ Yes ☐ No * Add curb blockout ☐ Yes ☐ No

* Existing median curb: Type: _____ Width _____ " Height _____ "

* Does curb need repair ☐ Yes ☐ No * Curb repair _____ lin. ft.

* Approach rail attachment: ☐ None ☐ Not attached ☐ 4 Hole ☐ 5 Hole ☐ Turn-down ☐ Other _____

* If the existing handrails will be removed, does the local maintenance supervisor wish to keep them? ☐ Yes ☐ No

Storage address: location: _____

address: _____

city: _____ state: _____ zip: _____

* Notes: _____

Picture **DSCN2364, DSCN2367**

#

6

EXPANSION DEVICES

Bent	Type	Recommendations			Gap Left	Gap Right	Temperature & Other Info
4		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	"	"	
3		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	"	"	
2		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	"	"	
1		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	"	"	
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	"	"	
		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	"	"	

* Notes: **Will be replaced with the redeck**

Picture
#

7

BEARINGS

Bent	Coating	Recommendations				Notes (indicate which bearings at each bent)
4	<input type="checkbox"/> CLEAN & OVERCOAT <input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All bearings
3	<input checked="" type="checkbox"/> CLEAN & OVERCOAT <input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	All bearings
2	<input checked="" type="checkbox"/> CLEAN & OVERCOAT <input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All bearings
1	<input type="checkbox"/> CLEAN & OVERCOAT <input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All bearings
	<input type="checkbox"/> BLAST CLEAN & RECOAT <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
	<input type="checkbox"/> BLAST CLEAN & RECOAT <input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	

* Notes:

Picture # (Provide Pictures of Each Bearing)

DSCN2368, DSCN2369, DSCN2370, DSCN2371, DSCN2375, DSCN2376, DSCN2377, DSCN2389, DSCN2390, DSCN2391, DSCN2392, DSCN2395, DSCN2396, DSCN2397, DSCN2398,

8

COATING SYSTEM (PAINT)

* Existing coating system: System S ☐ green ☒ gray ☐ other

* Date last coated: **7/2006**

* Is existing coating peeling? ☐ Yes (Overcoat is not an option) ☒ No

* Coating recommendation:

- ☐ Blast clean & recoat all steel ☒ Clean & overcoat all steel
- ☐ Blast clean & recoat only at joint locations ☐ Blast & recoat at joint locations and clean & overcoat all other steel

Note: Pull-off test required for overcoat (Calcium Sulfonate) option. Bridge Division will request pull-off tests.

* Notes: **Rust areas on top and bottom flanges.**

Picture **DSCN2380, DSCN2379**
#

SUPERSTRUCTURE REPAIRS (Repairs needed not previously stated.)**Concrete Slab Superstructure or Girder:** (above the bearings)**Steel I-beam**(Example: Deck solid slabs, voided slabs, box girders,
deck girders & prestressed girders)**Steel:** (Example: Beams, stringers, girders, diaphragms, cross-frames, misc. steel)**Member** (Check all that apply) (Attach pictures)**Describe & Locate****4** ☐ Section Loss _____ % ☐ Cracks _____ in. _____**3** ☐ Section Loss _____ % ☐ Cracks _____ in. _____**2** ☐ Section Loss _____ % ☐ Cracks _____ in. _____**1** ☐ Section Loss _____ % ☐ Cracks _____ in. _____**Notes:** **No issues noticed****Picture**

#

SUBSTRUCTURE REPAIR

Bent	Formed Repair	Unformed Repair	Seal Concrete Beam Cap Bts.	Coat Exposed Pile @ Int. Pile Cap Bts.	Describe (Beam, Backwall, Wing, etc.)
4	_____ sq. ft.	_____ sq. ft.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	_____
3	_____ sq. ft.	_____ sq. ft.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	_____
2	_____ sq. ft.	_____ sq. ft.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	_____
1	_____ sq. ft.	_____ sq. ft.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	_____
	_____ sq. ft.	_____ sq. ft.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	_____

* Does the structure need graffiti protection? ☒ No ☐ Bottom 8' of Concrete ☐ End Bents ☐ Other _____* Notes: **No repair needed.****Picture**

#

11

SIGNS, SIGNALS &/OR LIGHTING ATTACHED TO STRUCTURE

* Are there signs attached directly to this structure? ☐ Yes ☒ No quantity _____ location _____

* Describe proposed work to be done to signs. _____

* Are there signals attached directly to this structure? ☐ Yes ☒ No quantity _____ location _____

* Describe proposed work to be done to signals. _____

* Is there aviation lighting attached to this structure? ☐ Yes ☐ No ☒ N/A ☐ Red _____ ☐ Green _____
qnty. qnty.

* Is there navigational lighting attached to this structure? ☐ Yes ☐ No ☒ N/A ☐ Red _____ ☐ Green _____
qnty. qnty.

* Is there roadway lighting attached to this structure? ☐ Yes ☐ No ☒ N/A

* Describe proposed work to be done to lighting. _____

* Notes: _____

Picture
#

12

UTILITIES ATTACHED TO STRUCTURE

Type	Qty.	Size	Owner	Condition
<input type="checkbox"/> Conduit <input type="checkbox"/> Pipeline <input type="checkbox"/> Other	_____	_____	_____	<input type="checkbox"/> Repaint <input type="checkbox"/> Repair <input type="checkbox"/> Replace <input type="checkbox"/> Remove
<input type="checkbox"/> Conduit <input type="checkbox"/> Pipeline <input type="checkbox"/> Other	_____	_____	_____	<input type="checkbox"/> Repaint <input type="checkbox"/> Repair <input type="checkbox"/> Replace <input type="checkbox"/> Remove
<input type="checkbox"/> Conduit <input type="checkbox"/> Pipeline <input type="checkbox"/> Other	_____	_____	_____	<input type="checkbox"/> Repaint <input type="checkbox"/> Repair <input type="checkbox"/> Replace <input type="checkbox"/> Remove
<input type="checkbox"/> Conduit <input type="checkbox"/> Pipeline <input type="checkbox"/> Other	_____	_____	_____	<input type="checkbox"/> Repaint <input type="checkbox"/> Repair <input type="checkbox"/> Replace <input type="checkbox"/> Remove

* Notes: **No utilities attached to bridge**

Picture
#

13

CATHODIC PROTECTION SYSTEM

* Is there a cathodic system on this structure? ☐ Yes ☒ No ☐ Remove ☐ Do not alter ☐ Abandon in place (grooved system)

* Is it on and working? ☐ Yes ☐ No ☐ Unknown _____

* Notes: _____

Picture

#

14

CHANNEL ALIGNMENT, SLOPE PROTECTION & SCOUR

* Is channel aligned to bridge opening? ☒ Yes ☐ No Describe _____

* Is drift a continual problem? ☐ Yes ☒ No Describe & Locate _____

* Is erosion a problem? ☒ Yes ☐ No Describe & Locate Along edge drip line

* Describe slope protection in place. _____

Scour	At Footing	At Piling	Depth	Bent	Recommendation
	<input type="checkbox"/>	<input type="checkbox"/>	_____	_____	_____
	<input type="checkbox"/>	<input type="checkbox"/>	_____	_____	_____

* Describe needed work. Add rip-rap along the edge drip line.

Picture

#

DSCN2372, DSCN2373, DSCN2374, DSCN2383, DSCN2385,

15

TRAFFIC LANES

* Number of lanes striped: on structure 2 under structure N/A

* Shoulder width: ☒ None on structure _____ (left) _____ (right) under structure _____ (left) _____ (right)

* Sidewalk widths: on structure _____ (left) _____ (right) under structure _____ (left) _____ (right)

* Median width: on structure _____ under structure _____

* Proposed improvements for lanes/shoulders/sidewalks: _____

Picture

#

16

GENERAL AREA CONDITIONS

* Primary area: ☐ Commercial ☐ Industrial ☐ Residential ☒ Agricultural ☐ Military ☐ Other _____

* Posted speed limit on structure: N/A mph

* Posted load on structure: _____ tons @ _____ mph ☒ NA

Single Unit: _____ tons @ _____ mph ☒ NA

Semi (tractor/trailer): _____ tons @ _____ mph ☒ NA

* Are both signs in place?

☐ Yes ☐ No

* Do pedestrians and/or bicyclists regularly use this structure? ☐ Yes ☒ No ☐ Undetermined

* Notes: No load posting observed.

Picture
#

17

MAINTENANCE

* What work has been done to this structure that may not be reflected on existing bridge plans? _____

Picture
#

18

ADDITIONAL FIELD NOTES

Picture
#

19

STAGING / DETOUR

* **Traffic Control:** ☒ Close structure ☐ Stage construction on structure ☐ Cross over traffic to adjacent structure ☒ Detour

☐ Other option _____

* **Define probable detour route.** _____

20

PERSONS ASSISTING WITH CHECKLIST

Name Joyce Reynolds Title Project Manager Ph. (816) -387 - -2411

Name Shannon Kusilek Title District Design Engineer Ph. (816) 387 - 2441

Name _____ Title _____ Ph. () -

Name _____ Title _____ Ph. () -

Name _____ Title _____ Ph. () -

21

REQUIRED SIGNATURES

I have reviewed the information on this checklist and believe it to be as accurate as possible.

Name Joyce Reynolds Date 12/2/2022
Transportation Project Manager

Name Bryce Acton Date 12/2/2022
District Bridge Engineer

The structural rehabilitation checklist indicates how the bridge is functioning and aging.

All deterioration should be noted, even if it is known that the work will not be completed under the proposed project.

Send **NEW** Structural Rehabilitation Checklist by email

To: "Bridge Survey Processor"

Cc: Structural Project Manager or Structural Resource Manager