

# **ADDENDUM # 1**

Ralls County Bridge Replacement

BRO-R087(23)

Bridge #2410023 1

4/25/2025

You may reach the office of Hutchison Engineering, Inc. at (573) 240-9577 or via email at [kharris@hutchisoneng.com](mailto:kharris@hutchisoneng.com) to order plans and specifications.

Please utilize the attached revised plans for bidding purposes.

Please utilize the attached revised bidding form for bidding purposes.

**Please acknowledge receipt of Addendum #1 in your bid.**

## BIDDING FORM (ADDENDUM #1)

(work to be completed by contractor only)

RALLS COUNTY BRIDGE REPLACEMENT  
FEDERAL PROJECT BRO-R087(23)  
BRIDGE NO. 2410023 1  
92' - 3" SINGLE SPAN STEEL I-GIRDER BRIDGE  
HUTCHISON LANE

### ROADWAY

---

ITEM NO.	ITEM	UNITS	QTY	UNIT PRICE	AMOUNT
201-99.01	CLEARING AND GRUBBING	L.S.	1		
203-50.00	UNCLASSIFIED EXCAVATION	C.Y.	815		
203-55.00	EMBANKMENT IN PLACE	C.Y.	2,250		
203-60.00	COMPACTING EMBANKMENT	C.Y.	735		
304-05.04	TYPE 5 AGGREGATE FOR BASE (4" THICK SURFACE)	S.Y.	1,330		
606-10.10	GUARDRAIL TYPE A	L.F.	68.75		
606-23.00A	GUARDRAIL TRANSITION SECTION	EACH	2		
606-30.00A	GUARDRAIL TERMINAL SECTION	EACH	2		
609-60.20	FURNISHING TYPE 2 ROCK DITCH LINER	C.Y.	130		
609-60.42	PLACING TYPE 2 ROCK DITCH LINER	C.Y.	130		
611-30.20	FURNISHING TYPE 2 ROCK BLANKET	C.Y.	830		
611-30.40	PLACING TYPE 2 ROCK BLANKET	C.Y.	830		
616-10.05	CONSTRUCTION SIGNS	S.F.	45		
616-10.30	TYPE III TEMPORARY BARRICADES	EACH	2		
618-10.00	MOBILIZATION	L.S.	1		
624-1.04A	SEPARATION GEOTEXTILE CONTRACTOR FURNISHED	S.Y.	1,240		
627-40.00	SURVEYING AND STAKING	L.S.	1		
805-20.00A	SEEDING - COOL SEASON MIXTURES	ACRE	1.5		
806-10.19	SILT FENCE	L.F.	665		
				SUBTOTAL (ROADWAY):	

**BRIDGE**

ITEM NO.	ITEM	UNITS	QTY	UNIT PRICE	AMOUNT
203-50.00	CLASS 1 EXCAVATION	C.Y.	125		
216-05.00	REMOVAL OF BRIDGES	L.S.	1		
606-10.10	BRIDGE GUARDRAIL (THRIE BEAM)	L.F.	237.5		
606-99.02	BRIDGE RAIL END SHOE	EACH	2		
702-10.10	STRUCTURAL STEEL PILES (10 INCH)	L.F.	216		
702-60.00	PREBORE FOR PILING	L.F.	20		
702-60.00	PREBORE FOR PILING IN ROCK	L.F.	73		
702-70.00	PILE POINT REINFORCEMENT	EACH	12		
703-42.01	CLASS B-1 CONCRETE (4000 psi)	C.Y.	23		
703-42.12	SLAB ON STEEL	S.Y.	270		
712-10.10	W36x210 STEEL GIRDERS - GRADE 50W (90'-9 1/2")	EACH	4		
716-10.03	LAMINATED NEOPRENE BEARING (TAPERED)	EACH	8		
				SUBTOTAL (BRIDGE):	
				TOTAL:	

(PLEASE PRINT OR TYPE BID AMOUNT)

Contractor: \_\_\_\_\_

Representative: \_\_\_\_\_

(please print or type name and title along with signature of the individual that completed this bid)

Phone: \_\_\_\_\_

Address: \_\_\_\_\_

Fax: \_\_\_\_\_