

## RECEIPT OF ADDENDUM

I received Addendum 2, dated 7/28/2025 for:

City of Buffalo  
Buffalo Municipal Airport (H17) Security Fence Improvements

This addendum includes 3 pages including this sheet.

---

Contractor's Name

---

---

Contractor's Address

---

Signature / Date

**Return completed acknowledgement to: Toth and Associates, Inc.**

**FAX NO.: 417-888-0657**  
**Attention: Radu Mariuta, P.E.**

**OR EMAIL TO**  
**rmariuta@tothassociates.com**

**ADDENDUM NO. 1**

**TO CONTRACT DOCUMENTS FOR:**

**Buffalo Municipal Airport (H17) Security Fence Improvements**

**City of Buffalo  
Buffalo, MO**


**ENGINEER OF RECORD:  
TOTH AND ASSOCIATES, INC.  
1550 E. Republic Road  
Springfield, Missouri 65804**

July 28, 2025

Bidders are hereby informed that the construction plans and/or specifications are modified as follows:  
The following changes, corrections, additions, information and clarification of the Contract Documents are hereby made a part of the Contract Documents. Acknowledgement of receipt of this Addendum is required as part of this Contract.

---

SEAL



---

**RADU M. MARIUTA – PROFESSIONAL ENGINEER  
MO # PE-2021028075**

**CIVIL ENGINEER OF RECORD**

Toth and Associates, Inc  
1550 E. Republic Road, Springfield, MO 65804  
417-888-0645  
Missouri State Certificate of Authority # 2004004242

## **GENERAL CLARIFICATIONS:**

### **1. Electrical power to gates:**

*Per the language in Specification MO-162 Chain-Link Fences, the intent of the contract is for all electrical work to be provided by the contractor as part of the project.*

- *Cantilevered motorized gates shall include the gate assembly, electric operator, keypad system for entry, automatic detection system for exiting, **and all electrical work required for a working system.***

*The notes on the site plan regarding coordination of the electrical utilities are intended for coordination of the connection point to power for the gates, not indication that the owner will be bringing power to them.*

*Please include the cost of getting power to the gates in the line items:*

***Item MO-162 Motorized Cantilever Security Sliding Gate (6ft) -- per each***

***Item MO-162 Motorized Cantilever Security Sliding Gate (8ft) -- per each***

### **2. Patching of Pavement:**

- Contractor to include any pavement patching that may be required for the electrical work in the pricing of the gates.

### **3. Grounding**

- Per specification 162-3.9, grounding for the project shall be installed every 500 feet and at points where power lines cross the fence.

### **4. Staking**

- Per specification 50-06, construction staking is to be performed by the contractor at their expense. Include this cost in the line items for the fencing. Toth and associates can provide a quote for this work if requested.

**END OF ADDENDUM 02**