

**AGENDA**  
**Wayne County, U.S. 67**  
**Call 250919\_H02 Job No. JSE0083**  
**Virtual Pre-bid Meeting**  
**August 29, 2025**

- **INTRODUCTIONS**

- Please add your name, organization, and title to the chat
- The meeting is being recorded

- **PROJECT OVERVIEW**

- Scope of Project: Replace NB Route 67 Bridge L0210 over Otter Creek near approx. ½ mile south of Wayne County Road 546.
- Construct a permanent bypass on SB Route 67.
- Bridge Overview
- Roadway Overview
- Contract will be administered by Poplar Bluff Project Office, Matt Wilkerson R.E.

- **Schedule**

- Letting – September 19, 2025
- Commission Meeting Award – October 1, 2025
- Notice to Proceed – October 16, 2025 (**earlier than standard NTP**)
- Completion Date Dec 1, 2026
- Calendar Days 276

- **Construction Staging**

- Obtain approved Borrow. (**ASAP**)
- Construct Bypass.
- Remove Structure Prior to March 15, 2026. (**Migratory Birds**)
- Construct Bridge and NB Tie-Ins
- Install Permanent Delineators on Permanent Cross-Over.

- **Utilities**

- No known utility conflicts or adjustments
- **Right of way status**
  - No Right of way required for project.
- **JOB SPECIAL PROVISIONS**
- Early Notice to Proceed.
  - Commission Award on October 1, 2025.
  - Early Notice to Proceed October 16, 2025.
  - Return Contract and Bond prior to or within 15 days of Commission award.
- Contract Liquidated Damages: \$1800/day administrative damages
- Optional Pavements
  - NB 67 – 2” SP125C, 2”SP125C, 8” SP190C – A2 Shoulder
  - NB 67 – 9” PCCP – A2 Shoulder
  - Permanent Cross-Over - 2” SP125C, 2”SP125C, 8” SP190C
  - Permanent Cross-Over - 9” PCCP
- Restrictions for Migratory Birds
- Contractor Furnished Borrow
- Access to Private Properties.
- **CONTRACTOR QUESTIONS?**