

February 16, 2026

RE: Notice to Bidders
Project Name: Manchester Road Pedestrian Improvements STP-5504(604)
Addendum Number 02

This addendum is issued to provide revisions to the Specifications, Plans, and Bid form as well as additional information. All bidders are encouraged to carefully review and incorporate the information provided herein into their bid proposals:

1. Revised Specifications:

Job Special Provision: JSP H. Liquidated Damages for Winter Months LPA-15-09A shall be replaced in its entirety with the following:

H. Liquidated Damages for Winter Months LPA-15-09A

Delete Section 108.7.1.3(1).

Liquidated damages for failure to complete the work within the contract time shall not be waived from December 15 to March 15, both dates inclusive.

2. Revised Plans:

Revised plans have been attached as part of this addendum. Bidders are advised to review these revised documents carefully and incorporate them into their bid.

- C2-A.1 – Summary of Quantities

3. Revised Forms:

The following document has been attached as part of this addendum and shall be included in your bid submission:

- Revised Bid Form

4. Additional information:

- Manchester Road Pedestrian Improvements_Prebid Meeting Sign-in Sheet (Attachment)
- Pre-Bid Meeting Summary (Attachment)

Conclusion:

Prospective bidders are advised to thoroughly review all documents, including this addendum, before submitting their bids. Failure to incorporate the clarifications and updated information into your bid submission may result in disqualification.



=====

ACKNOWLEDGEMENT
ADDENDUM NO. 2

(Please Sign and Include with Bid)

Addendum Received By: _____ Date _____
(Signature of Authorized Representative)

Name: _____ Title: _____
(Printed Name of Authorized Representative)

=====

ITEMIZED BID: The bidder should complete the following section in accordance with Sec 102.7. The bidder proposes to furnish all labor, materials, equipment, services, etc. required for the performance and completion of the work, as follows:

MANCHESTER ROAD PEDESTRIAN IMPROVEMENTS - BAXTER ROAD TO HWY 141						
LINE NO.	ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
ROADWAY ITEMS:						
001	2022010	REMOVAL OF IMPROVEMENTS	LS	1		
002	3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	SY	3250		
003	3040508	TYPE 5 AGGREGATE FOR BASE (8 IN. THICK)	SY	1188		
004	4011209	BITUMINOUS PAVEMENT MIXTURE PG64-22, (BP-1)	TON	257		
005	4071005	TACK COAT	GAL	60		
006	5021108	CONCRETE PAVEMENT (8 IN. NON-REINF)	SY	784		
007	5029905	CONCRETE PAVEMENT (8 IN. NON-REINF), HIGH EARLY STRENGTH	SY	184		
008	6042010	ADJUSTING MANHOLE	EACH	10		
009	6042020	ADJUSTING BASIN OR INLET	EACH	4		
010	6085008	PAVED APPROACH, 8 IN.	SY	710		
011	6089905	PAVED APPROACH, 8 IN., HIGH EARLY STRENGTH	SY	1166		
012	6091010	CONCRETE CURB (6 IN. HEIGHT AND UNDER) TYPE S	LF	651		
013	6091051	CURB AND GUTTER TYPE A	LF	253		
014	6091052	CURB AND GUTTER TYPE B	LF	294		
015	6092011	INTEGRAL CURB (6 IN. HEIGHT AND UNDER) TYPE A	LF	1165		
016	6092012	INTEGRAL CURB (OVER 6 IN. HEIGHT) TYPE A	LF	46		
017	6099903	MODIFIED CONCRETE CURB (OVER 6 IN. HEIGHT) TYPE S	LF	135		
018	6099904	GUTTER TYPE B (MODIFIED)	LF	15		
019	6149901	PRECAST INLET TOP	EACH	1		
020	6149902	ADA COMPLIANT GRATE INLET TOP	EACH	1		
021	6149903	6" PVC PERFORATED PIPE TRENCH DRAIN SYSTEM	LF	172		
022	6149904	IN-LINE TRENCH DRAIN CLEANOUT	EACH	2		
023	6161099	CHANGEABLE MESSAGE SIGN WITH COMMUNICATION INTERFACE, CONTRACTOR FURNISHED, CONTRACTOR RETAINED	EACH	2		
024	6169901	TEMPORARY TRAFFIC CONTROL	LS	1		
025	6169902	ADA COMPLIANT MOVABLE BARRICADE	EACH	8		
026	6181000	MOBILIZATION	LS	1		
027	6200014	PLURAL COMPONENT LIQUID PAVEMENT MARKING, 24 IN. WHITE	LF	24		
028	6200020	PLURAL COMPONENT LIQUID PAVEMENT MARKING, LEFT/RIGHT ARROW	EACH	3		

MANCHESTER ROAD PEDESTRIAN IMPROVEMENTS - BAXTER ROAD TO HWY 141						
LINE NO.	ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
029	6200023	PLURAL COMPONENT LIQUID PAVEMENT MARKING, STRAIGHT ARROW	EACH	18		
030	6200035	PLURAL COMPONENT LIQUID PAVEMENT MARKING, 30 IN WHITE MIDBLOCK	EACH	69		
031	6205902A	6 IN. WHITE HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT, TYPE L BEADS	LF	3299		
032	6206000C	4 IN. WHITE STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	LF	386		
033	6206001C	4 IN. YELLOW STANDARD WATERBORNE PAVEMENT MARKING PAINT, TYPE P BEADS	LF	102		
034	6207001	PAVEMENT MARKING REMOVAL	LF	587		
035	6274000	CONTRACTOR FURNISHED SURVEYING AND STAKING	LS	1		
036	7209904	MODULAR BLOCK RETAINING WALL	SF	683		
037	7269902	CONNECTION TO EXISTING STRUCTURE	EACH	1		
038	80610007A	CURB INLET CHECK	EACH	42		
039	8061020	SILT FENCE	LF	470		
PEDESTRIAN FACILITIES:						
040	2061000	CLASS 1 EXCAVATION	CY	135		
041	2035500	EMBANKMENT IN PLACE	CY	650		
042	2036000	COMPACTING EMBANKMENT	CY	20		
043	2079909	LINEAR GRADING, CLASS 2 (MODIFIED)	STA	54.6		
044	3040504	TYPE 5 AGGREGATE FOR BASE (4 IN. THICK)	SY	3498		
045	6081000	CONCRETE MEDIAN	SY	9.1		
046	6081010	CONCRETE CURB RAMP	SY	323.3		
047	6081012	TRUNCATED DOMES	SF	251		
048	6086004	CONCRETE SIDEWALK, 4 IN.	SY	2855.4		
049	6086008	CONCRETE SIDEWALK, 8 IN.	SY	269.8		
050	6089902	ISLAND TUBULAR MARKERS	EACH	6		
051	6089906	CONCRETE SIDEWALK, 5 IN.	SY	49.7		
052	6113020	FURNISHING TYPE 2 ROCK BLANKET	CY	150		
053	6113040	PLACING TYPE 2 ROCK BLANKET	CY	150		
054	6209902	CURB REFLECTOR	EACH	12		
055	7021212	GALVANIZED STRUCTURAL STEEL PILES (12 IN)	LF	135		
056	7032003	CLASS B CONCRETE (SUBSTRUCTURE)	CY	11.4		
057	7129999	PREFABRICATED STEEL BRIDGE TRUSS	LS	1		
058	7151001	VERTICAL DRAIN AT END BENTS	EACH	2		

MANCHESTER ROAD PEDESTRIAN IMPROVEMENTS - BAXTER ROAD TO HWY 141						
LINE NO.	ITEM NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
LANDSCAPE/STREETSCAPING ITEMS:						
059	5029901	REMOVE AND RESET EXISTING PAVERS	SF	466		
060	6089907	BENCHES	EACH	2		
061	8031000A	TURF TYPE TALL FESCUE SODDING	SY	1961		
062	8089927	LANDSCAPE MULCH	CY	16		
063	8089929	LANDSCAPE ROCK	CY	5		
064	9019902	REMOVE AND RELOCATE LIGHTING FIXTURE (INCL. FOUNDATION)	EACH	2		
065	9031241	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	EACH	9		
066	9031270A	2 IN. PSST POST - 12 GA.	LF	113		
TRAFFIC SIGNALS:						
067	9025300	CONDUIT, 3" TRENCH W/ TRACE WIRE	EACH	37		
068	9022708	SIGNAL POST, 8 FT.	EACH	3		
069	9028308	CABLE, 16 AWG 2 CONDUCTOR	LF	552		
070	9028310	CABLE, 16 AWG 5 CONDUCTOR	LF	557		
071	9028812	PULL BOX, PREFORMED CLASS 3	LF	1		
072	9029100	BASE, CONCRETE	LF	1.4		
073	9029901	TRAFFIC SIGNAL MAINTENANCE AND PROGRAMMING	EACH	1		
074	9029902	REMOVAL OF EXISTING CONCRETE SIGNAL BASE	EACH	6		
075	9029904	AUDIBLE PEDESTRIAN PUSHBUTTON AND SIGNING WITH VERBAL WALK MESSAGE	EACH	5		
076	9029905	COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 1S	EACH	1		
077	9029906	COUNTDOWN PEDESTRIAN SIGNAL HEAD, TYPE 11S	EACH	2		
078	9029908	PULL BOX, ADJUST TO GRADE	EACH	4		
079	9029909	DRILL PULL BOX AND ADJUST TO GRADE	EACH	2		
080	9029910	RECONFIGURATION OF VIDEO DETECTION ZONES	EACH	2		
081	9108352	FIBER OPTIC CABLE, 24 - STRAND, 18 SINGLE MODE, 6 MULTIMODE	LF	500		
082	9109902	ITS PULL BOX, ADJUST TO GRADE	EACH	2		
081	9109903	MODOT ITS ASSETS RELOCATION	LF	500		
TOTAL			NUMBERS:			
TOTAL			WRITTEN:			

Pre-Bid Meeting Summary – Manchester Road Pedestrian Improvements STP-5504(604)

The following items were discussed during the pre-bid meeting:

Project Scope

- Pedestrian improvements along Manchester Road from Route 141 to Baxter Road.
- Work includes:
 - Replacement of existing sidewalk on the south side of Manchester Road
 - Construction of new sidewalk on the north side
 - Construction of a pedestrian bridge over Grand Glaize Creek

Project Rebid

- The project was previously bid in Fall 2024.
- The City rejected the prior bids and is re-bidding the project with revisions.

Maintenance of Traffic / Work Hours

- Contractor feedback from the prior bid identified nighttime work requirements as a major concern.
- The City coordinated with MoDOT to allow approximately 70% of the project to be constructed under daytime lane closures.
- Westbound Manchester Road from Route 141 to Henry Avenue will still require nighttime lane closures only.

Plan and Specification Revisions

- Removal of improvements has been more clearly itemized to better define the work.
- Permeable concrete sidewalk has been replaced with standard concrete sidewalk.
- Some pavement striping on the south side of Manchester Road has been eliminated.

Minor plan adjustments and clarifications have also been incorporated. Bidders shall review the revised plan set in its entirety.

Contract Time

- The project will have a calendar date completion of December 31, 2026.