

ADDENDUM NO. 1

Project: Green Pines Trail Extension

Federal Aid Project Number: TAP-5500(692)

Project Sponsor: City of Wildwood, MO

Date of Issuance: October 6, 2026

To: All Holders of Plans and Contract Documents for TAP-5500(692) – Green Pines Trail Extension, City of Wildwood, MO

Notice to Planholders: This Addendum No. 1 is hereby made a part of the Project Contract Documents to the same extent as if it were originally included herein. This Addendum No. 1 shall be inserted into the Contract Documents and submitted with the Bid. This Addendum No. 1 modifies the Contract Documents as follows:

Plan Sheet 2 of 26 shall be modified to change the 2” Type “C” Bituminous Concrete (Pavement) or Superpave Total to 177.0 Tons. The updated plan sheet 2 of 26 is included with this Addendum No. 1.

Bid Book Itemized Bid Form shall be modified to change the 2” Type “C” Bituminous Concrete (Pavement) or Superpave Total to 177.0 Tons. The updated Itemized Bid Form is included with this Addendum No. 1.

Addendum Acknowledgement: All prospective bidders must acknowledge this Addendum No. 1 in the “Notice to Contractors” Sections 13-14 on page 5 of the Project Construction Manual. Failure to properly acknowledge this Addendum No. 1 and include with the Contractor’s Bid will result in a non-responsive bid.

All questions related to this Addendum No. 1 shall be directed to:

Brendan Maher, Project Manager
City of Wildwood, MO
16860 Main Street
Wildwood, MO 63040
636-405-2043

Attachments (2)

5/19/2026 8:26:10 AM \\hrgreen.com\hrc\Draw\2024\2402168\CAD\Roadway\Plan_Sheets\002_Quantities_2402168.dgn

REMOVAL OF IMPROVEMENTS (201-20.20) *							
SHEET	ROUTE	STATION	STATION	LOCATION	DESCRIPTION	QUANTITY	UNIT
PL 1	GREEN PINES PARK CONNECTING TRAIL	2+53.36	2+55.84	LT / RT	4" CORRUGATED PLASTIC PIPE	1	EACH
1 LUMP SUM (TABLE SHOWN FOR INFORMATION ONLY)							

* FOR INFORMATION ONLY. NOT GUARANTEED TO BE A COMPLETE LIST OF ITEMS REQUIRED TO BE REMOVED FOR THIS PROJECT. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL REMOVALS, WHETHER SPECIFICALLY MENTIONED OR NOT.

TRAFFIC CONTROL (1)						
SHEET	ROUTE	STATION	OFFSET	612-30.15 MOVEABLE BARRICADE (2) (EACH)	612-30.15 TEMPORARY TRAFFIC SIGNS (2) (EACH)	REMARKS
PL 1	GREEN PINES PARK CONNECTING TRAIL	0+38.25	0	1		
PL 1	GREEN PINES PARK CONNECTING TRAIL	0+38.25	0		1	"SIDEWALK CLOSED" R9-9
PL 3	GREEN PINES PARK CONNECTING TRAIL	14+13.13	0	1		"SIDEWALK CLOSED" R9-9
PL 3	GREEN PINES PARK CONNECTING TRAIL	14+13.13	0		1	

(1) FOR INFORMATION ONLY. THERE WILL BE NO DIRECT PAY FOR TRAFFIC CONTROL ITEMS. ALL SIGNS, DEVICES, MARKINGS, REMOVALS SHALL BE INCIDENTAL TO THE LUMP SUM PAY ITEM "TEMPORARY TRAFFIC CONTROL (ALL INCLUSIVE)".

(2) SEE PLAN SHEETS FOR TRAFFIC CONTROL ITEM LOCATIONS.

DRAINAGE STRUCTURES					
SHEET	STATION	OFFSET	ROUTE	LOCATION	604-18.08 8-GRATE INLET, UNTRAPPED (EACH)
PL 3	11+00.00	17.82	GREEN PINES PARK CONNECTING TRAIL	RT	1
SUBTOTAL =					1
PAY TOTAL =					1

ADJUSTMENTS					
SHEET	ROUTE	STATION	OFFSET	LOCATION	604-20.30 ADJUSTING MANHOLE TO GRADE (EACH)
PL 3	GREEN PINES PARK CONNECTING TRAIL	11+79.53	6.7	RT	1
PL 3	GREEN PINES PARK CONNECTING TRAIL	11+81.22	14.4	LT	1
PL 3	GREEN PINES PARK CONNECTING TRAIL	12+89.42	0.8	LT	1
PAY TOTALS =					3

PAVEMENT							
SHEET	ROUTE	START STATION	END STATION	LOCATION	304-05.04 TYPE 5 AGGREGATE BASE (4" THICK) (S.Y.)	405-30.30 4" TYPE "X" BITUMINOUS CONCRETE (BASE) (TON)	405-30.10 2" TYPE "C" BITUMINOUS CONCRETE (PAVEMENT) OR SUPERPAVE (TON)
PL 1	GREEN PINES PARK CONNECTING TRAIL	0+39.83	4+50.00	LT / RT	458.2		
PL 1	GREEN PINES PARK CONNECTING TRAIL	0+39.83	4+50.00	LT / RT		110.0	
PL 1	GREEN PINES PARK CONNECTING TRAIL	0+39.83	4+50.00	LT / RT			55.0
PL 2	GREEN PINES PARK CONNECTING TRAIL	4+50.00	9+50.00	LT / RT	555.6		
PL 2	GREEN PINES PARK CONNECTING TRAIL	4+50.00	9+50.00	LT / RT		133.3	
PL 2	GREEN PINES PARK CONNECTING TRAIL	4+50.00	9+50.00	LT / RT			66.7
PL 3	GREEN PINES PARK CONNECTING TRAIL	9+50.00	14+11.12	LT / RT	460.5		
PL 3	GREEN PINES PARK CONNECTING TRAIL	9+50.00	14+11.12	LT / RT		110.5	
PL 3	GREEN PINES PARK CONNECTING TRAIL	9+50.00	14+11.12	LT / RT			-460.5- 55.3
PAY TOTALS (PARTICIPATING) =					1474.3	353.8	-582.2- 177.0
TOTALS =					1474.3	353.8	-582.2- 177.0

REMOVAL OF IMPROVEMENTS = 1 LUMP SUM	201-20.20
MOBILIZATION = 1 LUMP SUM	619-00.00
CONTRACTOR FURNISHED SURVEYING AND STAKING* = 1 LUMP SUM	627-40.00
*BID ITEM SHALL CONFORM TO MODOT STANDARDS AND SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 2011	
CLEARING AND GRUBBING = 1 LUMP SUM	201-20.10
TEMPORARY TRAFFIC CONTROL (ALL INCLUSIVE) = 1 LUMP SUM	612-30.15
SITE RESTORATION (ROADWAY PROJECT) = 1 LUMP SUM	805-40.00

DRAINAGE PIPE CULVERTS				
SHEET	ROUTE	FROM STRUCTURE	TO STRUCTURE	726-13.12 12" CLASS III REINFORCED CONCRETE PIPE CULVERT (L.F.)
PL 3	GREEN PINES PARK CONNECTING TRAIL	PR SINGLE AREA INLET	23V2-299D	99.0
SUBTOTAL =				99.0
PAY TOTAL =				99

EARTHWORK		
ROUTE	203-50.50 UNCLASSIFIED EXCAVATION (C.Y.)	203-60.00 COMPACTING EMBANKMENT* (C.Y.)
GREEN PINES PARK CONNECTING TRAIL	835	530
PAY TOTALS =	835	530

NOTE: NO SHRINKAGE FACTOR APPLIED.

* NO DIRECT PAYMENT FOR THIS BID ITEM WILL BE MADE. TABULATION IS FOR INFORMATIONAL PURPOSES ONLY.

** QUANTITY OF UNCLASSIFIED EXCAVATION ESTIMATED

HRGREEN PROJECT NO.
2402168

FEDERAL PROJECT NO.
TAP-5500(692)

E-W GATEWAY TIP NO.
7824-25

MSD:
25MSD-00074

MSD BASE MAP:
23V

REVISIONS

REV	DATE	BY	APP	DESCRIPTION
1	06/26	DIS		REVISED ASPHALTIC CONCRETE QUANTITY

DISCLAIMER OF RESPONSIBILITY

I, the undersigned, hereby certify that the documents indicated to be authorized by my seal are limited to this sheet, and I am not responsible for any other drawings, specifications, estimates, reports or other documents prepared or used for any part of the engineering project or survey.

STATE OF MISSOURI

DANIEL T. SHANE

NUMBER E-29833

Professional Engineer

DATE: 5/19/2026

PREPARED BY:

HRGreen

1000 S. MAIN STREET, SUITE 100, ST. LOUIS, MO 63101

PH: 314.433.1000 FAX: 314.433.1001

PROFESSIONAL ENGINEER

LICENSE NO.

GREEN PINES PARK PATH CONNECTOR

SUMMARY OF QUANTITIES (SHEET 1 OF 2)

DESIGNED: NPARRIS

DRAWN: CGRONER

CHECKED: DSHANE

SHEET SEQUENCE: 2 OF 26

BRIDGE SHEET NO.: OF

NOTE: PAY ITEMS SHALL BE IN ACCORDANCE WITH ST. LOUIS COUNTY STANDARD SPECIFICATIONS FOR ROADS AND BRIDGES, 2024, UNLESS OTHERWISE NOTED

Contractor Name: _____

**GREEN PINES TRAIL EXTENSION
ITEMIZED BID FORM**

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	EXTENSION
ROADWAY ITEMS					
201-20.10	CLEARING AND GRUBBING	L.S.	1		
201-20.20	REMOVAL OF IMPROVEMENTS	L.S.	1		
203-50.50	UNCLASSIFIED EXCAVATION	C.Y.	835		
304-05.04	TYPE 5 AGGREGATE BASE (4" THICK)	(S.Y.)	1474		
405-30.30	4" TYPE "X" BITUMINOUS CONCRETE (BASE)	(TON)	354		
405-30.10	2" TYPE "C" BITUMINOUS CONCRETE (PAVEMENT) OR SUPERPAVE	(TON)	582 177		
604-20.30	ADJUSTING MANHOLE TO GRADE	EACH	3		
612-30.15	TRAFFIC CONTROL (ALL INCLUSIVE)	L.S.	1		
619-00.00	MOBILIZATION	L.S.	1		
627-40.00	CONTRACTOR FURNISHED SURVEYING AND STAKING	L.S.	1		
803-10.00	SODDING	S.Y.	3593		
805-40.00	SITE RESTORATION (ROADWAY PROJECT)	L.S.	1		
806-70.00	SILT FENCE	L.F.	3158		
806-30.01	ROCK DITCH CHECK	(EACH)	52		
806-10.16 (MoDOT)	SEDIMENT REMOVAL	(C.Y.)	85		
DRAINAGE ITEMS					
726-13.12	12" CLASS III REINFORCED CONCRETE PIPE CULVERT	(L.F.)	99		
604-18.08	8-GRATE INLET, UNTRAPPED	(EACH)	1		

TOTAL BID (BASE BID) NUMBERS:

TOTAL BID (BASE BID) WRITTEN:
